

Intended for  
**Buffalo Niagara Waterkeeper**

Document type  
**Report**

Date  
**January 2023**

***Feasibility & Design of  
Floodplain Reconnection  
of Buffalo Creek***

**RAMBOLL**

# Feasibility & Design of Floodplain Reconnection of Buffalo Creek

Project name **Feasibility & Design of Floodplain Reconnection of Buffalo Creek**

Project no. **1940102804**

Recipient **Buffalo Niagara Waterkeeper**

Document type **Report**

Version **2**

Date **January 6, 2023**

Prepared by **Kadir Goz**

Checked by **Shaun Gannon, P.E., D.WRE, P.H., CFM, PMP**

Approved by **Michelle McEntire, PE**

Ramboll  
Harro East Building  
400 Andrews Street, Suite 710  
Rochester, NY 14604  
USA

T 585-295-7700  
F 585-510-3023  
<https://ramboll.com>

## Contents

<b>1.</b>	<b>Introduction</b>	<b>5</b>
1.1	Background	5
1.2	Project Location	5
1.3	Flood History	6
1.4	Objectives	7
<b>2.</b>	<b>Methodology</b>	<b>8</b>
2.1	Model Data	8
2.2	Effective FIS model	8
2.3	Existing Conditions Model	9
2.4	Survey Data	10
2.5	Flood Bench Scenarios	11
2.6	Proposed Scenario Modeling	13
2.7	Ice-Jam Analysis	14
<b>3.</b>	<b>Results</b>	<b>15</b>
3.1	Effective FEMA and Existing Conditions Model Results	15
3.2	Proposed Conditions Model Results	17
3.3	Berm Impacts	27
3.4	Ice-Jam Simulation Results	29
3.5	Bank and Channel Stabilization Features	41
<b>4.</b>	<b>Summary</b>	<b>44</b>
<b>5.</b>	<b>Next Steps</b>	<b>47</b>
<b>6.</b>	<b>References</b>	<b>48</b>

## Attachments

- Attachment A: Project Site Maps
- Attachment B: Hydrologic & Hydraulic Modeling Technical Memorandum
- Attachment C: Field Notes
- Attachment D: Flood Bench Sectional View
- Attachment E: Canisius High School Development Project
- Attachment F: HEC-RAS Model Simulation Output
- Attachment G: Bank and Channel Stabilization Strategies
- Attachment H: Project Cost Estimate

## Table of Tables

Table 1. USGS <i>StreamStats</i> data for Buffalo Creek for the 10-, 2-, 1-, and 0.2- percent AEP events (10, 50, 100, and 500-year recurrence intervals).	8
Table 2. Summary table of proposed flood bench locations.	12
Table 3. Summary table of modeled flood bench scenarios.	13
Table 4. Results of the existing and proposed conditions models for the 10-, 2-, 1-, and 0.2- percent AEP events (10, 50, 100, and 500-year recurrence intervals).	17
Table 5. WSEL (feet NAVD88) differences for the existing and proposed conditions models in the vicinity of Lexington Green for the 1-percent AEP event.	27
Table 6. Berm and WSELs (feet NAVD88) along Lexington Green for the existing and proposed conditions models for the 1-percent AEP event.	29
Table 7. Results of the existing and proposed conditions models with ice-jams for the 10-, 2-, 1-, and 0.2- percent AEP events (10, 50, 100, and 500-year recurrence intervals).	31
Table 8. WSEL (feet NAVD88) differences between the existing and proposed conditions with ice-jam models in the vicinity of Lexington Green for the 10-percent AEP event.	31
Table 9. Bank and channel stabilization strategies along Buffalo Creek for the 1-percent AEP event.	43

## Table of Figures

Figure 1. Buffalo Creek in the vicinity of the Lexington Green neighborhood, West Seneca, NY.	6
Figure 2. FEMA Effective FIS model layout for Buffalo Creek.	9
Figure 3. Existing conditions model for Buffalo Creek.	10
Figure 4. Field survey locations along Buffalo Creek.	11
Figure 5. Map of Buffalo Creek and the proposed flood bench locations.	13
Figure 6. Example Cross-Section Depicting a Flood Bench.	14
Figure 7. Effective FEMA and existing conditions profile plot using the FEMA 1-percent AEP (100-year recurrence) event peak discharge.	15
Figure 8. Flood extents for the effective FEMA (blue) and existing condition (red) model simulation results using the FEMA 1-percent AEP (100-year recurrence) event peak discharge.	16
Figure 9. Scenario #1 - Flood extents for proposed conditions (blue) and existing condition (pink) model using the USGS <i>StreamStats</i> 1-percent AEP (100-year recurrence) event peak discharge.	18
Figure 10. Scenario #2 - Flood extents for proposed (blue) and existing conditions (pink) model using the USGS <i>StreamStats</i> 1-percent AEP (100-year recurrence) event peak discharge.	19
Figure 11. Scenario #3 - Flood extents for proposed (blue) and existing conditions (pink) model using the USGS <i>StreamStats</i> 1-percent AEP (100-year recurrence) event peak discharge.	20
Figure 12. Scenario #4 - Flood extents for proposed (blue) and existing conditions (pink) model using the USGS <i>StreamStats</i> 1-percent AEP (100-year recurrence) event peak discharge.	21
Figure 13. Scenario #5 - Flood extents for proposed (blue) and existing conditions (pink) model using the USGS <i>StreamStats</i> 1-percent AEP (100-year recurrence) event peak discharge.	22
Figure 14. Scenario #6 - Flood extents for proposed (blue) and existing conditions (pink) model using the USGS <i>StreamStats</i> 1-percent AEP (100-year recurrence) event peak discharge.	23
Figure 15. Scenario #7 - Flood extents for proposed (blue) and existing conditions (pink) model using the USGS <i>StreamStats</i> 1-percent AEP (100-year recurrence) event peak discharge.	24
Figure 16. Scenario #8 - Flood extents for proposed (blue) and existing conditions (pink) model using the USGS <i>StreamStats</i> 1-percent AEP (100-year recurrence) event peak discharge.	25
Figure 17. Scenario #9 - Flood extents for proposed (blue) and existing condition (pink) model using the USGS <i>StreamStats</i> 1-percent AEP (100-year recurrence) event peak discharge.	26
Figure 18. Flood extents for existing with berm (pink) and existing without berm (green) conditions models using the USGS StreamStats 1-percent AEP (100-year recurrence) event peak discharge.	28
Figure 19. Flood extents for the existing conditions model under open-water (blue) and ice-jam (pink) conditions models using the USGS <i>StreamStats</i> 10-percent AEP (10-year recurrence) event peak discharge.	30

Figure 20. Scenario #1 - Flood extents for proposed (blue) and existing condition (pink) with ice-jam models using the USGS <i>StreamStats</i> 10-percent AEP (10-year recurrence) event peak discharge.	32
Figure 21. Scenario #2 - Flood extents for proposed (blue) and existing condition (pink) with ice-jam models using the USGS <i>StreamStats</i> 10-percent AEP (10-year recurrence) event peak discharge.	33
Figure 22. Scenario #3 - Flood extents for proposed (blue) and existing condition (pink) with ice-jam models using the USGS <i>StreamStats</i> 10-percent AEP (10-year recurrence) event peak discharge.	34
Figure 23. Scenario #4 - Flood extents for proposed (blue) and existing condition (pink) with ice-jam models using the USGS <i>StreamStats</i> 10-percent AEP (10-year recurrence) event peak discharge.	35
Figure 24. Scenario #5 - Flood extents for proposed (blue) and existing condition (pink) with ice-jam models using the USGS <i>StreamStats</i> 10-percent AEP (10-year recurrence) event peak discharge.	36
Figure 25. Scenario #6 - Flood extents for proposed (blue) and existing condition (pink) with ice-jam models using the USGS <i>StreamStats</i> 10-percent AEP (10-year recurrence) event peak discharge.	37
Figure 26. Scenario #7 - Flood extents for proposed (blue) and existing condition (pink) with ice-jam models using the USGS <i>StreamStats</i> 10-percent AEP (10-year recurrence) event peak discharge.	38
Figure 27. Scenario #8 - Flood extents for proposed (blue) and existing condition (pink) with ice-jam models using the USGS <i>StreamStats</i> 10-percent AEP (10-year recurrence) event peak discharge.	39
Figure 28. Scenario #9 - Flood extents for proposed (blue) and existing condition (pink) with ice-jam models using the USGS <i>StreamStats</i> 10-percent AEP (10-year recurrence) event peak discharge.	40
Figure 29. Flood bench locations and extent for Scenario #6.	45

## 1. Introduction

### 1.1 Background

Buffalo Niagara Waterkeeper (Waterkeeper) is a community-based, not-for-profit organization that leads regional efforts to safeguard water resources for present and future generations and connects people to the water through education, recreation, and preservation. Funding for this project was obtained through the National Fish and Wildlife Foundation's National Coastal Resilience Fund, which works to restore, increase and strengthen natural infrastructure to protect coastal communities while also enhancing habitats for fish and wildlife.

In November 2018, New York State Governor Andrew Cuomo announced the Resilient NY Initiative in response to devastating flooding in communities across the State during the preceding years. The Buffalo Creek watershed was chosen as one of the study sites for this initiative. Overseen by the New York State Department of Environmental Conservation (NYSDEC) and the New York State Office of General Services (NYSOGS), the Resilient NY Initiative identified the causes of flooding within the Buffalo Creek watershed and developed, evaluated, and recommended effective and ecologically sustainable flood and ice jam hazard mitigation projects.

Three high risk areas for flooding were identified in the final report *Resilient NY Flood Mitigation Initiative: Buffalo Creek* (2020), including the Lexington Green Neighborhood. One of the alternatives presented in the report was the creation of a floodplain bench upstream of the Lexington Green neighborhood. The creation of a floodplain bench would increase the width (*i.e.*, cross-sectional flow) of Buffalo Creek and add storage area during times of high flows thus alleviating flooding downstream. It is important to note that this report did not identify specific parcels on which to create the floodplain bench. It also did not identify parcel ownership, parcel conditions, or the willingness of the property owners to allow for construction of a floodplain bench on their land.

### 1.2 Project Location

This project is located along Buffalo Creek in the Town of West Seneca, NY (Town) upstream of the union with Cayuga Creek. The Town is located just outside of Buffalo, NY and covers an area of approximately 21 square miles. It is transected by nine (9) major highways, including the NY State Thruway, which makes it an ideal location for both residential and commercial development. The Town has experienced a long history of flooding damages and impacts associated with rapid snowmelt, heavy rainfall, and ice jams. Some of the largest of these impacts are cited as occurring along the Buffalo Creek corridor.

The Lexington Green neighborhood sits along a bend in Buffalo Creek approximately 0.7 miles upstream of its union with Cayuga Creek at the Harlem Road Bridge. Buffalo Creek runs along the north and east sides of the neighborhood over a length of approximately 0.45 miles. The neighborhood was developed in the mid-1960s on top of the former Buffalo Creek channel, which was filled with gravel and excavated materials from a sediment control project. Approximately 90 homes were built within the neighborhood, all of which are still occupied as of 2022. Attachment A displays the primary and secondary project locations in the Town of West Seneca, NY.



**Figure 1. Buffalo Creek in the vicinity of the Lexington Green neighborhood, West Seneca, NY.**

### 1.3 Flood History

Flooding along Buffalo Creek generally occurs in the late winter and early spring due to rapid snowmelt and spring rains. The situation is compounded by restrictive bridges, which cause ice jams along the stream channel. In addition, continued development in the floodplain exposes a greater numbers of assets to potential flood damages. Most major floods have historically occurred during the months of January to March.

Historically, the Lexington Green neighborhood has been susceptible to flooding, particularly ice jams in the late winter to early spring. In the winter of 2014, two significant flood events occurred within 6 weeks of each other causing a combined damage estimate of \$1.2 million (USACE 2016). These storms caused damage to over 70 homes and 2 dozen vehicles in the Lexington Green neighborhood. In the winter of 2019, a significant ice-jam flooding event caused the evacuation of the School Street Neighborhood. Most recently, in the winter of 2022, a severe flooding event caused emergency evacuations of several neighborhoods in the Town of West Seneca along Buffalo Creek.

The Federal Emergency Management Agency (FEMA) is responsible for flood studies and mapping in the United States. FEMA produces Flood Insurance Rate Maps (FIRMs), which are the official community maps that show special flood hazard areas (SFHAs) and the risk premium zones. For Buffalo Creek in the Town of West Seneca, NY, FIRMs were developed and updated in 2019. The current effective Flood Insurance Study (FIS) for Buffalo Creek is dated June 16, 2021. Attachment A displays the FEMA effective flood zones for Buffalo Creek in the project area.

#### **1.4 Objectives**

Ramboll was tasked with identifying opportunities for reconnecting Buffalo Creek to its floodplain to:

- Address reoccurring flooding
- Improve flood resiliency
- Develop preliminary designs of floodplain benches based on verified on-the-ground opportunities in the vicinity of the Lexington Green neighborhood.

During the last six months, Ramboll performed a preliminary analysis of the benefits of constructing flood benches along Buffalo Creek in the vicinity of the Lexington Green neighborhood. The purpose of this report is to provide a summary of the evaluated flood bench scenarios.

Based on historical flood reports and public engagement, it is understood that the Lexington Green neighborhood is susceptible to both open-water and ice-jam related flooding. A separate ice-jam analysis was performed for the flood bench alternatives to determine their effectiveness during ice-jam flooding events.

## 2. Methodology

### 2.1 Model Data

Attachment B is a technical memorandum describing the methodology used to evaluate each flood bench for this project in further detail. The following data were obtained and utilized for this project:

- FEMA peak discharges (FEMA 2021)
- USGS *StreamStats* peak discharges (USGS 2021)
- New York State Digital Ortho-Imagery Program imagery (NYSOITS 2021)
- National Land Cover Database (NLCD) data (USGS 2021)
- NYSDOT bridge data (NYSDOT 2019)
- New York State 1-meter LiDAR digital elevation model (DEM) data with vertical accuracy of 19.6-centimeters (7.7 inches) in the North American Vertical Datum of 1988 (NAVD88) (NYSOITS 2019)

To evaluate existing and proposed conditions along Buffalo Creek, it was necessary to obtain discharge data for the 10-, 2-, 1-, and 0.2- percent AEP (10, 50, 100, and 500-year recurrence) events. Hydrologic data was obtained from the USGS *StreamStats* software due to the limited available FEMA data for Buffalo Creek within the project area.

The USGS *StreamStats* v4.10.1 software is a map-based web application that provides an assortment of analytical tools. The primary purpose of *StreamStats* is to provide estimates of streamflow statistics for user-selected un-gaged sites and for USGS stream gages, which are locations where data is collected (Ries et al. 2017, USGS 2022). Table 1 displays the data obtained from *StreamStats* for Buffalo Creek at the union with Cayuga Creek.

**Table 1. USGS *StreamStats* data for Buffalo Creek for the 10-, 2-, 1-, and 0.2- percent AEP events (10, 50, 100, and 500-year recurrence intervals).**

Location	Drainage Area (sq miles)	River Station (ft)	Peak Discharges (cfs)			
			10-Percent	2-Percent	1-Percent	0.2-Percent
Union with Cayuga Creek	146	0+00	7,990	11,800	13,600	18,000

### 2.2 Effective FIS model

As part of its role, FEMA performs hydrologic & hydraulic (H&H) analyses and develops H&H models for each studied watershed within a community. These models are referred to as **effective FIS models**. The effective FIS model for Buffalo Creek was created using the United States Army Corps of Engineers (USACE) Hydrologic Engineering Center River Analysis System (HEC-RAS) program (USACE 2021).

According to the Flood Insurance Study (FIS) for Erie County, NY (2021), the effective FIS model for Buffalo Creek in the Town of West Seneca was completed by FEMA in 1976. It was then revised and updated in 1992. For this project, the effective FIS model was obtained for the project area, which begins at the union between Buffalo Creek and Cayuga Creek (river station 0+00) and extends upstream to the Buffalo Airfield (river station 205+00) (Figure 2). In Figure 2 below, the blue line represents the centerline of Buffalo Creek while the green lines represent the

cross-sections in the effective FIS model. Additionally, the numbered labels represent the distance (in feet) along the centerline upstream from the union of Buffalo and Cayuga Creeks.




Figure 2. FEMA Effective FIS model layout for Buffalo Creek.

### 2.3 Existing Conditions Model

Due to the age of the effective FIS model (first developed in 1976 and updated in 1992), most of the input data used by FEMA in the model is outdated and potentially inaccurate. For the purposes of this project, updates were made to the effective FIS model data, using the latest LiDAR digital elevation model (DEM) (2019) and land cover data (2019) to modify the geometry and values used for land cover (NYSOITS 2019; USGS 2021). This updated model is referred to as the *existing conditions model*.

Due to the water penetration limitations of the LiDAR technology, minimum channel elevations were maintained or modified to match the effective FIS model (1992) or FIS profile plot (2019).

In addition, 12 cross sections were added to the existing conditions model between river stations 36+50 and 80+00 to provide the necessary starting and ending positions for the different flood bench scenarios along the Lexington Green neighborhood. These new cross sections had their overland set to the DEM data and the minimum channel elevations were modified to match the minimum channel elevation from the effective FIS model profile plot. Figure 3 displays the existing conditions model layout for Buffalo Creek. The blue line represents the centerline of Buffalo Creek while the green lines represent the cross-sections in the existing conditions. Additionally, the numbered labels represent the distance (in feet) along the centerline upstream from the union of Buffalo and Cayuga Creeks.




Figure 3. Existing conditions model for Buffalo Creek.

#### 2.4 Survey Data

Field staff from Ramboll performed a site visit on November 2, 2022, where overbank and in-channel survey data and streambank assessments were performed. Four locations were surveyed due to their accessibility, close proximity to the Lexington Green neighborhood, and lack of adequate representation in the effective FIS model layout. Figure 4 displays the field survey locations along Buffalo Creek.



**Figure 4. Field survey locations along Buffalo Creek.**

Field surveys involved field staff using surveying and leveling equipment to measure land surface elevations perpendicularly across the creek channel from one overbank area to the other. In addition, stream bank assessments were performed at each location to identify the condition and locations of overbank zones (e.g., toe, bank, overbank, transitional, and upland zones).

This survey data was used to validate the overbank and channel elevations in the existing conditions model. In addition, survey data was incorporated into the existing conditions model where significant discrepancies were found. Attachment C contains the field notes from the field staff.

## 2.5 Flood Bench Scenarios

A flood bench (also referred to as a floodplain bench or bankfull bench) is a flat area adjacent to the stream at some specified elevation. Flood benches are constructed to create an area for flows to spread out, dissipate energy, and catch erosion. A flood bench is effective at reducing flood stages and velocities, improving water quality, reducing stream bank erosion, and providing stream bed stability. Attachment D contains a sectional plan view of a flood bench.


Potential flood bench locations were identified using input received from the public engagement meeting and contact with individual property owners. A public engagement meeting took place on August 22, 2022, where Ramboll discussed the project goals and potential property owner participation. Highland Planning, LLC (Highland) took the lead in contacting and engaging with property owners to gauge interest in being included in this project. Based on discussions and participation by the community and property owners, six potential flood bench configurations were identified along Buffalo Creek within the project area.

In addition, through public engagement and discussions with representatives of Canisius High School, it was identified that the school is in the process of constructing two baseball fields, a practice field, and tennis courts in the open area adjacent to Buffalo Creek. The site plans and drawings for this construction were provided to Ramboll and incorporated into the H&H model for Buffalo Creek. Attachment E contains the site plans for the development.

Table 2 summarizes the different identified flood bench locations with descriptions. Figure 5 displays the locations and extents of each flood bench, including the proposed development locations by the Canisius High School.

**Table 2. Summary table of proposed flood bench locations.**

Flood Bench ID	Description
<b>1a</b>	Western portion of the Canisius School tax parcel
<b>1b</b>	Western portion of the Canisius School tax parcel (outside of the proposed development area)
<b>2</b>	Western portion of the 1904 Union Rd tax parcel
<b>3</b>	Western portion of the 3099 Clinton Street tax parcel
<b>4</b>	Western portion of the Transmission Land (Right Bank) tax parcel
<b>5</b>	Western portion of the Transmission Land (Upstream – Left Bank) tax parcel
<b>6</b>	Western portion of the Transmission Land (Downstream - Left Bank) tax parcel



**Figure 5. Map of Buffalo Creek and the proposed flood bench locations.**


Based on the six identified flood bench locations, nine flood bench scenarios of different configurations were developed. Table 3 outlines the nine flood bench scenarios.

**Table 3. Summary table of modeled flood bench scenarios.**

Scenario ID	Flood Bench Configurations
1	1a
2	1b
3	1b + 2
4	2 & 3
5	1b + 2 + 3
6	2 + 3 + 4
7	1b + 2 + 3 + 4
8	5 + 6
9	1b + 2 + 3 + 4 + 5 + 6

## 2.6 Proposed Scenario Modeling

**Proposed conditions models** were developed for each flood bench configuration based on the existing conditions model. To model each flood bench scenario, terrain modifications were made to each cross section that intersected a proposed flood bench. Figure 6 displays an example cross section where the terrain was modified to represent a flood bench.



**Figure 6. Example Cross-Section Depicting a Flood Bench.**

## 2.7 Ice-Jam Analysis


An ice jam typically occurs in the late winter and early spring in ice-covered streams when ice accumulates at man-made (e.g., bridge piers, dams) or natural narrower or shallower sections or meanders of a river slowing down or blocking the incoming ice by bridging the ice across the width of the river. Ice-jam flooding presents a complex problem for scientists and engineers since the resulting flood stage can be significantly higher than the flood stage caused from streamflow alone. In other words, a relatively minor discharge of streamflow can result in a major flooding event during an ice jam (USACE 2006).

The ice jam analysis in this study used the 10% ACE (10-yr) to develop an **existing condition with ice cover model**. Ice-jam simulations were performed for each proposed conditions model using the built-in Ice Cover settings within the HEC-RAS model software. Based on historical ice jam data, ice cover lengths and depths were obtained and input into the model. For the ice-jam simulations, an ice cover of 1-ft thickness was used starting from the confluence with Cayuga Creek/Buffalo River (river station 0+00) upstream to the Union Road bridge (river station 118+60).

## 3. Results

### 3.1 Effective FEMA and Existing Conditions Model Results

Attachment F contains the model results for the effective FEMA and existing conditions models. Based on the modeling results, there is a difference in water surface elevations (WSELS) between the effective FIS model and the existing conditions model of up to 2.0-feet using the FEMA 1-percent AEP peak discharge. Figure 7 displays the profile plot of the effective FEMA and existing conditions model results.



**Figure 7. Effective FEMA and existing conditions profile plot using the FEMA 1-percent AEP (100-year recurrence) event peak discharge.**

The difference in water surface elevations (WSELS) between the effective FIS model and the existing conditions model are a result of multiple factors, including:

- Updated geometry using the most current LiDAR DEM available
- Updated values to represent land use changes over time in the watershed
- Additional cross-sections to provide more consistent and higher resolution calculations and results
- Difference in versions of the USACE HEC-RAS modeling used for the effective FIS and the existing conditions model.

Figure 8 displays the flood extents of the effective FIS model and the existing conditions model results using the FEMA 1-percent AEP event peak discharge.




Figure 8. Flood extents for the effective FEMA (blue) and existing condition (red) model simulation results using the FEMA 1-percent AEP (100-year recurrence) event peak discharge.

The largest difference between the effective FEMA and existing conditions model simulations results occurs downstream of the Oxbow and in the vicinity of the Lexington Green neighborhood. Since the development of the effective FIS a temporary protective berm was placed to help reduce the risk of flooding in the Lexington Green neighborhood.

For regulatory and insurance purposes, the berm along the Lexington green neighborhood is not recognized as an official levee since it does not meet the minimum design standards for providing safe, reliable flood protection. The minimum design standards include design height for the specified level of protection (e.g., 1% AEP/100-year level), overtopping criteria, top width, side slopes, seepage, and stability (i.e., foundation protection, erosion and scour protection, etc.). Therefore, it was considered in the developing the effective FIRM nor this study.

### 3.2 Proposed Conditions Model Results

Attachment F contains the results for the existing and proposed conditions models. The model results of each proposed flood bench scenario in comparison to the existing conditions model is summarized in Table 4.

**Table 4. Results of the existing and proposed conditions models for the 10-, 2-, 1-, and 0.2- percent AEP events (10, 50, 100, and 500-year recurrence intervals).**

Scenario ID	Flood Bench Configurations	Reductions in Water Surface Elevations (feet NAVD88)			
		10-Percent	2-Percent	1-Percent	0.2-Percent
1	1a	1.0	1.4	1.5	1.6
2	1b	0.4	0.6	0.6	0.6
3	1b + 2	0.8	1.2	1.3	1.3
4	2 + 3	1.4	1.6	1.6	1.6
5	1b + 2 + 3	1.4	1.6	1.6	1.6
6	2 + 3 + 4	1.5	2.0	2.2	2.4
7	1b + 2 + 3 + 4	1.5	2.0	2.2	2.5
8	5 + 6	0.6	0.7	0.7	0.7
9	1b + 2 + 3 + 4 + 5 + 6	1.6	2.2	2.4	2.8

Figures 9 through 17 display the flood extents from the proposed (blue) and existing (pink) conditions model for each flood bench using the USGS StreamStats 1-percent AEP (100-year recurrence) event peak discharge. Where the flood extents for both the proposed and existing conditions model overlap, the flood extents will appear as purple on the figures.



Figure 9. Scenario #1 - Flood extents for proposed conditions (blue) and existing condition (pink) model using the USGS StreamStats 1-percent AEP (100-year recurrence) event peak discharge.




Figure 10. Scenario #2 - Flood extents for proposed (blue) and existing conditions (pink) model using the USGS StreamStats 1-percent AEP (100-year recurrence) event peak discharge.




Figure 11. Scenario #3 - Flood extents for proposed (blue) and existing conditions (pink) model using the USGS StreamStats 1-percent AEP (100-year recurrence) event peak discharge.



Figure 12. Scenario #4 - Flood extents for proposed (blue) and existing conditions (pink) model using the USGS StreamStats 1-percent AEP (100-year recurrence) event peak discharge.



Figure 13. Scenario #5 - Flood extents for proposed (blue) and existing conditions (pink) model using the USGS StreamStats 1-percent AEP (100-year recurrence) event peak discharge.




Figure 14. Scenario #6 - Flood extents for proposed (blue) and existing conditions (pink) model using the USGS StreamStats 1-percent AEP (100-year recurrence) event peak discharge.



Figure 15. Scenario #7 - Flood extents for proposed (blue) and existing conditions (pink) model using the USGS StreamStats 1-percent AEP (100-year recurrence) event peak discharge.



**Figure 16. Scenario #8 - Flood extents for proposed (blue) and existing conditions (pink) model using the USGS *StreamStats* 1-percent AEP (100-year recurrence) event peak discharge.**



**Figure 17. Scenario #9 - Flood extents for proposed (blue) and existing condition (pink) model using the USGS *StreamStats* 1-percent AEP (100-year recurrence) event peak discharge.**

Table 5 summarizes the difference in WSELs between the existing and proposed conditions scenario model results for the 1-percent AEP event for the reach along the Lexington Green neighborhood (river stations 39+97 to 53+07). It should be noted positive values indicate the existing conditions WSELs are higher than the proposed scenario, while negative values indicate the existing conditions WSELs are lower than the proposed scenario. Results for events that occur more frequently (i.e., 10- and 2-percent) can be found in Attachment F.

**Table 5. WSEL (feet NAVD88) differences for the existing and proposed conditions models in the vicinity of Lexington Green for the 1-percent AEP event.**

	Water Surface Elevation (ft NAVD88)						
	RS 39+97	RS 41+82	RS 43+63	RS 45+82	RS 47+86	RS 50+51	RS 53+07
<b>Scenario #1</b>	-0.1	-0.2	-0.5	0	0.3	0.7	1.3
<b>Scenario #2</b>	0	0	-0.4	0	0	0	0.3
<b>Scenario #3</b>	0	0	-0.4	0	0	0	0.2
<b>Scenario #4</b>	0	0	0	0	0	0	-0.2
<b>Scenario #5</b>	0	0	-0.4	0	0	0	0.2
<b>Scenario #6</b>	0	0	0	0	0	0	-0.2
<b>Scenario #7</b>	0	0	-0.4	0	0	0	0.2
<b>Scenario #8</b>	0	0	0	0	0	0	-0.1
<b>Scenario #9</b>	0	0	-0.4	0	0	0	0.2

In the vicinity of the Lexington Green neighborhood, WSELs remain unchanged for most of flood bench scenarios across the majority of this reach. Scenario #1 displays the most significant benefits with WSEL reductions of up to 1.3-ft, primarily in the upstream portion of Lexington Green.

### 3.3 Berm Impacts

For regulatory and insurance purposes, the berm along the Lexington Green neighborhood is not recognized as an official levee since it does not meet the minimum design standards for providing safe, reliable flood protection. However, due to the existence of and flood mitigation impacts of the existing berm, the project team included the berm in the H&H analysis performed in this study. The berm elevation in the existing conditions model was set to 599.5-ft NAVD88 in line with the LiDAR DEM data. Figure 18 displays the flood extents for the existing conditions model simulation results with and without the berm.



Figure 18. Flood extents for existing with berm (pink) and existing without berm (green) conditions models using the USGS StreamStats 1-percent AEP (100-year recurrence) event peak discharge.

Table 6 summarizes the results for the 1-percent AEP event of the existing and proposed conditions modeling for the reach containing the berm along the Lexington Green neighborhood. Results for events that occur more frequently (i.e., 10- and 2-percent) can be found in Attachment F.

**Table 6. Berm and WSELs (feet NAVD88) along Lexington Green for the existing and proposed conditions models for the 1-percent AEP event.**

	Water Surface Elevation (ft NAVD88)		
	RS 45+82	RS 47+86	RS 50+51
<b>Berm Elevation (ft NAVD88)</b>	<b>599.5</b>	<b>599.5</b>	<b>600.5</b>
<b>Existing Conditions</b>	595.8	596.4	597.0
<b>Scenario #1</b>	595.8	596.1	596.3
<b>Scenario #2</b>	595.8	596.4	597.0
<b>Scenario #3</b>	595.8	596.4	597.0
<b>Scenario #4</b>	595.8	596.4	597.0
<b>Scenario #5</b>	595.8	596.4	597.0
<b>Scenario #6</b>	595.8	596.4	597.0
<b>Scenario #7</b>	595.8	596.4	597.0
<b>Scenario #8</b>	595.8	596.4	597.0
<b>Scenario #9</b>	595.8	596.4	597.0

Based on the model simulation results, only the flood bench Scenario #1 produced a reduction in WSELs in the vicinity of the berm. All of the other scenarios maintained the same WSEL as the existing conditions model.

It is important to note that since the berm was not built to USACE guidelines, the berm does not have the appropriate high-ground elevation tie-ins for the upstream and downstream ends of the berm. As a result, flood waters from high flow events can circumvent the berm causing flooding to the areas behind the berm. In addition, the probability of failure of the berm is high due to the improper construction. Once the berm fails, as any levee failure, the resulting damages can be significant and catastrophic. Further consultation with the USACE and NYSDEC regarding modifications to the berm or construction of a certified levee is recommended.

### 3.4 Ice-Jam Simulation Results

Attachment F contains the results for the ice-jam simulations for the existing and proposed conditions models. Figure 19 displays the flood extents for the existing conditions model under open-water (blue) and ice-jam (pink) conditions using the USGS *StreamStats* 10-percent AEP (10-year recurrence) event peak discharge. Where the flood extents for the existing conditions model under open-water and ice-jam conditions overlap, the flood extents will appear as purple on the figures.




Figure 19. Flood extents for the existing conditions model under open-water (blue) and ice-jam (pink) conditions models using the USGS StreamStats 10-percent AEP (10-year recurrence) event peak discharge.

Table 7 summarizes the model results of each proposed flood bench scenario with an ice-jam in comparison to the existing condition with an ice-jam models.

**Table 7. Results of the existing and proposed conditions models with ice-jams for the 10-, 2-, 1-, and 0.2-percent AEP events (10, 50, 100, and 500-year recurrence intervals).**

Scenario ID	Flood Bench Configurations	Reductions in Water Surface Elevations (feet NAVD88)			
		10-Percent	2-Percent	1-Percent	0.2-Percent
1	1a	2.8	1.2	1.2	1.2
2	1b	1.6	0.2	0.1	0.1
3	1b + 2	1.9	1.5	0.6	0.6
4	2 + 3	1.5	1.7	1.6	1.6
5	1b + 2 + 3	1.9	1.7	1.6	1.6
6	2 + 3 + 4	3.1	2.0	1.8	1.7
7	1b + 2 + 3 + 4	3.2	2.0	1.8	1.7
8	5 + 6	1.1	0.5	0.5	0.4
9	1b + 2 + 3 + 4 + 5 + 6	3.6	2.4	2.3	2.1

Table 8 summarizes the difference in WSELs for the 10-percent AEP event of the existing and proposed conditions with ice-jam model results for the reach along the Lexington Green neighborhood (river stations 39+97 to 53+07). It should be noted positive values indicate the existing conditions WSELs are higher than the proposed scenario, while negative values indicate the existing conditions WSELs are lower than the proposed scenario. Results for higher intensity events that occur less frequently (i.e., 2-, 1- and 0.2-percent) can be found in Attachment F.

**Table 8. WSEL (feet NAVD88) differences between the existing and proposed conditions with ice-jam models in the vicinity of Lexington Green for the 10-percent AEP event.**

	Water Surface Elevation (ft NAVD88)						
	RS 39+97	RS 41+82	RS 43+63	RS 45+82	RS 47+86	RS 50+51	RS 53+07
Scenario #1	-0.3	-0.7	-0.6	0.7	1.7	2.4	2.8
Scenario #2	0	0	0	0	0.5	0.8	1.1
Scenario #3	0	0	-0.1	0	0.5	0.9	1.2
Scenario #4	0	0	0	0	0.1	0.2	0.5
Scenario #5	0	0	-0.1	0	0.5	0.9	1.2
Scenario #6	0	0	0	0	0.1	0.2	0.5
Scenario #7	0.1	0	0	0	0.5	0.9	1.2
Scenario #8	0	0	0	0	0.1	0.1	0.3
Scenario #9	0.1	0	0	0	0.5	0.9	1.3

Figures 20 through 28 display the flood extents from the proposed with ice-jam (blue) and existing with ice-jam (pink) conditions models for each flood bench using the USGS *StreamStats* 10-percent AEP (10-year recurrence) event peak discharge. Where the flood extents for both the proposed and existing conditions with ice-jam models overlap, the flood extents will appear as purple on the figures.



Figure 20. Scenario #1 - Flood extents for proposed (blue) and existing condition (pink) with ice-jam models using the USGS StreamStats 10-percent AEP (10-year recurrence) event peak discharge.



Figure 21. Scenario #2 - Flood extents for proposed (blue) and existing condition (pink) with ice-jam models using the USGS StreamStats 10-percent AEP (10-year recurrence) event peak discharge.



Figure 22. Scenario #3 - Flood extents for proposed (blue) and existing condition (pink) with ice-jam models using the USGS StreamStats 10-percent AEP (10-year recurrence) event peak discharge.



Figure 23. Scenario #4 - Flood extents for proposed (blue) and existing condition (pink) with ice-jam models using the USGS StreamStats 10-percent AEP (10-year recurrence) event peak discharge.



Figure 24. Scenario #5 - Flood extents for proposed (blue) and existing condition (pink) with ice-jam models using the USGS StreamStats 10-percent AEP (10-year recurrence) event peak discharge.



Figure 25. Scenario #6 - Flood extents for proposed (blue) and existing condition (pink) with ice-jam models using the USGS StreamStats 10-percent AEP (10-year recurrence) event peak discharge.



Figure 26. Scenario #7 - Flood extents for proposed (blue) and existing condition (pink) with ice-jam models using the USGS StreamStats 10-percent AEP (10-year recurrence) event peak discharge.



Figure 27. Scenario #8 - Flood extents for proposed (blue) and existing condition (pink) with ice-jam models using the USGS StreamStats 10-percent AEP (10-year recurrence) event peak discharge.



Figure 28. Scenario #9 - Flood extents for proposed (blue) and existing condition (pink) with ice-jam models using the USGS StreamStats 10-percent AEP (10-year recurrence) event peak discharge.

### 3.5 Bank and Channel Stabilization Features

Streambank erosion is a natural process that occurs when the forces of flowing water exceed the ability of the soil and vegetation to hold the banks in place. The forces that cause erosion increase during flood events, and most erosion occurs at these times. Human disturbances to watersheds that increase frequency and magnitude of runoff events also increase streambank erosion. Loss of streambank and streamside vegetation reduces the resisting forces and makes streambanks more susceptible to erosion. This is often the single greatest contributing factor to harmful or accelerated erosion on small and medium-size streams (GASWCC 2000).

Streambank stabilization measures work either by reducing the force of flowing water, by increasing the resistance of the bank to erosion, or by some combination of both. Generally speaking, there are four approaches to streambank protection: 1) the use of vegetation; 2) soil bioengineering; 3) the use of rock work in conjunction with plants; and 4) conventional bank armoring (GASWCC 2000).

Streambank stabilization can also play a vital role in flood risk management in areas located in flood prone areas. The magnitude of that risk is a function of the flood hazard, the characteristics of a particular location (i.e., elevation, proximity to the waterway, susceptibility to fast-moving flows, etc.), measures that have been taken to mitigate the potential impact of flooding, the vulnerability of people and property, and the consequences that result from a particular flood event. A flood risk management strategy identifies and implements measures that reduce the overall risk, and what remains is the residual risk. In developing the strategy, those responsible judge the costs and benefits of each measure taken and their overall impact in reducing the risk (NRC 2013).

There are two types of engineering strategies to sediment and debris management and flood mitigation: structural and non-structural. Structural adjustments involve two different approaches: hard and soft structures. Hard engineering strategies act as a barrier between the river and the surrounding land where artificial structures are used to change or disrupt natural processes. Soft engineering does not involve building artificial structures, but takes a more sustainable and natural approach to managing the potential for erosion, deposition, and flooding by enhancing or protecting a river's natural features (NRC 2013). Flood benches and streambank stabilization and protection are considered soft engineering strategies.

The purpose of non-structural flood mitigation is to change the way that people interact with the floodplain, flood risk, and also aims to move people away from flood-prone areas. More and more communities have looked for alternatives to structural flood damage reduction techniques and instead have begun to pursue nonstructural techniques used to reduce flood damages that do not disturb the environment or that can lead to environmental restoration. Non-structural flood damage reduction techniques have proven to be extremely viable in alternatives consisting of total non-structural, or a combination non-structural and structural measures (USACE 2001; NRC 2013).

Bank and channel stabilization features are dependent on two forces: velocity and shear stress. Velocity in a waterway is controlled by a number of factors, including friction slope, channel geometry, size of sediments on the stream bed, and the discharge (volume) of water passing a point in a unit of time. A stream typically reaches its greatest velocity when it is close to flooding

over its banks, known as the bank-full stage. As soon as the flooding stream overtops its banks and occupies the wide area of its flood plain, the water has a much larger area to flow through and the velocity drops significantly. At this point, sediment that was being carried by the high-velocity water is deposited near the edge of the channel, forming a natural bank or levee (Earle 2019).

Shear stress is the parameter often used as a measure of the stream's ability to entrain bed material, which is created by the friction from water acting on the bed material. Generally, shear stress acts in the direction of the flow in a uniform channel as it slides along the channel bed and banks. A given particle will move only when the shear stress acting on it is greater than the resistance of the particle to movement. The resistance of the particles to movement and thus its entrainment will vary depending on its size, shape, its size relative to surrounding particles, how it is oriented and the degree to which it is embedded. The magnitude of shear stress required to move a given particle is known as the critical shear stress. When the shear stress equals the critical shear stress, the channel will likely be in equilibrium. Where shear stress is excessively greater than critical shear stress, channel degradation will likely result. Where the shear stress is less than critical shear stress, channel aggradation will likely result. Thus, the ability to calculate or measure both shear and critical shear stress is crucial in understanding channel adjustments (VTANR 2004).

Channel shear stress and velocity values were obtained from the existing conditions model simulation results (Attachment F). For the reach of Buffalo Creek that runs adjacent to the Lexington Green neighborhood between river stations 40+00 to 65+50, the maximum shear stress and velocity value was 1.3 lb/sq. ft. and 8.7 ft/s for the 1-percent AEP event.

Table 9 summarizes the bank and channel stabilization strategies that could potentially be employed along Buffalo Creek in the vicinity of the Lexington Green neighborhood (river stations 40+00 to 66+50) for the 1-percent AEP event. Attachment G summarizes the different bank and channel stabilization features discussed in Table 9. It should be noted that the identified bank and channel stabilization strategies are not intended to represent a fully comprehensive list and are based on the preliminary analysis performed in this study. Additional geomorphic research and advanced multi-dimensional open-water and ice-jam modeling is recommended to determine the most appropriate strategy for this reach of Buffalo Creek.

**Table 9. Bank and channel stabilization strategies along Buffalo Creek for the 1-percent AEP event.**

<b>Measure Type</b>	<b>Treatment Type</b>	<b>Description of Measure</b>
<b>Brush Mattress</b>	Staked only w/ rock riprap toe (grown)	Brush mattresses slow water velocities along the streambank and reduce erosion. The open space between the woody material allows for sediment deposition and water drainage. The build-up of sediment enhances the colonization of native plants.
<b>Coir Geotextile Roll</b>	Roll with Polypropylene rope mesh staked and with rock riprap toe	Coir geotextiles protect land surfaces, help with soil stabilization, promote vegetation growth in varying slopes, and provide erosion control.
<b>Gravel/Cobble</b>	12-inch	Cobble or gravel armor is used to protect a sloping bank against fluvial entrainment by flow in the stream or over the top of the bank.
<b>Soil Bioengineering</b>	Vegetated coir mat	Soil bioengineering methods have a common geotechnical benefit of providing root reinforcement in the soil and can help modify drainage patterns of the soil, help stabilize soils at steeper angles if desired, help keep grasses, and bushy vegetation in place resisting erosion, and support woody debris or other types of vegetation.
	Live brush mattress (grown)	
	Brush layering (initial/grown)	
<b>Boulder Clusters</b>	Small (>10-inch diameter) and larger	Boulder clusters can prevent large buildup of wood and reduce flood and bank erosion.

## 4. Summary

Based on the results of the proposed conditions modeling, there are multiple flood bench configurations that could provide flood mitigation benefits to the areas in the vicinity of the flood benches. The top three scenarios that produced the largest reduction of water surface elevations were:

1. **Scenario #9:** Up to 2.4-ft of modeled water surface elevation reductions at the 1-percent AEP (100-year recurrence) event.
2. **Scenario #7:** Up to 2.2-ft of modeled water surface elevation reductions at the 1-percent AEP (100-year recurrence) event.
3. **Scenario #6:** Up to 2.2-ft of modeled water surface elevation reductions at the 1-percent AEP (100-year recurrence) event.

Scenario #9 involved utilizing flood benches from all 6 proposed locations, while Scenario #7 involved flood benches 1b, 2, 3, and 4 and Scenario #6 involved flood benches 2, 3, and 4. None of the remaining scenarios exceeded 2-ft of water surface elevation reductions, with Scenarios #1, 2, and 8 producing the lowest water surface elevation reductions of less than 1-ft.

The common element between the top three scenarios was the involvement of flood benches 2, 3, and 4. As of November 2022, the landowners for flood benches 2 and 3 have expressed interest in pursuing flood mitigation projects on their properties, such as the proposed flood benches.

Flood bench 4 involves land owned by National Grid and contains utility equipment and transmission lines. Any flood mitigation project involving this land would require permission and coordination with National Grid. As of November 2022, the project team and Buffalo Niagara Waterkeeper were in contact with company representatives regarding potential interest in pursuing a flood mitigation project.

Flood benches 1a and 1b involve land owned by Canisius High School. As of November 2022, the school has started construction on the two new baseball fields, practice field, and tennis courts. Flood bench 1a would involve land being used for this new construction and, as such, would most likely not be supported by the school. Flood bench 1b does not involve land impacted by the new construction and may be potentially supported by the school. As of November 2022, the project team and Buffalo Niagara Waterkeeper were in discussions with school representatives regarding potential interest in pursuing a flood mitigation project, such as flood bench 1b.

Based on the analysis performed in this study, the Project Team recommends Scenario #6 be considered for advancement. Scenario #6 provided measurable flood mitigation benefits based on the H&H modeling simulations and requires the least number of property owner participants. In addition, the property owners for flood benches 2 and 3 have expressed interest in participating in the project during individual and the public engagement meeting. Figure 29 displays the location and extent of the flood benches for Scenario #6.



**Figure 29. Flood bench locations and extent for Scenario #6.**

The flood mitigation benefits of Scenario #6 occur predominately upstream of the Lexington Green neighborhood starting in the vicinity of George Drive/Windtree Court and extending upstream of the Railroad bridge (Figure 14). Properties in the vicinity of Mineral Springs and Indian Church Roads along the left bank of Buffalo Creek downstream of the railroad bridge would experience significant flood mitigation benefits if Scenario #6 were implemented. In addition, there is no increase in WSELs at river station 43+63 under Scenario #6, while there is an increase of up to 0.3-feet for Scenarios #7 and #9.

Based on model simulation results, Scenario #6 provides up to 0.5-feet of modeled water surface elevation reductions at the 10-percent AEP (10-year recurrence) event during an ice-jam event when compared to open-water conditions in the vicinity of the Lexington Green neighborhood. A flood bench further downstream of Scenario #6 would provide additional reductions in WSELs (i.e., reduce flood depths); however, the flood mitigation benefits would remain primarily in the upstream portion of the Lexington Green neighborhood and would not extend to the downstream portion of the neighborhood, regardless of whether an additional flood bench downstream of Scenario #6 was considered.

For the three recommended scenarios (#6, #7, and #9), there are no adverse impacts to areas upstream or downstream of the Lexington Green neighborhood, including areas in the vicinity of Canisius High School and Harlem Road bridge, according to the model simulation results.

Natural floodplains and flood benches provide flood risk reduction benefits by slowing runoff and storing flood water. They also provide other benefits of considerable economic, social, and environmental value that should be considered in local land-use decisions. Floodplains frequently contain wetlands and other important ecological areas which directly affect the quality of the local

environment. Floodplain management is the operation of a community program of preventive and corrective measures to reduce the risk of current and future flooding, resulting in a more resilient community. These measures take a variety of forms, are carried out by multiple stakeholders with a vested interest in responsible floodplain management, and generally include requirements for zoning, subdivision or building codes, and special-purpose floodplain ordinances. While FEMA has minimum floodplain management standards for communities participating in the National Flood Insurance Program (NFIP), best practices demonstrate the adoption of higher standards which will lead to safer, stronger, and more resilient communities (FEMA 2006).

There are some potential constraints to Scenario #6 that should be considered by the Project Team and community moving forward. The property owner of flood bench 4 is National Grid, which has transmission line equipment and towers within the proposed flood bench area. Coordination and buy-in from National Grid, in conjunction with design plans that mitigate any impacts to their utility equipment and towers, would be necessary to progress Scenario #6. The availability of potential State and/or Federal funding through grants, loans, awards, etc. would also need to be considered. Finally, the Oxbow along Buffalo Creek downstream of the Lexington Green neighborhood is a protected wetland so coordination with the New York State Department of Environmental Conservation (NYSDEC) would be necessary for any flood mitigation project along Buffalo Creek in the project area.

## 5. Next Steps

Engineering studies are typically completed in phases referred to as the 30-60-90-100% process. The analysis performed in this study represents a 30% conceptual design. A 30% conceptual design includes: advance preliminary concept sketches to develop conceptual design plans for the project area; rudimentary design sketches of plan, profile, and typical section views of proposed flood mitigation strategies; preliminary rough order of magnitude cost estimates for identified flood mitigation strategies; and a technical memorandum presenting engineering analysis and concept design basis.

The 60% preliminary design phase requires one or more flood mitigation strategies to be identified as a potential construction project. Once a flood mitigation strategy has been identified, a 60% preliminary design can be completed. The preliminary design involves advancing the conceptual design by incorporating any comments received from the 30% phase; modifying design plans with more specific engineering details; *using multi-dimensional or variable-specific (i.e., ice cover, sediment, etc.) hydrologic and hydraulic models* to evaluate identified flood mitigation strategies; developing additional “amenities” plans for any community identified features (i.e., walking and/or bike trails, facilities, etc.); modifying the rough order magnitude cost estimates to reflect updated engineering analyses and designs; and developing a preliminary design report presenting the updated engineering analyses and design basis.

Along with the engineering and design process, there are additional procedures that would need to be considered and potentially completed during the 60% preliminary design phase. These procedures include regulatory permitting applications; wetland delineations; rare, threatened, and endangered species identification and analyses; the Historic Preservation Review Process; preparing the Environmental Assessment Form with supporting documents to complete the State Environmental Quality Review; local permit applications; and responding to comments during the design and permit review process.

The 90% final design phase includes advanced design drawings, plans, and profiles of the construction project for both the existing and proposed conditions and construction documents with technical specifications and supporting information for the front-end specifications (i.e., bid forms, conditions of contract, forms of agreement, etc.).

The 100% final design includes the final design drawings, construction cost opinions, and contract documents signed and sealed by a licensed engineer.

## 6. References

[CRREL] Cold Regions Research and Engineering Laboratory. [Internet]. 2022. CRREL Ice Jam Database – Buffalo Creek. Hanover (NH): United States Army Corps of Engineers (USACE), Ice Engineering Research Group; [updated 2022 Dec 7; cited 2022 Dec 7]. Available from: [https://icejam.sec.usace.army.mil/ords/f?p=1001:7:::::.](https://icejam.sec.usace.army.mil/ords/f?p=1001:7:::::)

Earle S. 2019. Physical Geology – 2nd Edition. British Columbia (CA): BCcampus Open Education; [accessed Jan 18, 2021]. Available from: <https://opentextbc.ca/physicalgeology2ed/>.

Federal Emergency Management Agency (FEMA). 2006. Floodplain Management Requirements: A Study Guide and Desk Reference for Local Officials. Washington DC (US): United States Department of Homeland Security (USDHS). Available from: [https://www.fema.gov/media-library-data/20130726-1539-20490-9157/nfip\\_sg\\_full.pdf](https://www.fema.gov/media-library-data/20130726-1539-20490-9157/nfip_sg_full.pdf).

Federal Emergency Management Agency (FEMA). 2021. Flood Insurance Study, Erie County, New York (All Jurisdictions). Washington DC (US): United States Department of Homeland Security. Flood Insurance Study Number 36029CV001C-007C. Available from: FEMA.

Georgia Soil and Water Conservation Commission (GASWCC). 2000. Guidelines for Streambank Restoration. Atlanta (GA): Georgia Soil and Water Conservation Commission (GASWCC). Available from: <https://epd.georgia.gov>.

National Research Council (NRC). 2013. Levees and the National Flood Insurance Program: Improving Policies and Practices. Washington DC (US): The National Academies Press. Available from: [www.nap.edu](http://www.nap.edu).

[NYSDOT] New York State Department of Transportation. [Internet]. 2019. Bridge Point Locations & Select Attributes -New York State Department of Transportation. Albany (NY): New York State Department of Transportation, Structures Division; [updated 2019 Feb; cited 2022 Sept 29]. Available from: <https://gis.ny.gov>.

[NYSOITS] New York Office of Information Technology Services. 2019. New York State 1-meter DEM – LIDAR collection (QL2) for Erie, Genesee, and Livingston Counties New York Lidar; Hydro Flattened Bare Earth DEM. Albany (NY): New York Office of Information Technology Services. Available from: <https://gis.ny.gov/>.

[NYSOITS] New York State Office of Information Technology Services. 2021. 2021 One Foot 4 Band West Zone Orthoimagery. Albany (NY): New York State Office of Information Technology Services (NYSOITS), GIS Program Office. Available from: <http://gis.ny.gov/gateway/mg/>.

Ramboll Americas Engineering Solutions, Inc. (Ramboll). 2020. Resilient New York – Buffalo Creek. Albany (NY): New York State Department of Environmental Conservations (NYSDEC), New York State Office of General Services (NYSOGS).

Ries KG III, Newson JK, Smith MJ, Guthrie JD, Steeves PA, Haluska TL, Kolb KR, Thompson RF, Santoro RD, Vraga HW. 2017. StreamStats, version 4. Reston (VA): United States Geologic Survey (USGS). Fact Sheet 2017-3046. Available from: <https://pubs.er.usgs.gov/publication/fs20173046>.

United States Army Corps of Engineers (USACE). 2001. Non-Structural Flood Damage Reduction Within the Corps of Engineers: What Districts Are Doing. Davis (CA): United States Army Corps of Engineers (USACE), National Flood Proofing Committee (NFPC). Available from: USACE.

United States Army Corps of Engineers (USACE). 2006. Engineering and Design – ICE ENGINEERING. Washington DC (US): United States Department of Defense (USDOD), United States Department of the Army, United States Army Corps of Engineers (USACE). EM 1110-2-1612. Available from: <https://www.publications.usace.army.mil>.

United States Army Corps of Engineers (USACE). 2016. Federal Interest Determination – Buffalo Creek - Lexington Green CAP 205. Buffalo (NY): United States Army Corps of Engineers (USACE), Buffalo District. Report No.: P2#443918.

United States Army Corps of Engineers (USACE). 2021. HEC-RAS River Analysis System. [computer software]. Version 6.2.0. Davis (CA): United States Army Corps of Engineers (USACE), Hydrologic Engineering Center (HEC).

United States Army Corps of Engineers (USACE). 2022. HEC-RAS 1D Sediment Transport User's Manual. Davis (CA): United States Army Corps of Engineers (USACE), Hydrologic Engineering Center (HEC). Available from: <https://www.hec.usace.army.mil/confluence/rasdocs/rassed1d>.

[USGS] United States Geologic Survey. 2021a. National Land Cover Database (NLCD) 2019 Land Cover Conterminous United States. Sioux Falls (SD): United States Department of the Interior. Available from: <https://www.mrlc.gov/>.

[USGS] United States Geologic Survey. [Internet]. 2022. New York StreamStats Application, version 4.10.1. Reston (VA): United States Geologic Survey (USGS); [updated 2022 Feb 18; cited 2022 Sept 29]. Available from: <https://streamstats.usgs.gov/ss/>.


URS Corporation (URS). 2015. Multi-Jurisdictional Hazard Mitigation Plan Update Erie County, New York – Revised Draft. Buffalo (NY): Erie County Department of Emergency Services (ECDES). Available from: <http://www2.erie.gov/disaster/sites/www2.erie.gov.disaster/files/uploads/Multi-Jurisdictional%20Hazard%20Plan.pdf>.

Vermont Agency of Natural Resources (VTANR). 2004. Appendix O - Vermont Stream Geomorphic Assessment. In: Stream Geomorphic Assessment Handbooks. Montpelier (VT): Vermont Agency of Natural Resources (VTANR). Available from: <https://dec.vermont.gov/>.

Attachment A  
**Project Site Maps**

**Legend**

- Special Flood Hazard Areas (SFHAs)
- Regulatory Floodway
- 1% Annual Chance Hazard
- 0.2% Annual Chance Hazard
- Buffalo Creek
- Tax Parcels (Public)



## FEMA Special Flood Hazard Zones (DFRIM)


Buffalo Creek

Town of West Seneca, NY

FIGURE 1 of 2

RAMBOLL AMERICAS  
ENGINEERING SOLUTIONS, INC.  
A RAMBOLL COMPANY

RAMBOLL



Attachment B  
**Hydrologic & Hydraulic Modeling Technical Memorandum**

# HYDROLOGIC & HYDRAULIC MODELING TECHNICAL MEMORANDUM

Project name **Feasibility & Design of Floodplain Reconnection of Buffalo Creek**  
Project no. **1940102804**  
Client **Buffalo Niagara Waterkeeper**  
Memo No. **1**  
Version **3**  
To **Katherine Winkler, Senior Project Manager, Buffalo Niagara Waterkeeper**  
From **Ramboll Americas Engineering Solutions, Inc.**  
Copy to **Holly Kistner, Project Manager, Buffalo Niagara Waterkeeper**  
**Gary Dickson, Town Supervisor, Town of West Seneca**  
**Amelia Greenan, Deputy Supervisor, Town of West Seneca**  
**David Johnson, Town Engineer, Clark Patterson Lee (CPL)**  
  
Prepared by **Kadir Goz**  
Checked by **Shaun Gannon, P.E., D.WRE, P.H., CFM, PMP**  
Approved by **Michelle McEntire, PE**

Date: December 30, 2022

Ramboll  
Harro East Building  
400 Andrews Street, Suite 710  
Rochester, NY 14604  
USA

T 585-295-7700  
F 585-510-3023  
<https://ramboll.com>

## Table of Contents

<b>1 Methodology .....</b>	<b>5</b>
1.1 Model Input Data .....	5
1.2 FEMA Hydrologic & Hydraulic (H&H) Model .....	6
1.3 Existing Conditions Model .....	7
1.4 Boundary Conditions.....	8
1.5 Survey Data .....	8
1.6 Overbank Modifications .....	9
1.7 Flood Bench Scenarios .....	10
1.8 Proposed Scenario Modeling.....	13
1.9 Ice-Jam Analysis .....	14
<b>2 Results.....</b>	<b>16</b>
2.1 Effective FEMA versus Existing Conditions Models.....	16
2.2 Scenario Modeling Results .....	20
2.3 Berm Impacts.....	30
2.4 Ice-Jam Simulation Results.....	32
2.5 Bank and Channel Stabilization Features.....	46
<b>3 References.....</b>	<b>50</b>

### Table of Tables

Table 1. USGS <i>StreamStats</i> Peak Streamflow for Buffalo Creek.....	6
Table 2. Summary Table of Proposed Flood Bench Configurations.....	12
Table 3. Summary table of modeled flood bench scenarios. ....	13
Table 4. HEC-RAS Model Results for the FEMA FIS 1-Percent Peak Discharge. ....	16
Table 5. Results of the Proposed Conditions Models.....	20
Table 6. WSELs (feet NAVD88) in the vicinity of Lexington Green for the existing and proposed conditions models for the 1-percent AEP event. ....	30
Table 7. WSELs (feet NAVD88) in the vicinity of the berm along Lexington Green for the existing and proposed conditions models for the 1-percent AEP event. ....	32
Table 8. Results of the existing and proposed conditions models with ice-jams for the 10-, 2-, 1-, and 0.2- percent AEP events (10, 50, 100, and 500-year recurrence intervals). ....	35
Table 9. WSELs (feet NAVD88) in the vicinity of Lexington Green for the existing and proposed conditions with ice-jam models for the 10-percent AEP event. ....	35
Table 10. Existing Conditions Model Results for Channel Maximum Shear Stress and Velocity.....	46
Table 11. Bank and channel stabilization strategies along Buffalo Creek for the 1-percent AEP event. ....	49

### Table of Figures

Figure 1. FEMA Effective FIS model layout for Buffalo Creek.....	7
Figure 2. Existing conditions model layout from the USACE HEC-RAS model software for Buffalo Creek. ....	8
Figure 3. Field survey locations along Buffalo Creek. ....	9
Figure 4. HEC-RAS representation of a blocked obstruction. ....	10
Figure 5. Location map of Buffalo Creek and the flood bench scenarios. ....	12

Figure 6. Example Cross-Section from HEC-RAS Depicting a Flood Bench. ....	14
Figure 7. Effective FEMA and existing conditions profile plot using the FEMA 1-percent AEP (100-year recurrence) event peak discharge. ....	17
Figure 8. Flood extents for the effective FEMA (blue) and existing condition (red) model simulation results using the FEMA 1-percent AEP (100-year recurrence) event peak discharge. ....	19
Figure 9. HEC-RAS model profile plots for Flood Bench Scenario #1.....	21
Figure 10. HEC-RAS model profile plots for Flood Bench Scenario #2.....	22
Figure 11. HEC-RAS model profile plots for Flood Bench Scenario #3.....	23
Figure 12. HEC-RAS model profile plots for Flood Bench Scenario #4.....	24
Figure 13. HEC-RAS model profile plots for Flood Bench Scenario #5 .....	25
Figure 14. HEC-RAS model profile plots for Flood Bench Scenario #6.....	26
Figure 15. HEC-RAS model profile plots for Flood Bench Scenario #7.....	27
Figure 16. HEC-RAS model profile plots for Flood Bench Scenario #8.....	28
Figure 17. HEC-RAS model profile plots for Flood Bench Scenario #9.....	29
Figure 18. Flood extents for existing with berm (pink) and existing without berm (green) conditions models using the USGS StreamStats 1-percent AEP (100-year recurrence) event peak discharge.....	31
Figure 19. Flood extents for the existing conditions model under open-water (blue) and ice-jam (pink) conditions models using the USGS StreamStats 10-percent AEP (10-year recurrence) event peak discharge. ....	34
Figure 20. HEC-RAS model profile plots for Flood Bench Scenario #1 under ice cover conditions. ....	37
Figure 21. HEC-RAS model profile plots for Flood Bench Scenario #2 under ice cover conditions. ....	38
Figure 22. HEC-RAS model profile plots for Flood Bench Scenario #3 under ice cover conditions. ....	39
Figure 23. HEC-RAS model profile plots for Flood Bench Scenario #4 under ice cover conditions. ....	40
Figure 24. HEC-RAS model profile plots for Flood Bench Scenario #5 under ice cover conditions. ....	41
Figure 25. HEC-RAS model profile plots for Flood Bench Scenario #6 under ice cover conditions. ....	42
Figure 26. HEC-RAS model profile plots for Flood Bench Scenario #7 under ice cover conditions. ....	43
Figure 27. HEC-RAS model profile plots for Flood Bench Scenario #8 under ice cover conditions. ....	44
Figure 28. HEC-RAS model profile plots for Flood Bench Scenario #9 under ice cover conditions. ....	45

## 1 Methodology

### 1.1 Model Input Data

The following data was obtained and utilized for the H&H modeling efforts:

- FEMA effective H&H model for Buffalo Creek (FEMA 2021)
- FEMA peak discharges (FEMA 2021)
- USGS *StreamStats* peak discharges (USGS 2021)
- New York State Digital Ortho-Imagery Program imagery (NYSOITS 2021)
- National Land Cover Database (NLCD) data (USGS 2021)
- NYSDOT bridge data (NYSDOT 2019)
- New York State 1-meter LiDAR digital elevation model (DEM) data with vertical accuracy of 19.6-centimeters (7.7 inches) in the North American Vertical Datum of 1988 (NAVD88) (NYSOITS 2019)

The hydrologic input data that was used by FEMA in the effective Flood Insurance Study (FIS) model was a peak discharge calculated using the methodology outlined in USGS Water Resources Investigations (WRI) 79-83 "Technique for Estimating Magnitude and Frequency of Flooding in Rural Unregulated Streams in New York State excluding Long Island" (USGS 1979), for un-gaged sites on gaged streams. This report is obsolete and was replaced in 2006 by Scientific Investigation Report (SIR) 2006-5112 "Magnitude and Frequency of Flood in New York." SIR 2006-5112 forms the bases for the current method, USGS Stream Stats, for estimating peak discharges lacking stream measurement gages.

Peak discharge data for Buffalo Creek in the effective (FIS) for Erie County, NY (2021); were for the 1-percent AEP event, also referred to as the 100-year recurrence event, only, which was 16,000 cubic feet per second (cfs). To evaluate existing and proposed conditions along Buffalo Creek, it was necessary to obtain discharge data for the 50-, 20-, 10-, 2-, 1-, and 0.2- percent AEP (2, 5, 10, 50, 100, and 500-year recurrence) events. Hydrologic data was obtained from the USGS StreamStats software.

The USGS StreamStats v4.10.1 software (<https://streamstats.usgs.gov/ss/>) is a map-based web application that provides an assortment of analytical tools that are useful for water resources planning and management, and engineering purposes. The primary purpose of StreamStats is to provide estimates of streamflow statistics for user-selected un-gaged sites on streams and for USGS stream gages, which are locations where streamflow data are collected (Ries et al. 2017, USGS 2022). Table 1 displays the peak streamflow data obtained from StreamStats for Buffalo Creek at the confluence with Cayuga Creek.

The StreamStats peak discharge of 13,600 cfs is less than the effective FIS value of 16,000 cfs. This is attributed to StreamStats using updated equations as detailed in SIR 2006-5112.

**Table 1. USGS StreamStats Peak Streamflow for Buffalo Creek.**

Location	Drainage Area (sq miles)	River Station (ft)	Peak Discharges (cfs)			
			10-Percent	2-Percent	1-Percent	0.2-Percent
Confluence with Cayuga Creek	146	0+00	7,990	11,800	13,600	18,000


## 1.2 FEMA Hydrologic & Hydraulic (H&H) Model

As part of its role under the National Flood Insurance Program (NFIP), FEMA performs hydrologic & hydraulic (H&H) analyses and develops H&H models for each studied watershed within a community to establish regulatory flood insurance boundaries (i.e., effective FIS). The effective FIS for Buffalo Creek was created using the United States Army Corps of Engineers (USACE) Hydrologic Engineering Center River Analysis System (HEC-RAS) program (USACE 2021).

According to the FIS for Erie County, NY (2021), the effective FEMA model for Buffalo Creek in the Town of West Seneca was originally completed by FEMA in 1976. It was then revised and updated in 1992. For the current effective FIS (2021) the 1992 data was remapped using Digital Elevation Models (DEM) and ortho-imagery.

For this project, the effective FEMA model was obtained for the project area, which begins at the union between Buffalo Creek and Cayuga Creek (river station 0+00) and extends upstream to the Buffalo Airfield (river station 205+00) (Figure 2). In Figure 1 below, the blue line represents the centerline of Buffalo Creek while the green lines represent the cross-sections in the effective FEMA model.

Additionally, the numbered labels represent the distance (in feet) along the centerline upstream from the union of Buffalo and Cayuga Creeks.



**Figure 1.** FEMA Effective FIS model layout for Buffalo Creek.

### 1.3 Existing Conditions Model

The FEMA effective H&H model was obtained by Ramboll and was one component in the development of the existing conditions model. Due to the age of the effective FEMA model (first developed in 1976 and updated in 1992), most of the data used by FEMA in the model is outdated and potentially inaccurate. Therefore, the model used in this study is a combination of DEM data and the effective FIS.

Using LiDAR based DEM and land cover data (both from 2019), the geometry from each cross section in the effective FEMA model had the overland and channel geometries cut from the DEM. Manning's roughness values were assigned based on land cover type (NYSOITS 2019; USGS 2021). Since LiDAR does not completely penetrate water and record the channel bottom, the minimum channel elevation of each cross section was modified to match the channel elevation from the effective FEMA model (1992) or FIS profile plot (2019).

In addition, 12 cross sections were added to those in the effective FIS model between river stations 36+50 and 80+00 to provide the necessary starting and ending positions for the different flood bench scenarios along the Lexington Green neighborhood. These new cross sections had their overland set to the DEM data and the minimum channel elevations were modified to match the minimum channel elevation from the effective FIS model profile plot. This updated model is referred to as the ***existing conditions model***. Figure 2 displays the existing conditions model layout for Buffalo Creek. The blue line represents the centerline of Buffalo Creek while the green lines represent the cross-sections in the existing conditions. Additionally, the numbered labels represent the distance (in feet) along the centerline upstream from the union of Buffalo and Cayuga Creeks.




Figure 2. Existing conditions model layout from the USACE HEC-RAS model software for Buffalo Creek.

#### 1.4 Boundary Conditions

The modeling software requires an estimate of the conditions at the downstream boundary of the study to solve for water surface elevation at each cross section. These are referred to as Boundary Conditions. The method used in the effective FIS and the existing conditions model was slope, also referred to as the normal depth method (FEMA 2021). For this model, the slope between the last three cross sections was used and calculated to be 0.00012 ft/ft.

#### 1.5 Survey Data

Field staff from Ramboll performed a field visit on November 2, 2022, where overbank and in-channel survey data and streambank assessments were performed. Four locations were surveyed due to their accessibility, close proximity to the Lexington Green neighborhood, and lack of adequate representation in the effective FEMA model layout. Figure 3 displays the field survey locations along Buffalo Creek.



**Figure 3. Field survey locations along Buffalo Creek.**

Field surveys involved field staff using surveying and leveling equipment to measure land surface elevations perpendicularly across the creek channel from one overbank area to the other at the four identified locations. In addition, stream bank assessments were performed at each location to determine the condition and locations of overbank zones (e.g., toe, bank, overbank, transitional, and upland zones).

This survey data was used to validate the overbank and channel elevations in the existing conditions model and incorporated into the model where significant discrepancies were found by modifying the cross-section geometry in the existing conditions model. Attachment B contains the field notes from the field staff

### 1.6 Overbank Modifications

Through public engagement and a meeting with Canisius High School, it was identified that the school is in the process of constructing two baseball fields, a practice field, and tennis courts in the open area adjacent to Buffalo Creek. The site plans and drawings for this construction was provided to Ramboll and incorporated into the H&H model for Buffalo Creek.

The new construction includes the placement of fill material in overland areas adjacent to Buffalo Creek. To account for this fill the existing conditions model was modified using blocked obstructions. Blocked Obstructions simply “blockout” a portion of the cross-section area preventing water from expanding into it. Attachment B contains the site plans for the development. Figure 4 displays the HEC-RAS cross section data window where a blocked obstruction was used to represent the proposed development.




Figure 4. HEC-RAS representation of a blocked obstruction.

### 1.7 Flood Bench Scenarios

A flood bench (also referred to as floodplain bench or bankfull bench) is a flat area adjacent to the stream at some specified elevation constructed to both create an area for flows above a specific discharge to spread out, dissipate energy and to provide for sediment and debris deposition. A flood bench is effective for reducing flood stages and velocities, improving water quality, reducing stream bank erosion, and providing stream bed stability. Attachment C contains a sectional plan view of a flood bench.

Potential flood bench locations were identified using input received from the public engagement meeting and contact with individual property owners. Highland Planning, LLC (Highland), the public outreach and engagement sub-contractor for this project, took the lead in contacting and engaging with property owners to gauge interest in being included in this project. A public engagement meeting took place on

August 22, 2022, where project members from Ramboll discussed the project goals and potential property owner participation. Based on discussions and participation by the community and property owners, six potential flood bench configurations were identified along Buffalo Creek within the project area.

In addition, through public engagement and discussions with representatives of Canisius High School, it was identified that the school is in the process of constructing two baseball fields, a practice field, and tennis courts in the open area adjacent to Buffalo Creek. The site plans and drawings for this construction were provided to Ramboll and incorporated into the H&H model for Buffalo Creek. Attachment D contains the site plans for the development.

Table 2 summarizes the different identified flood bench configurations with descriptions. Figure 5 displays the locations and extents of each flood bench scenario, including the proposed development locations by the Canisius High School.

**Table 2. Summary Table of Proposed Flood Bench Configurations**

Flood Bench ID	Description
<b>1a</b>	Western portion of the Canisius School tax parcel
<b>1b</b>	Western portion of the Canisius School tax parcel (outside of proposed site plans)
<b>2</b>	Western portion of the 1904 Union Rd tax parcel
<b>3</b>	Western portion of the 3099 Clinton Street tax parcel
<b>4</b>	Western portion of the Transmission Land (Right Bank) tax parcel
<b>5</b>	Western portion of the Transmission Land (Upstream – Left Bank) tax parcel
<b>6</b>	Western portion of the Transmission Land (Downstream - Left Bank) tax parcel

**Figure 5. Location map of Buffalo Creek and the flood bench scenarios.**


Based on the six identified flood bench locations, nine flood bench scenarios of different configurations were developed and modeled using the HEC-RAS modeling software. Table 3 outlines the nine flood bench scenarios.

**Table 3. Summary table of modeled flood bench scenarios.**

Scenario ID	Flood Bench Configurations
1	1a
2	1b
3	1b + 2
4	2 & 3
5	1b + 2 + 3
6	2 + 3 + 4
7	1b + 2 + 3 + 4
8	5 + 6
9	1b + 2 + 3 + 4 + 5 + 6

### 1.8 Proposed Scenario Modeling

Using the HEC-RAS modeling software, ***proposed conditions models*** were developed for each flood bench configuration based on the existing conditions model. To model each flood bench scenario, cross section, that intersected a proposed flood bench in that specified configuration, were modified by adjusting the elevation of the overland terrain. Figure 6 displays an example cross section where the overbank terrain was modified to represent a flood bench.



**Figure 6.** Example Cross-Section from HEC-RAS Depicting a Flood Bench.

### 1.9 Ice-Jam Analysis

An ice jam typically occurs in the late winter and early spring in ice-covered streams when ice accumulates at man-made (e.g., bridge piers, dams) or natural narrower or shallower sections or meanders of a river slowing down or blocking the incoming ice by bridging the ice across the width of the river. Ice-jam flooding presents a complex problem for scientists and engineers since the resulting flood stage can be significantly higher than the flood stage caused from streamflow alone. In other words, a relatively minor discharge of streamflow can result in a major flooding event during an ice jam (USACE 2006).

The ice jam analysis in this study used the 10% ACE (10-yr) to develop an **existing condition with ice cover model**. Ice-jam simulations were performed for each proposed conditions model using the built-in Ice Cover settings within the HEC-RAS model software. Based on historical ice jam data, ice

cover lengths and depths were obtained and input into the model. For the ice-jam simulations, an ice cover of 1-ft thickness was used starting from the confluence with Cayuga Creek/Buffalo River (river station 0+00) upstream to the Union Road bridge (river station 118+60).

## 2 Results

### 2.1 Effective FEMA versus Existing Conditions Models

Based on the modeling simulation results, there is a difference in water surface elevations (WSELS) between the effective FEMA and existing conditions models of up to 2.0-feet using the FEMA 1-percent AEP peak discharge of 16,000 cfs. Table 4 outlines the results of the effective FEMA and Existing Conditions models. Figure 7 displays the profile plot of the effective FEMA and existing conditions model results.

**Table 4. HEC-RAS Model Results for the FEMA FIS 1-Percent Peak Discharge.**

River Station (ft) Effective/Existing	Water Surface Elevation (ft NAVD88)		
	Effective FEMA	Existing Conditions	Difference Effective - Existing
<b>20473/20483</b>	635.1	634.5	0.6
<b>19313</b>	631.8	631.6	0.2
<b>18263/18244</b>	629.9	629.9	0.0
<b>17053</b>	628.0	627.5	0.5
<b>15733/15751</b>	625.2	624.4	0.8
<b>14399/14403</b>	623.3	623.0	0.3
<b>12984/12986</b>	622.1	621.8	0.3
<b>11955/12162</b>	618.3	619.0	-0.7
<b>11899/11955</b>	618.2	618.2	0.0
<b>Union Rd</b>			
<b>11826/11789</b>	617.5	615.9	1.6
<b>11682/11675</b>	617.5	616.2	1.3
<b>10330/10302</b>	614.5	613.0	1.6
<b>9376/9372</b>	610.1	608.1	2.0
<b>8312</b>	607.8	608.1	-0.3
<b>8081/8145</b>	606.6	607.7	-1.2
<b>Railroad Bridge</b>			
<b>8016/7984</b>	606.4	606.6	-0.3
<b>7906</b>	606.3	-	-
<b>7758</b>	-	606.3	-
<b>7564</b>	-	605.9	-
<b>7340</b>	-	605.5	-
<b>7140/7151</b>	603.3	604.9	-1.6
<b>6890</b>	-	604.3	-
<b>6631</b>	-	602.8	-
<b>6324</b>	-	601.7	-
<b>6009/6015</b>	599.5	600.0	-0.5

River Station (ft) Effective/Existing	Water Surface Elevation (ft NAVD88)		
	Effective FEMA	Existing Conditions	Difference Effective - Existing
5607	-	599.0	-
5307	-	598.3	-
5051	-	597.5	-
4785/4786	597.8	596.7	1.1
4582	-	595.7	-
4363	-	594.6	-
4182	-	594.0	-
3997	-	593.5	-
3686/3670	594.0	593.5	0.5
2949/2921	592.7	591.4	1.3
1922/1922	591.5	590.8	0.7
866/833	589.6	590.0	-0.4
279	588.9	588.9	0.0




Figure 7. Effective FEMA and existing conditions profile plot using the FEMA 1-percent AEP (100-year recurrence) event peak discharge.

The differences between the effective and existing conditions models are a result of multiple factors, including:

- Updated overbank and channel geometry using the most current LiDAR DEM available
- Updated Manning's n values in the overbank areas to represent land use changes over time in the watershed
- The additional cross-sections in the project area providing more consistent and higher resolution hydraulic calculations and output data
- Difference in versions of the USACE HEC-RAS modeling used for the effective FIS and the existing conditions model.

The existing conditions model, developed for this study, was not prepared in accordance with all requirements of FEMA Guidelines and Specifications. Therefore, this model should not be considered the bases to challenge the effective Flood Insurance Rate Maps (FIRMs).

Figure 8 displays the flood extents of the effective FEMA and existing conditions model results using the FEMA 1-percent AEP event peak discharge. It should be noted that all models used in this study are 1-dimensional (1D) HEC-RAS models. The flood extent outputs from 1D models are static WSELs that are superimposed over the DEM terrain. Any terrain elevation within the model domain that is below the WSEL at a given cross-section will appear flooded regardless of the hydrological connectivity of the area to the flooding source.




Figure 8. Flood extents for the effective FEMA (blue) and existing condition (red) model simulation results using the FEMA 1-percent AEP (100-year recurrence) event peak discharge.

The largest difference between the effective FEMA and existing conditions model simulations results occurs downstream of the Oxbow and in the vicinity of the Lexington Green neighborhood. Since the development of the effective FIS a temporary protective berm was placed to help reduce the risk of flooding in the Lexington Green neighborhood.

For regulatory and insurance purposes, the berm along the Lexington green neighborhood is not recognized as an official levee since it does not meet the minimum design standards for providing safe, reliable flood protection. The minimum design standards include design height for the specified level of protection (e.g., 1% AEP/100-year level), overtopping criteria, top width, side slopes, seepage, and stability (i.e., foundation protection, erosion and scour protection, etc.). Therefore, it was considered in the developing the effective FIRM nor this study.

## 2.2 Scenario Modeling Results

The results of each proposed flood bench scenario modeled in comparison to the existing conditions model is summarized in Table 5. The table represents the maximum difference in water surface elevation at any point within the study area.

**Table 5. Results of the Proposed Conditions Models.**

Scenario ID	Flood Bench Configurations	Reductions in Water Surface Elevations (ft NAVD88)			
		10-Percent	2-Percent	1-Percent	0.2-Percent
1	1a	1.0	1.4	1.5	1.6
2	1b	0.4	0.6	0.6	0.6
3	1b + 2	0.8	1.2	1.3	1.3
4	2 + 3	1.4	1.6	1.6	1.6
5	1b + 2 + 3	1.4	1.6	1.6	1.6
6	2 + 3 + 4	1.5	2.0	2.2	2.4
7	1b + 2 + 3 + 4	1.5	2.0	2.2	2.5
8	5 + 6	0.6	0.7	0.7	0.7
9	1b + 2 + 3 + 4 + 5 + 6	1.6	2.2	2.4	2.8

Figures 9 through 17 display the HEC-RAS profile plot results for each flood bench scenario compared to the existing conditions WSELs using the USGS *StreamStats* 10-, 2-, 1-, and 0.2-percent AEP event peak discharges.




Figure 9. HEC-RAS model profile plots for Flood Bench Scenario #1.





Figure 10. HEC-RAS model profile plots for Flood Bench Scenario #2.



**Figure 11. HEC-RAS model profile plots for Flood Bench Scenario #3.**





Figure 12. HEC-RAS model profile plots for Flood Bench Scenario #4.



**Figure 13. HEC-RAS model profile plots for Flood Bench Scenario #5 .**




Figure 14. HEC-RAS model profile plots for Flood Bench Scenario #6.




Figure 15. HEC-RAS model profile plots for Flood Bench Scenario #7.




Figure 16. HEC-RAS model profile plots for Flood Bench Scenario #8.




Figure 17. HEC-RAS model profile plots for Flood Bench Scenario #9.

Table 6 looks specifically at the changes in water surface elevation within the Lexington Green neighborhood (river stations 39+97 to 53+07) for the 1-percent AEP event. Results for events that occur more frequently (i.e., 10- and 2-percent) can be found in Attachment F.

**Table 6. WSELs (feet NAVD88) in the vicinity of Lexington Green for the existing and proposed conditions models for the 1-percent AEP event.**

	Water Surface Elevation (ft NAVD88)						
	RS 39+97	RS 41+82	RS 43+63	RS 45+82	RS 47+86	RS 50+51	RS 53+07
<b>Existing Conditions</b>	594.6	594.8	595.1	595.8	596.4	597.0	597.7
<b>Scenario #1</b>	594.7	595.0	595.6	595.8	596.1	596.3	596.4
<b>Scenario #2</b>	594.6	594.8	595.5	595.8	596.4	597.0	597.4
<b>Scenario #3</b>	594.6	594.8	595.5	595.8	596.4	597.0	597.5
<b>Scenario #4</b>	594.6	594.8	595.1	595.8	596.4	597.0	597.9
<b>Scenario #5</b>	594.6	594.8	595.5	595.8	596.4	597.0	597.5
<b>Scenario #6</b>	594.6	594.8	595.1	595.8	596.4	597.0	597.9
<b>Scenario #7</b>	594.6	594.8	595.5	595.8	596.4	597.0	597.5
<b>Scenario #8</b>	594.6	594.8	595.1	595.8	596.4	597.0	597.8
<b>Scenario #9</b>	594.6	594.8	595.5	595.8	596.4	597.0	597.5

Near the Lexington Green neighborhood, WSELs remain unchanged for most of flood bench scenarios. Scenario #1 displays the most significant benefits with WSEL reductions of up to 1.3-ft, primarily in the upstream portion of Lexington Green.

### 2.3 Berm Impacts

For regulatory and insurance purposes, the berm along the Lexington Green neighborhood is not recognized as an official levee since it does not meet the minimum design standards for providing safe, reliable flood protection. However, due to the existence of and flood mitigation impacts of the existing berm, the project team included the berm in the H&H analysis performed in this study. The berm elevation in the existing conditions model was set to 599.5-ft NAVD88 in line with the LiDAR DEM data. Figure 18 displays the flood extents for the existing conditions model simulation results with and without the berm.



**Figure 18. Flood extents for existing with berm (pink) and existing without berm (green) conditions models using the USGS StreamStats 1-percent AEP (100-year recurrence) event peak discharge.**

Table 7 summarizes the results for the 1-percent AEP event of the existing and proposed conditions modeling for the reach containing the berm along the Lexington Green neighborhood. Results for events that occur more frequently (i.e., 10- and 2-percent) can be found in Attachment F.

**Table 7. WSELs (feet NAVD88) in the vicinity of the berm along Lexington Green for the existing and proposed conditions models for the 1-percent AEP event.**

	Water Surface Elevation (ft NAVD88)		
	RS 45+82	RS 47+86	RS 50+51
<b>Berm Elevation (ft NAVD88)</b>	<b>599.5</b>	<b>599.5</b>	<b>600.5</b>
<b>Existing Conditions</b>	595.8	596.4	597.0
<b>Scenario #1</b>	595.8	596.1	596.3
<b>Scenario #2</b>	595.8	596.4	597.0
<b>Scenario #3</b>	595.8	596.4	597.0
<b>Scenario #4</b>	595.8	596.4	597.0
<b>Scenario #5</b>	595.8	596.4	597.0
<b>Scenario #6</b>	595.8	596.4	597.0
<b>Scenario #7</b>	595.8	596.4	597.0
<b>Scenario #8</b>	595.8	596.4	597.0
<b>Scenario #9</b>	595.8	596.4	597.0

It is important to note that since the berm was not built to USACE guidelines, the berm does not have the appropriate high-ground elevation tie-ins for the upstream and downstream ends of the berm. As a result, flood waters from high flow events can circumvent the berm causing flooding to the areas behind the berm. In addition, the probability of failure of the berm is high due to the improper construction. Once the berm fails, as any levee failure, the resulting damages can be significant and catastrophic. Further consultation with the USACE and NYSDEC regarding modifications to the berm or construction of a certified levee is recommended.

#### 2.4 Ice-Jam Simulation Results

The ice jam analysis in this study used the 10% ACE (10-yr) to develop an existing condition with ice cover model simulation at each identified ice-jam susceptible location using the built-in Ice Cover settings within the HEC-RAS model software. Where ice cover was modeled in the vicinity of bridges, the Ice Jam Computation Option under the Bridge/Culvert Data editor was changed to the option "ice remains constant through the bridge" in the HEC-RAS model software (USACE 2021).

Based on historical ice jam data and public engagement, ice cover lengths and depths were obtained and input into the model. Manual calibration of the length and depth of the ice cover in the model was performed to reproduce historical flood levels caused by ice-jam events along Buffalo Creek in the vicinity of Lexington Green. The calibration determined that an ice cover of 1 ft thick and extending from the confluence with Cayuga Creek (Buffalo River) upstream to the Union Road bridge reproduced the historical flood levels.

Using the calibrated ice cover specifications, the existing condition ice-cover simulation model was used to test the effectiveness of the flood bench alternatives. Figure 19 displays the flood extents for the existing conditions model under open-water (blue) and ice-jam (pink) conditions using the USGS StreamStats 10-percent AEP (10-year recurrence) event peak discharge. Where the flood extents for the existing conditions model under open-water and ice-jam conditions overlap, the flood extents will appear as purple on the figures.



Figure 19. Flood extents for the existing conditions model under open-water (blue) and ice-jam (pink) conditions models using the USGS StreamStats 10-percent AEP (10-year recurrence) event peak discharge.

Table 8 summarizes the model results of each proposed flood bench scenario with an ice-jam in comparison to the existing condition with an ice-jam models.

**Table 8. Results of the existing and proposed conditions models with ice-jams for the 10-, 2-, 1-, and 0.2-percent AEP events (10, 50, 100, and 500-year recurrence intervals).**

Scenario ID	Flood Bench Configurations	Reductions in Water Surface Elevations (feet NAVD88)			
		10-Percent	2-Percent	1-Percent	0.2-Percent
1	1a	2.8	1.2	1.2	1.2
2	1b	1.6	0.2	0.1	0.1
3	1b + 2	1.9	1.5	0.6	0.6
4	2 + 3	1.5	1.7	1.6	1.6
5	1b + 2 + 3	1.9	1.7	1.6	1.6
6	2 + 3 + 4	3.1	2.0	1.8	1.7
7	1b + 2 + 3 + 4	3.2	2.0	1.8	1.7
8	5 + 6	1.1	0.5	0.5	0.4
9	1b + 2 + 3 + 4 + 5 + 6	3.6	2.4	2.3	2.1

Scenario #9 provides the greatest overall flood mitigation benefits under ice-jam conditions in the project area with WSEL reductions of up to 3.6-ft. Scenarios #7 and #6 follow with WSEL reductions of up to 3.2- and 3.1-ft, respectively. Table 9 summarizes the WSEL results for the 10-percent AEP event of the existing and proposed conditions with ice-jam models for the reach along the Lexington Green neighborhood (river stations 39+97 to 53+07). Results for higher intensity events that occur less frequently (i.e., 2-, 1- and 0.2-percent) can be found in Attachment F.

**Table 9. WSELs (feet NAVD88) in the vicinity of Lexington Green for the existing and proposed conditions with ice-jam models for the 10-percent AEP event.**

	Water Surface Elevation (ft NAVD88)						
	RS 39+97	RS 41+82	RS 43+63	RS 45+82	RS 47+86	RS 50+51	RS 53+07
<b>Existing Conditions</b>	595.6	596.0	596.5	597.9	599.1	599.9	600.5
<b>Scenario #1</b>	595.9	596.7	597.1	597.2	597.4	597.5	597.7
<b>Scenario #2</b>	595.6	596.0	596.5	597.9	598.6	599.1	599.4
<b>Scenario #3</b>	595.6	596.0	596.6	597.9	598.6	599.0	599.3
<b>Scenario #4</b>	595.6	596.0	596.5	597.9	599.0	599.7	600.0
<b>Scenario #5</b>	595.6	596.0	596.6	597.9	598.6	599.0	599.3
<b>Scenario #6</b>	595.6	596.0	596.5	597.9	599.0	599.7	600.0
<b>Scenario #7</b>	595.5	596.0	596.5	597.9	598.6	599.0	599.3
<b>Scenario #8</b>	595.6	596.0	596.5	597.9	599.0	599.8	600.2
<b>Scenario #9</b>	595.5	596.0	596.5	597.9	598.6	599.0	599.2

In the vicinity of Lexington Green, Scenario #1 provides the greatest flood mitigation benefits under ice-jam conditions with WSEL reductions of up to 2.8-ft, while Scenarios #9, #7, and #6 follow with

reductions of up to 1.3- and 1.2-ft, respectively. Figures 20 through 28 display the HEC-RAS profile plot results for the ice-jam simulations of each flood bench scenario compared to the existing conditions WSELs using the USGS *StreamStats* 10-, 2-, 1-, and 0.2-percent AEP event peak discharges. Where the flood extents for both the proposed and existing conditions with ice-jam models overlap, the flood extents will appear as purple on the figures.





Figure 20. HEC-RAS model profile plots for Flood Bench Scenario #1 under ice cover conditions.



**Figure 21. HEC-RAS model profile plots for Flood Bench Scenario #2 under ice cover conditions.**




Figure 22. HEC-RAS model profile plots for Flood Bench Scenario #3 under ice cover conditions.




Figure 23. HEC-RAS model profile plots for Flood Bench Scenario #4 under ice cover conditions.





Figure 24. HEC-RAS model profile plots for Flood Bench Scenario #5 under ice cover conditions.



**Figure 25. HEC-RAS model profile plots for Flood Bench Scenario #6 under ice cover conditions.**






Figure 26. HEC-RAS model profile plots for Flood Bench Scenario #7 under ice cover conditions.



**Figure 27. HEC-RAS model profile plots for Flood Bench Scenario #8 under ice cover conditions.**



**Figure 28. HEC-RAS model profile plots for Flood Bench Scenario #9 under ice cover conditions.**

## 2.5 Bank and Channel Stabilization Features

Streambank erosion is a natural process that occurs when the forces of flowing water exceed the ability of the soil and vegetation to hold the banks in place. The forces that cause erosion increase during flood events, and most erosion occurs at these times. Human disturbances to watersheds that increase frequency and magnitude of runoff events also increase streambank erosion. Loss of streambank and streamside vegetation reduces the resisting forces and makes streambanks more susceptible to erosion. This is often the single greatest contributing factor to harmful or accelerated erosion on small and medium-size streams (GASWCC 2000).

Streambank stabilization measures work either by reducing the force of flowing water, by increasing the resistance of the bank to erosion, or by some combination of both. Generally speaking, there are four approaches to streambank protection: 1) the use of vegetation; 2) soil bioengineering; 3) the use of rock work in conjunction with plants; and 4) conventional bank armoring (GASWCC 2000).

Bank and channel stabilization features are dependent on two forces: velocity and shear stress. Velocity in a waterway is controlled by a number of factors, including friction slope, channel geometry, size of sediments on the stream bed, and the discharge (volume) of water passing a point in a unit of time. A stream typically reaches its greatest velocity when it is close to flooding over its banks, known as the bank-full stage. As soon as the flooding stream overtops its banks and occupies the wide area of its flood plain, the water has a much larger area to flow through and the velocity drops significantly. At this point, sediment that was being carried by the high-velocity water is deposited near the edge of the channel, forming a natural bank or levee (Earle 2019).

Shear stress is the parameter often used as a measure of the stream's ability to entrain bed material, which is created by the friction from water acting on the bed material. Generally, shear stress acts in the direction of the flow in a uniform channel as it slides along the channel bed and banks.

Channel shear stress and velocity values were obtained from the existing conditions model simulation results (Attachment E). For the reach of Buffalo Creek that runs adjacent to the Lexington Green neighborhood between river stations (RS) 40+00 to 65+50, the maximum shear stress and velocity value was 1.3 lb/sq ft and 8.7 ft/s for the 1-percent AEP. Table 10 displays the channel maximum shear stress (lb/sq ft) and velocity (ft/s) for the existing conditions model.

**Table 10. Existing Conditions Model Results for Channel Maximum Shear Stress and Velocity.**

River Station (ft)	Channel Maximum Shear Stress (lb/sq ft)				Channel Maximum Velocity (ft/s)			
	10-Percent	2-Percent	1-Percent	0.2-Percent	10-Percent	2-Percent	1-Percent	0.2-Percent
<b>204+83</b>	0.9	1.2	1.3	1.7	7.1	8.7	9.3	10.5
<b>193+13</b>	1.3	1.6	1.7	1.9	8.4	9.7	10.2	10.9
<b>182+44</b>	0.9	1.0	1.0	1.1	7.0	7.7	7.9	8.5
<b>170+53</b>	0.9	1.2	1.2	1.4	7.3	8.4	8.8	9.7
<b>157+51</b>	1.1	1.3	1.4	1.6	7.7	8.9	9.3	10.1

River Station (ft)	Channel Maximum Shear Stress (lb/sq ft)				Channel Maximum Velocity (ft/s)			
	10-Percent	2-Percent	1-Percent	0.2-Percent	10-Percent	2-Percent	1-Percent	0.2-Percent
<b>144+03</b>	0.7	0.7	0.7	0.7	6.2	6.5	6.5	6.5
<b>129+86</b>	0.7	0.6	0.6	0.5	6.2	6.3	6.2	6.1
<b>121+62</b>	1.3	1.7	1.9	2.0	8.6	10.3	11.0	11.7
<b>119+55</b>	1.4	1.8	2.0	2.4	9.0	10.6	11.3	12.6
<b>117+89</b>	1.9	2.6	3.0	4.1	10.1	12.3	13.4	15.8
<b>116+75</b>	0.9	1.4	1.6	2.2	7.4	9.2	10.1	12.0
<b>103+02</b>	1.2	1.4	1.4	1.8	7.9	8.9	9.1	10.6
<b>93+72</b>	2.4	3.0	3.2	2.6	10.7	12.5	13.2	12.4
<b>83+12</b>	0.2	0.3	0.3	0.4	3.7	4.3	4.6	5.2
<b>81+45</b>	0.2	0.3	0.4	0.6	3.6	4.8	5.3	6.4
<b>79+84</b>	0.5	0.8	0.9	1.3	5.2	6.8	7.6	9.3
<b>77+58</b>	0.6	0.7	0.8	0.9	6.0	6.7	7.0	7.7
<b>75+64</b>	0.7	0.7	0.7	0.7	6.2	6.4	6.5	6.7
<b>73+40</b>	0.6	0.6	0.6	0.6	5.7	6.0	6.1	6.2
<b>71+51</b>	0.7	0.8	0.8	0.6	6.2	6.9	6.9	6.1
<b>68+90</b>	0.7	0.7	0.6	0.6	6.2	6.2	6.1	6.1
<b>66+31</b>	0.9	1.1	1.1	1.2	6.7	7.7	8.0	8.6
<b>63+24</b>	0.6	0.8	0.9	1.2	5.9	7.0	7.4	8.5
<b>60+15</b>	1.3	1.3	1.3	1.3	8.1	8.5	8.7	9.1
<b>56+07</b>	0.8	0.9	0.9	0.9	6.7	7.2	7.3	7.8
<b>53+07</b>	0.6	0.6	0.7	0.8	5.7	6.3	6.6	7.5
<b>50+51</b>	0.6	0.7	0.8	0.8	5.7	6.6	6.9	7.4
<b>47+86</b>	0.6	0.8	0.8	0.8	6.0	7.0	7.3	7.6
<b>45+82</b>	0.7	0.9	0.9	1.0	6.4	7.4	7.7	8.2
<b>43+63</b>	0.6	0.9	1.0	1.2	6.2	7.4	7.9	8.8
<b>41+82</b>	0.7	0.9	1.0	1.3	6.2	7.5	8.0	9.2
<b>39+97</b>	0.6	0.8	1.0	1.3	6.0	7.2	7.8	9.2
<b>36+70</b>	0.4	0.4	0.4	0.5	5.1	5.2	5.4	5.8
<b>29+21</b>	0.4	0.5	0.5	0.5	4.9	5.8	6.0	6.2
<b>19+22</b>	0.1	0.2	0.2	0.2	3.2	3.3	3.5	3.7
<b>8+33</b>	0.1	0.1	0.1	0.1	2.7	2.8	2.8	3.0

River Station (ft)	Channel Maximum Shear Stress (lb/sq ft)				Channel Maximum Velocity (ft/s)			
	10-Percent	2-Percent	1-Percent	0.2-Percent	10-Percent	2-Percent	1-Percent	0.2-Percent
<b>2+79</b>	0.1	0.1	0.1	0.1	2.8	3.0	3.1	3.3

Table 11 summarizes the bank and channel stabilization strategies that could potentially be employed along Buffalo Creek in the vicinity of the Lexington Green neighborhood (RS 40+00 to 66+50) for the 1-percent AEP event. It should be noted that the identified bank and channel stabilization strategies are not intended to represent a fully comprehensive list and are based on the preliminary analysis performed in this study. Additional geomorphic research and advanced multi-dimensional open-water and ice-jam modeling is recommended to determine the most appropriate strategy for this reach of Buffalo Creek.

**Table 11. Bank and channel stabilization strategies along Buffalo Creek for the 1-percent AEP event.**

Measure Type	Treatment Type	Description of Measure
<b>Brush Mattress</b>	Staked only w/ rock riprap toe (grown)	Brush mattresses slow water velocities along the streambank and reduce erosion. The open space between the woody material allows for sediment deposition and water drainage. The build-up of sediment enhances the colonization of native plants.
<b>Coir Geotextile Roll</b>	Roll with Polypropylene rope mesh staked and with rock riprap toe	Coir geotextiles protect land surfaces, help with soil stabilization, promote vegetation growth in varying slopes, and provide erosion control.
<b>Gravel/Cobble</b>	12-inch	Cobble or gravel armor is used to protect a sloping bank against fluvial entrainment by flow in the stream or over the top of the bank.
<b>Soil Bioengineering</b>	Vegetated coir mat	Soil bioengineering methods have a common geotechnical benefit of providing root reinforcement in the soil and can help modify drainage patterns of the soil, help stabilize soils at steeper angles if desired, help keep grasses, and bushy vegetation in place resisting erosion, and support woody debris or other types of vegetation.
	Live brush mattress (grown)	
	Brush layering (initial/grown)	
<b>Boulder Clusters</b>	Small (>10-inch diameter) and larger	Boulder clusters can prevent large buildup of wood and reduce flood and bank erosion.

### **3 References**

Earle S. 2019. Physical Geology – 2nd Edition. British Columbia (CA): BCcampus Open Education; [accessed Jan 18, 2021]. Available from: <https://opentextbc.ca/physicalgeology2ed/>.

Federal Emergency Management Agency (FEMA). 2021. Flood Insurance Study, Erie County, New York (All Jurisdictions). Washington DC (US): United States Department of Homeland Security. Flood Insurance Study Number 36029CV001C-007C. Available from: FEMA.

Georgia Soil and Water Conservation Commission (GASWCC). 2000. Guidelines for Streambank Restoration. Atlanta (GA): Georgia Soil and Water Conservation Commission (GASWCC). Available from: <https://epd.georgia.gov>.

National Research Council (NRC). 2013. Levees and the National Flood Insurance Program: Improving Policies and Practices. Washington DC (US): The National Academies Press. Available from: [www.nap.edu](http://www.nap.edu).

[NYSDOT] New York State Department of Transportation. [Internet]. 2019. Bridge Point Locations & Select Attributes -New York State Department of Transportation. Albany (NY): New York State Department of Transportation, Structures Division; [updated 2019 Feb; cited 2022 Sept 29]. Available from: <https://gis.ny.gov>.

[NYSOITS] New York Office of Information Technology Services. 2019. New York State 1-meter DEM – LIDAR collection (QL2) for Erie, Genesee, and Livingston Counties New York Lidar; Hydro Flattened Bare Earth DEM. Albany (NY): New York Office of Information Technology Services. Available from: <https://gis.ny.gov/>.

[NYSOITS] New York State Office of Information Technology Services. 2021. 2021 One Foot 4 Band West Zone Orthoimagery. Albany (NY): New York State Office of Information Technology Services (NYSOITS), GIS Program Office. Available from: <http://gis.ny.gov/gateway/mg/>.

Ries KG III, Newson JK, Smith MJ, Guthrie JD, Steeves PA, Haluska TL, Kolb KR, Thompson RF, Santoro RD, Vraga HW. 2017. StreamStats, version 4. Reston (VA): United States Geologic Survey (USGS). Fact Sheet 2017-3046. Available from: <https://pubs.er.usgs.gov/publication/fs20173046>.

United States Army Corps of Engineers (USACE). 2001. Non-Structural Flood Damage Reduction Within the Corps of Engineers: What Districts Are Doing. Davis (CA): United States Army Corps of Engineers (USACE), National Flood Proofing Committee (NFPC). Available from: USACE.

United States Army Corps of Engineers (USACE). 2006. Engineering and Design – ICE ENGINEERING. Washington DC (US): United States Department of Defense (USDOD), United States Department of the Army, United States Army Corps of Engineers (USACE). EM 1110-2-1612. Available from: <https://www.publications.usace.army.mil>.

United States Army Corps of Engineers (USACE). 2016. Federal Interest Determination – Buffalo Creek - Lexington Green CAP 205. Buffalo (NY): United States Army Corps of Engineers (USACE), Buffalo District. Report No.: P2#443918.

United States Army Corps of Engineers (USACE). 2021. HEC-RAS River Analysis System. [computer software]. Version 6.2.0. Davis (CA): United States Army Corps of Engineers (USACE), Hydrologic Engineering Center (HEC).

United States Army Corps of Engineers (USACE). 2022. HEC-RAS 1D Sediment Transport User's Manual. Davis (CA): United States Army Corps of Engineers (USACE), Hydrologic Engineering Center (HEC). Available from: <https://www.hec.usace.army.mil/confluence/rasdocs/rassed1d>.

[USGS] United States Geologic Survey. 2021a. National Land Cover Database (NLCD) 2019 Land Cover Conterminous United States. Sioux Falls (SD): United States Department of the Interior. Available from: <https://www.mrlc.gov/>.

[USGS] United States Geologic Survey. [Internet]. 2022. New York StreamStats Application, version 4.10.1. Reston (VA): United States Geologic Survey (USGS); [updated 2022 Feb 18; cited 2022 Sept 29]. Available from: <https://streamstats.usgs.gov/ss/>.

Vermont Agency of Natural Resources (VTANR). 2004. Appendix O - Vermont Stream Geomorphic Assessment. In: Stream Geomorphic Assessment Handbooks. Montpelier (VT): Vermont Agency of Natural Resources (VTANR). Available from: <https://dec.vermont.gov/>.

Attachment C  
**Field Notes**


November 2nd - Buffalo Creek field  
work

Personnel - Lexi Hackford & Michelle  
McEntire

Benchmark was sill #5 - crest elevation  
at 585.7' based on USACE Document  
attached

Survey Point #1	BS	HI	FS	ELEV.	Description
*	14.71			585.7'	BM = Crest of sill #5
*	400.40'		15.8'	584.60'	Bottom of Creek (upstream of sill)
*			16.0'	584.4'	Bottom of Creek (downstream of sill)
			13.5'	586.9'	Bankfull Elev. (Top Bank Zone)
			11.3'	589.1'	overbank Elev. (Top of overbank)
			4.5'	595.9'	upland Elev. (where surveyor laser was.)

\* These water bottom elevations were taken  
from 30'-40' out into the water, with  
Michelle standing on the sill.



#### Step 3 – Bank Soil Composition

18.0'

**Instructions:** Visually and tactiley (i.e., using your hands / trowel) assess the relative size of the bank material. Record the type of stratification using the Soil Stratification in the figure below. Assign percent of sub-reach length to each material category. Note that cohesive banks are composed of soil, which has a certain percentage of silt and clay. Non-cohesive banks lack silt and clay, though can be a mixture of sands, gravel, cobbles, etc. Table 1 contains descriptions and lengths associated with each sediment class. Using Figure 1, columns 3 and 4 as reference for recording observations on bank stratification and composition.

GPS enabled pictures should be taken from a head on view that clearly shows any stratification.

Table 1. Grain size descriptions

Type	Cohesive		Non-Cohesive		
	Silt / Clay (soil)	Sand	Gravel	Cobble	Boulder
Grain Size	< 0.062 mm	0.063 to 2 mm	2 to 64 mm	64 to 256 mm	256 + mm
Description	Fine texture, cohesive, smooth when rubbed between fingers	Fine sugar to kosher salt sized particles	Peppercorn to egg sized	Baseball to grapefruit sized	Melon sized and larger

#### Step 4 – Bank Angle and Shape

**Instructions:** The bank angle categories are as follows: Mild ( $0^\circ$ - $30^\circ$ ), Moderate ( $30^\circ$ - $60^\circ$ ), Steep ( $60^\circ$ - $90^\circ$ ), and Overhang ( $> 90^\circ$ ). Evaluate percent of each sub-reach having each bank angle category. Bank Shape is focused on the potential for or evidence of erosion. Record the "shape" using Figure 1, column 2.

The top of Sill #5 was used as the benchmark for the second survey location.

**Survey Point #2**

<u>BS</u>	<u>HT</u>	<u>FS</u>	<u>Elev.</u>	<u>Description</u>
12.8'			585.7'	BM = Crest of Sill #5
	598.50'			
		9.9'	588.6'	Bottom of creek right @ edge
		8.7'	589.8'	Top of bank
0.8'		591.7'		Bankfull Elev. (Top of Bank Zone)
			594.4'	Overbank Elev. (where survey laser was)

Unfortunately, no length measurements were taken @ this spot due to the density of the trees & grass.

There wasn't a clear overbank, transitional & upland zone. One zone covered all three of zones & was very gradually sloping.

To get to the next creek survey location, we needed to use an intermediate survey location to get us down the creek.

<u>BS</u>	<u>HI</u>	<u>FS</u>	Elev.	<u>Description</u>
598.50'	4.9'	591.6'	591.6'	location / spot where survey equip. will be moved to.

Survey equipment was now moved to this location. Instrument Height was 4.2'. To get to the next creek survey location, we needed to move the survey equip. again.

<u>BS</u>	<u>HI</u>	<u>FS</u>	Elev.	<u>Description</u>
= 591.6' + 4.2'	5.7'	590.1'	= 595.8'	location / spot where the survey equip. was moved to.

(Survey location #3)

<u>BS</u>	<u>HI</u>	<u>FS</u>	<u>ELEV.</u>	<u>Description</u>
<i>(Survey location #4)</i>			= 590.1' + 4.2' = 594.3'	
			12.8'    581.5'	In the water along the bank
			10.8'    583.5'	Bankfull Elev. ( <sup>Top of</sup> <sup>Bank zone</sup> )
			7.1'    587.2'	overbank Elev. (Top of overbank)
			5.6'    588.7'	Upland Elev. (closer to where the survey equip. was)




Figure 2: Stream Zones

## Step 3 – Bank Soil Composition

62.0'

**Instructions:** Visually and tactiley (i.e., using your hands / trowel) assess the relative size of the bank material. Record the type of stratification using the Soil Stratification in the figure below. Assign percent of sub-reach length to each material category. Note that cohesive banks are composed of soil, which has a certain percentage of silt and clay. Non-cohesive banks lack silt and clay, though can be a mixture of sands, gravel, cobbles, etc. Table 1 contains descriptions and lengths associated with each sediment class. Using Figure 1, columns 3 and 4 as reference for recording observations on bank stratification and composition.

**GPS enabled pictures should be taken from a head on view that clearly shows any stratification.**

Table 1. Grain size descriptions

<b>Cohesive</b>		<b>Non-Cohesive</b>			
Type	Silt / Clay (soil)	Sand	Gravel	Cobble	Boulder
<b>Grain Size</b>	< 0.062 mm	0.063 to 2 mm	2 to 64 mm	64 to 256 mm	256 + mm
<b>Description</b>	Fine texture, cohesive, smooth when rubbed between fingers	Fine sugar to kosher salt sized particles	Peppercorn to egg sized	Baseball to grapefruit sized	Melon sized and larger

## Step 4 – Bank Angle and Shape

**Instructions:** The bank angle categories are as follows: Mild ( $0^\circ$ - $30^\circ$ ), Moderate ( $30^\circ$ - $60^\circ$ ), Steep ( $60^\circ$ - $90^\circ$ ), and Overhang ( $> 90^\circ$ ). Evaluate percent of each sub-reach having each bank angle category. Bank Shape is focused on the potential for or evidence of erosion. Record the "shape" using Figure 1, column 2.

# Stream Assessment Protocol Form

Step 1 — Wollman Pebble Count — use additional form

Location 1

Step 2 — Bank Vegetation Assessment: Record Percentage of Bank Covered by Ground Cover, record presence of absence of roots in, on or exposed.

Zone	Percent Coverage	Description
Bank	90/10	grasses, bushes / Rock
Stream Edge	100%	grasses
Overbank	90/10	few exposed roots grasses, bushes / Rock

Step 3 — Bank Soil Assessment: Count the total number of stratifications, record the total and then complete the table to record the type from Table 1 of the instructions and description of relevant features.

Number of total Stratifications 2

Stratification No.	Type	Description
1 (bottom)	cohesive	dark, clay /
2	boulder	boulders, patches that look like concrete

**Step 4 – Bank Angle:** Select one of the following and record the type in the space provided

Bank Angle Type	Check the appropriate One Below
Mild ( $0^\circ$ - $30^\circ$ )	
Moderate ( $30^\circ$ - $60^\circ$ )	<input checked="" type="checkbox"/>
Steep ( $60^\circ$ - $90^\circ$ )	
Overhang ( $> 90^\circ$ )	

Record the Type per the figure provided in the instructions Medium

**Step 5 – Evidence of Bank Failure / Bed Stability:** Selected one of the following and record the type and provide and relevant description.

Bank Angle Type	Check the appropriate One Below	Type	Description
Low ( $0$ – $25\%$ )			
Moderate ( $25$ – $50\%$ )	<input checked="" type="checkbox"/>	C	Some exposed roots, no fresh erosion
High ( $50$ – $75\%$ )			
Severe ( $70$ – $100\%$ )			

# Stream Assessment Protocol Form

Step 1 — Wellman Pebble Count — use additional form

Survey Point 2

Step 2 — Bank Vegetation Assessment: Record Percentage of Bank Covered by Ground Cover, record presence of absence of roots in, on or exposed.

Zone	Percent Coverage	Description
Bank	100	grasses, bushes
Stream Edge	100	grasses, bushes
Overbank	80/20	grasses/trees no exposed roots

Step 3 — Bank Soil Assessment: Count the total number of stratifications, record the total and then complete the table to record the type from Table 1 of the instructions and description of relevant features.

Number of total Stratifications \_\_\_\_\_

Stratification No.	Type	Description
1	cohesive	clay loam

**Step 4 – Bank Angle:** Select one of the following and record the type in the space provided

Bank Angle Type	Check the appropriate One Below
Mild (0°-30°)	
Moderate (30°-60°)	X
Steep (60°-90°)	
Overhang (> 90°)	

Record the Type per the figure provided in the instructions 1an

**Step 5 – Evidence of Bank Failure / Bed Stability:** Selected one of the following and record the type and provide and relevant description.

Bank Angle Type	Check the appropriate One Below	Type	Description
Low (0 – 25%)	X	C	no exposed roots or evidence of erosion
Moderate (25 – 50%)			
High (50 – 75%)			
Severe (70 – 100%)			

# Stream Assessment Protocol Form

Step 1 - Wellman Pebble Count - use additional form

Survey point 3 (<sup>location</sup><sub>#4 on Survey</sub>) <sup>gas</sup>

Step 2 - Bank Vegetation Assessment: Record Percentage of Bank Covered by Ground Cover, record presence of absence of roots in, on or exposed.

Zone	Percent Coverage	Description
Bank	70/30	70% grasses 30% dirt/rock trail a few roots exposed from overbank trees
Stream Edge	90/10	grasses/rock
Overbank	90/10	grasses/trees no exposed roots

Step 3 - Bank Soil Assessment: Count the total number of stratifications, record the total and then complete the table to record the type from Table 1 of the instructions and description of relevant features.

Number of total Stratifications 1

Stratification No.	Type	Description
1	Cohesive	Clay loam with scattered boulders

**Step 4 – Bank Angle:** Select one of the following and record the type in the space provided

Bank Angle Type	Check the appropriate One Below
Mild (0°-30°)	X
Moderate (30°-60°)	
Steep (60°-90°)	
Overhang (> 90°)	

Record the Type per the figure provided in the instructions Low

**Step 5 – Evidence of Bank Failure / Bed Stability:** Selected one of the following and record the type and provide and relevant description.

Bank Angle Type	Check the appropriate One Below	Type	Description
Low (0 – 25%)	X	<del>A</del>	minor root exposure (single) tree
Moderate (25 – 50%)			
High (50 – 75%)			
Severe (70 – 100%)			

Attachment D  
[\*\*Flood Bench Sectional View\*\*](#)



PLAN VIEW


100 0 100  
SCALE: 1"=100'

LEGEND

- WALKING TRAIL TO BE RESTORED
- BOUNDARY OF FLOODPLAIN
- PROPERTY LINE

NOTES

1. DESIGN REQUIREMENTS FROM NATIONAL GRID WILL BE COORDINATED DURING THE FINAL DESIGN PHASE. BASED ON HISTORICAL PROJECTS, NATIONAL GRID USUALLY REQUIRES CLEARANCE AROUND THE ELECTRICAL TOWERS FOR ACCESS AND MAINTENANCE.
2. LOCATION AND DESIGN OF THE WALKING TRAIL WILL BE DISCUSSED AND COMPLETED DURING THE FINAL DESIGN PHASE. FOR THE PRELIMINARY DESIGN PHASE IT IS ASSUMED THE TRAIL WOULD BE RESTORED IN A SIMILAR LOCATION TO THE EXISTING.



TYPICAL SECTION

100 0 100 10' 0 10'  
SCALE HORIZ. 1"=100' SCALE VERT. 1"=10'

IT IS A VIOLATION OF LAW FOR ANY PERSON  
UNLESS ACTING UNDER THE DIRECTION OF A  
LICENSED ENGINEER, TO ALTER THIS DOCUMENT.

THIS DRAWING WAS PREPARED AT THE SCALE INDICATED. INACCURACIES IN THE STATED SCALE MAY BE INTRODUCED  
WHEN DRAWINGS ARE REPRODUCED BY ANY MEANS. USE THE GRAPHIC SCALE BAR TO DETERMINE THE ACTUAL SIZE.  
DRAWING IS NOT SCALABLE IF NO SCALE BAR IS PRESENT.

PRELIMINARY  
NOT FOR  
CONSTRUCTION  
DATE: 12/19/2022

CLIENT  
BUFFALO NIAGARA  
WATERKEEPER

A	12/19/22	DRAFT 30% DESIGN PACKAGE	SG
NO.	DATE	REVISION	INT.

DESIGNER / PROFESSIONAL ENGINEER RESPONSIBLE  
S. GANNON  
PROJECT NO.  
1940102804  
333 WEST WASHINGTON ST., SYRACUSE, NY 13202  
315-956-6100  
CHECKED BY  
M. MCENTIRE  
DRAWN BY  
C. ERICKSON  
DATE  
DECEMBER 2022


RAMBOLL AMERICAS ENGINEERING SOLUTIONS, INC.  
PROJECT  
FEASIBILITY AND DESIGN OF FLOODPLAIN  
RECONNECTION OF BUFFALO CREEK  
ADDRESS  
BUFFALO, NEW YORK



SHEET DESCRIPTION  
FLOOD BENCH - PLAN & TYPICAL SECTION  
DRAWING LOCATION

C-101

Attachment E  
**Canisius High School Development Project**



- Approx. Location of Baseball Diamonds
- Approx. Location of Tennis Courts
- Approx. Location of Practice Field
- Proposed Flood Bench Footprint

**BUFFALO CREEK FLOODPLAIN  
RECONNECTION STUDY**  
**APROXXIMATE LOCATION OF NEW CANISIUS  
HIGH SCHOOL BASEBALL DIAMONDS**

RAMBOLL AMERICAS  
ENGINEERING SOLUTIONS, INC.  
A RAMBOLL COMPANY

West Seneca  
New York

**RAMBOLL**

Attachment F  
[HEC-RAS Model Simulation Output](#)

# Feasibility & Design of Floodplain Reconnection of Buffalo Creek

1-D HEC-RAS Hydraulic & Hydrologic Model - Existing & Proposed Conditions  
Buffalo Creek - Town of West Seneca, Erie County, NY  
Ramboll Americas Engineering Solutions, Inc.

December 20, 2022

## Contents

FEMA Effective Model . . . . .	3
Existing Conditions Model . . . . .	13
FEMA Effective versus Existing Conditions Models . . . . .	30
Flood Scenario #1 . . . . .	32
Flood Scenario #2 . . . . .	38
Flood Scenario #3 . . . . .	44
Flood Scenario #4 . . . . .	50
Flood Scenario #5 . . . . .	56
Flood Scenario #6 . . . . .	62
Flood Scenario #7 . . . . .	68
Flood Scenario #8 . . . . .	74
Flood Scenario #9 . . . . .	80

## FEMA Effective Model

Plan: Effective\_FEMA\_BC  
Geometry: Effective\_FEMA\_BC  
Steady Flow Data: FEMA FIS 1-Percent  
Date: December 2022




Figure 1: Effective FEMA Profile Plot




Figure 2: Effective FEMA Model Terrain Map




Figure 3: Effective FEMA Model Aerial Map




Figure 4: Effective FEMA Model Street Map




Figure 5: Effective FEMA Model Land Cover Map




Figure 6: FEMA FIS Steady Flow Data

Table 1: Effective FEMA HEC-RAS Output

Alternative	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl
Effective FEMA	20473	1-Percent	16000	621.4	635.1	630.06	636.15	0.002421	8.44	2339.85	364.14	0.42
Effective FEMA	19313	1-Percent	16000	620.4	631.8	629.79	633.18	0.002643	9.96	2270.58	556.38	0.56
Effective FEMA	18263	1-Percent	16000	617.6	629.86		630.33	0.002285	6.2	3585.57	571.84	0.34
Effective FEMA	17053	1-Percent	16000	615.5	628.01		628.38	0.001161	5.14	3992.91	627.27	0.29
Effective FEMA	15733	1-Percent	16000	612.8	625.18		625.8	0.003874	6.48	2710.14	374.15	0.38
Effective FEMA	14399	1-Percent	16000	610.3	623.27		623.45	0.000921	3.37	4984.12	692.91	0.2
Effective FEMA	12984	1-Percent	16000	608.9	622.13	615.52	622.31	0.000711	3.66	6304.66	1416.74	0.2
Effective FEMA	11955	1-Percent	16000	604.9	618.32	615.38	620.71	0.003356	12.42	1320.64	138.65	0.64
Effective FEMA	11899	1-Percent	16000	605.5	618.21	614.87	620.48	0.002946	12.09	1323.08	134.91	0.61
Effective FEMA	11850		Bridge									
Effective FEMA	11826	1-Percent	16000	605.5	617.5	614.88	620.06	0.003606	12.85	1245.2	136.86	0.67
Effective FEMA	11682	1-Percent	16000	602.4	617.5	612.81	618.99	0.003836	9.81	1668.98	147.46	0.49
Effective FEMA	10330	1-Percent	16000	603.2	614.52		615.18	0.001918	6.9	3216.14	636.76	0.43
Effective FEMA	9376	1-Percent	16000	599.6	610.11	610.11	612.22	0.005103	12.63	2118.79	668.68	0.76
Effective FEMA	8312	1-Percent	16000	595.5	607.8	602.4	607.99	0.000636	4.11	5465.65	679.97	0.23
Effective FEMA	8081	1-Percent	16000	592.1	606.56	601.47	607.6	0.000513	8.19	1953.81	253.78	0.42
Effective FEMA	8050		Bridge									
Effective FEMA	8016	1-Percent	16000	592.1	606.36	601.5	607.44	0.000544	8.33	1919.76	292.29	0.43
Effective FEMA	7906	1-Percent	16000	595.2	606.33	602.64	607.26	0.001812	8.1	3055.94	898.65	0.46
Effective FEMA	7140	1-Percent	16000	594.7	603.3	602.43	604.88	0.006025	10.26	1845.29	853.03	0.74
Effective FEMA	6009	1-Percent	16000	588.7	599.49	596.72	600.55	0.002488	8.27	1961.97	334.24	0.52
Effective FEMA	4785	1-Percent	16000	582.8	597.84	592.13	598.55	0.001057	6.98	3137.3	1124.05	0.36
Effective FEMA	3686	1-Percent	16000	582.1	593.98	592.25	596.24	0.004861	12.06	1326.56	1152.57	0.73
Effective FEMA	2949	1-Percent	16000	576.6	592.66	587.34	593.56	0.00212	7.9	2612.01	756.55	0.39
Effective FEMA	1922	1-Percent	16000	573.7	591.46		591.81	0.001175	5.64	5434.96	927.57	0.27
Effective FEMA	866	1-Percent	16000	571.5	589.6	584.44	590.45	0.001302	8.04	3784.45	964.76	0.4
Effective FEMA	279	1-Percent	16000	571	588.89	583.32	589.71	0.001201	7.89	2887.44	564.69	0.39

Table 2: Effective FEMA with USGS StreamStats Discharges HEC-RAS Output

Alternative	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.ChnL	Flow.Area	Top.Width	Froude...Chl	Scenario
Reach 1	20473	10-Percent	7990	621.4	631.86	627.21	632.43	0.001879	6.06	1357.15	185.89	0.36	Effective FEMA (USGS)
Reach 1	20473	2-Percent	11800	621.4	633.59	628.68	634.42	0.0022	7.37	1814.85	337.27	0.4	Effective FEMA (USGS)
Reach 1	20473	1-Percent	13600	621.4	634.28	629.31	635.2	0.002304	7.86	2050.38	348.33	0.41	Effective FEMA (USGS)
Reach 1	20473	0.2-Percent	18000	621.4	635.68	630.7	636.83	0.002546	8.93	2545.61	430.52	0.44	Effective FEMA (USGS)
Reach 1	19313	10-Percent	7990	620.4	629.04	626.42	629.94	0.002401	7.64	1188.06	371.96	0.5	Effective FEMA (USGS)
Reach 1	19313	2-Percent	11800	620.4	630.46	627.85	631.63	0.002578	8.93	1736.04	393.96	0.54	Effective FEMA (USGS)
Reach 1	19313	1-Percent	13600	620.4	631.06	628.77	632.32	0.002611	9.4	1973.09	435.77	0.55	Effective FEMA (USGS)
Reach 1	19313	0.2-Percent	18000	620.4	632.37	630.34	633.81	0.002617	10.3	2686.88	616.08	0.56	Effective FEMA (USGS)
Reach 1	18263	10-Percent	7990	617.6	626.71		627.1	0.002735	5.31	1958.7	490.71	0.35	Effective FEMA (USGS)
Reach 1	18263	2-Percent	11800	617.6	628.35		628.77	0.002437	5.76	2775.42	505.97	0.34	Effective FEMA (USGS)
Reach 1	18263	1-Percent	13600	617.6	629.03		629.47	0.002368	5.97	3120.59	528.93	0.34	Effective FEMA (USGS)
Reach 1	18263	0.2-Percent	18000	617.6	630.52		631	0.002222	6.37	3962.61	582.35	0.34	Effective FEMA (USGS)
Reach 1	17053	10-Percent	7990	615.5	624.82		625.08	0.00109	4.14	2123.56	507.77	0.28	Effective FEMA (USGS)
Reach 1	17053	2-Percent	11800	615.5	626.46		626.79	0.001151	4.7	3050.49	590.59	0.29	Effective FEMA (USGS)
Reach 1	17053	1-Percent	13600	615.5	627.15		627.5	0.00116	4.91	3461.86	606.87	0.29	Effective FEMA (USGS)
Reach 1	17053	0.2-Percent	18000	615.5	628.69		629.08	0.001157	5.31	4423.83	643.35	0.29	Effective FEMA (USGS)
Reach 1	15733	10-Percent	7990	612.8	622.06		622.48	0.004504	5.23	1595.1	339.76	0.38	Effective FEMA (USGS)
Reach 1	15733	2-Percent	11800	612.8	623.62		624.15	0.004205	5.93	2138.64	356.94	0.39	Effective FEMA (USGS)
Reach 1	15733	1-Percent	13600	612.8	624.3		624.87	0.004065	6.19	2384.91	364.46	0.39	Effective FEMA (USGS)
Reach 1	15733	0.2-Percent	18000	612.8	625.87		626.53	0.003756	6.7	2969.53	381.71	0.38	Effective FEMA (USGS)
Reach 1	14399	10-Percent	7990	610.3	619.59		619.72	0.001125	2.94	2736.44	557.25	0.23	Effective FEMA (USGS)
Reach 1	14399	2-Percent	11800	610.3	621.42		621.58	0.001029	3.18	3784.79	603.21	0.21	Effective FEMA (USGS)
Reach 1	14399	1-Percent	13600	610.3	622.23		622.39	0.000985	3.27	4284.67	642.12	0.21	Effective FEMA (USGS)
Reach 1	14399	0.2-Percent	18000	610.3	624.06		624.24	0.000889	3.45	5542.19	730.19	0.2	Effective FEMA (USGS)
Reach 1	12984	10-Percent	7990	608.9	617.84	613.62	618.05	0.001233	3.67	2389.78	893.91	0.25	Effective FEMA (USGS)
Reach 1	12984	2-Percent	11800	608.9	620.02	614.63	620.21	0.000912	3.67	4326.06	1181.3	0.22	Effective FEMA (USGS)
Reach 1	12984	1-Percent	13600	608.9	620.95	615.06	621.13	0.000811	3.66	5176.31	1272.6	0.21	Effective FEMA (USGS)
Reach 1	12984	0.2-Percent	18000	608.9	623.06	615.87	623.2	0.000601	3.52	8370.15	1572.53	0.18	Effective FEMA (USGS)
Reach 1	11955	10-Percent	7990	604.9	615.01	612.1	616.18	0.002568	8.69	924.84	115.44	0.53	Effective FEMA (USGS)
Reach 1	11955	2-Percent	11800	604.9	616.75	613.77	618.5	0.002969	10.6	1129.59	119.54	0.59	Effective FEMA (USGS)
Reach 1	11955	1-Percent	13600	604.9	617.45	614.48	619.47	0.003147	11.42	1214.02	121.18	0.61	Effective FEMA (USGS)
Reach 1	11955	0.2-Percent	18000	604.9	619.05	616.1	621.72	0.003466	13.14	1411.27	174.44	0.66	Effective FEMA (USGS)
Reach 1	11899	10-Percent	7990	605.5	614.93	611.65	616	0.002119	8.3	962.79	130.86	0.49	Effective FEMA (USGS)
Reach 1	11899	2-Percent	11800	605.5	616.66	613.28	618.28	0.002537	10.24	1152.61	132.99	0.56	Effective FEMA (USGS)
Reach 1	11899	1-Percent	13600	605.5	617.35	613.99	619.25	0.002724	11.07	1228.72	133.85	0.58	Effective FEMA (USGS)
Reach 1	11899	0.2-Percent	18000	605.5	618.92	615.6	621.48	0.003076	12.84	1401.69	135.79	0.63	Effective FEMA (USGS)
Reach 1	11850	Bridge											Effective FEMA (USGS)
Reach 1	11826	10-Percent	7990	605.5	614.61	611.66	615.77	0.002395	8.61	928.14	131.85	0.52	Effective FEMA (USGS)
Reach 1	11826	2-Percent	11800	605.5	616.19	613.28	617.97	0.002953	10.71	1101.34	134.59	0.6	Effective FEMA (USGS)
Reach 1	11826	1-Percent	13600	605.5	616.79	614	618.9	0.003231	11.65	1167.3	135.63	0.63	Effective FEMA (USGS)
Reach 1	11826	0.2-Percent	18000	605.5	618.02	615.6	620.99	0.003927	13.82	1302.64	137.77	0.71	Effective FEMA (USGS)
Reach 1	11682	10-Percent	7990	602.4	614.52	609.67	615.17	0.002389	6.46	1244.8	137.5	0.37	Effective FEMA (USGS)
Reach 1	11682	2-Percent	11800	602.4	616.13	611.29	617.16	0.003083	8.14	1470.57	142.89	0.43	Effective FEMA (USGS)
Reach 1	11682	1-Percent	13600	602.4	616.75	611.96	617.98	0.00341	8.88	1560.12	144.97	0.46	Effective FEMA (USGS)

Table 2: Effective FEMA with USGS StreamStats Discharges HEC-RAS Output (*continued*)

Alternative	River.Sta	Profile	Q.Total	Min.Ch.El	W.S.Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl	Scenario
Reach 1	11682	0.2-Percent	18000	602.4	618.05	613.45	619.78	0.0042	10.57	1754.16	166.09	0.52	Effective FEMA (USGS)
Reach 1	10330	10-Percent	7990	603.2	611.97		612.43	0.001675	5.51	1681.17	500.21	0.41	Effective FEMA (USGS)
Reach 1	10330	2-Percent	11800	603.2	613.38		613.93	0.001754	6.17	2513.69	604.81	0.41	Effective FEMA (USGS)
Reach 1	10330	1-Percent	13600	603.2	613.93		614.52	0.001803	6.46	2844.33	615.96	0.42	Effective FEMA (USGS)
Reach 1	10330	0.2-Percent	18000	603.2	615.03		615.73	0.001957	7.17	3547.28	655.76	0.43	Effective FEMA (USGS)
Reach 1	9376	10-Percent	7990	599.6	606.57	606.57	609.01	0.010011	12.55	651.58	155	0.98	Effective FEMA (USGS)
Reach 1	9376	2-Percent	11800	599.6	608.69	608.69	610.92	0.006184	12.33	1297.68	464.97	0.81	Effective FEMA (USGS)
Reach 1	9376	1-Percent	13600	599.6	609.35	609.35	611.54	0.005661	12.51	1638.94	592.59	0.79	Effective FEMA (USGS)
Reach 1	9376	0.2-Percent	18000	599.6	610.54	610.54	612.73	0.005125	13.07	2398.05	784.81	0.77	Effective FEMA (USGS)
Reach 1	8312	10-Percent	7990	595.5	604.23	600.89	604.39	0.000756	3.61	3135.86	632.92	0.25	Effective FEMA (USGS)
Reach 1	8312	2-Percent	11800	595.5	606.11	601.75	606.28	0.000667	3.83	4339.99	653.38	0.23	Effective FEMA (USGS)
Reach 1	8312	1-Percent	13600	595.5	606.9	602.03	607.08	0.000643	3.93	4860.2	665.8	0.23	Effective FEMA (USGS)
Reach 1	8312	0.2-Percent	18000	595.5	608.51	602.74	608.71	0.000631	4.25	5952.7	691.15	0.23	Effective FEMA (USGS)
Reach 1	8081	10-Percent	7990	592.1	603.74	599	604.19	0.000323	5.4	1479.58	233.07	0.32	Effective FEMA (USGS)
Reach 1	8081	2-Percent	11800	592.1	605.28	600.29	606	0.000411	6.79	1738.93	244.39	0.37	Effective FEMA (USGS)
Reach 1	8081	1-Percent	13600	592.1	605.91	600.81	606.75	0.000449	7.38	1844.06	248.98	0.39	Effective FEMA (USGS)
Reach 1	8081	0.2-Percent	18000	592.1	607.06	602.02	608.27	0.000565	8.84	2037.19	257.42	0.45	Effective FEMA (USGS)
Reach 1	8050	Bridge											Effective FEMA (USGS)
Reach 1	8016	10-Percent	7990	592.1	603.66	598.99	604.12	0.000333	5.45	1466.03	233.94	0.33	Effective FEMA (USGS)
Reach 1	8016	2-Percent	11800	592.1	605.15	600.28	605.88	0.000429	6.87	1717.01	264.05	0.38	Effective FEMA (USGS)
Reach 1	8016	1-Percent	13600	592.1	605.75	600.81	606.62	0.000472	7.48	1817.67	278.07	0.4	Effective FEMA (USGS)
Reach 1	8016	0.2-Percent	18000	592.1	606.81	602.03	608.07	0.000605	9.02	1995.37	302.82	0.46	Effective FEMA (USGS)
Reach 1	7906	10-Percent	7990	595.2	603.36	600.11	603.99	0.001755	6.38	1284.81	286.01	0.43	Effective FEMA (USGS)
Reach 1	7906	2-Percent	11800	595.2	604.97	601.4	605.78	0.001809	7.35	2134.95	730.62	0.45	Effective FEMA (USGS)
Reach 1	7906	1-Percent	13600	595.2	605.68	601.95	606.51	0.001742	7.58	2600.53	813.62	0.44	Effective FEMA (USGS)
Reach 1	7906	0.2-Percent	18000	595.2	606.83	603.33	607.83	0.001868	8.5	3426.86	972.67	0.47	Effective FEMA (USGS)
Reach 1	7140	10-Percent	7990	594.7	600.63	599.43	601.78	0.005315	8.59	930.3	195.64	0.68	Effective FEMA (USGS)
Reach 1	7140	2-Percent	11800	594.7	601.84	600.65	603.41	0.005866	10.09	1255.46	331.54	0.73	Effective FEMA (USGS)
Reach 1	7140	1-Percent	13600	594.7	602.64	601.26	604.13	0.006453	9.9	1550.2	623.25	0.75	Effective FEMA (USGS)
Reach 1	7140	0.2-Percent	18000	594.7	603.78	602.8	605.44	0.005804	10.58	2105.54	1027.17	0.73	Effective FEMA (USGS)
Reach 1	6009	10-Percent	7990	588.7	596.11	594.44	596.92	0.00342	7.23	1104.75	220.4	0.57	Effective FEMA (USGS)
Reach 1	6009	2-Percent	11800	588.7	598.07	595.55	598.94	0.002619	7.47	1588.04	256.46	0.52	Effective FEMA (USGS)
Reach 1	6009	1-Percent	13600	588.7	598.81	596.01	599.73	0.002442	7.72	1777.71	289.52	0.51	Effective FEMA (USGS)
Reach 1	6009	0.2-Percent	18000	588.7	600.33	597.14	601.42	0.00223	8.39	2205.07	681.84	0.5	Effective FEMA (USGS)
Reach 1	4785	10-Percent	7990	582.8	594.34	589.35	594.77	0.000978	5.29	1534.76	231.35	0.33	Effective FEMA (USGS)
Reach 1	4785	2-Percent	11800	582.8	596.46	590.78	597.03	0.000955	6.1	2102.1	335.63	0.34	Effective FEMA (USGS)
Reach 1	4785	1-Percent	13600	582.8	597.3	591.38	597.9	0.000921	6.32	2781.05	1006.88	0.34	Effective FEMA (USGS)
Reach 1	4785	0.2-Percent	18000	582.8	598.96	592.72	599.63	0.000915	6.91	4099.26	1398.68	0.34	Effective FEMA (USGS)
Reach 1	3686	10-Percent	7990	582.1	592.25	589.39	593.13	0.002378	7.52	1062.29	1099.81	0.5	Effective FEMA (USGS)
Reach 1	3686	2-Percent	11800	582.1	594.23	590.84	595.39	0.002416	8.63	1366.84	1160.4	0.52	Effective FEMA (USGS)
Reach 1	3686	1-Percent	13600	582.1	594.95	591.47	596.26	0.002498	9.18	1482.31	1182.96	0.53	Effective FEMA (USGS)
Reach 1	3686	0.2-Percent	18000	582.1	596.01	592.86	597.84	0.003036	10.88	1721.6	1404.47	0.6	Effective FEMA (USGS)
Reach 1	2949	10-Percent	7990	576.6	591.83	583.94	592.1	0.000685	4.29	2306.47	579.23	0.22	Effective FEMA (USGS)

Table 2: Effective FEMA with USGS StreamStats Discharges HEC-RAS Output (*continued*)

Alternative	River.Sta	Profile	Q.Total	Min.Ch.El	W.S.Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl	Scenario
Reach 1	2949	2-Percent	11800	576.6	593.8	585.69	594.18	0.000832	5.24	3153.84	1214.54	0.25	Effective FEMA (USGS)
Reach 1	2949	1-Percent	13600	576.6	594.52	586.46	594.96	0.000903	5.64	3583.47	1392.58	0.26	Effective FEMA (USGS)
Reach 1	2949	0.2-Percent	18000	576.6	596.08	587.96	596.42	0.00074	5.47	7419.76	1531.34	0.24	Effective FEMA (USGS)
Reach 1	1922	10-Percent	7990	573.7	591.52		591.61	0.000286	2.79	5489.86	928.94	0.13	Effective FEMA (USGS)
Reach 1	1922	2-Percent	11800	573.7	593.51		593.61	0.00031	3.18	7392.46	990.68	0.14	Effective FEMA (USGS)
Reach 1	1922	1-Percent	13600	573.7	594.23		594.34	0.000328	3.36	8115.49	1014.92	0.14	Effective FEMA (USGS)
Reach 1	1922	0.2-Percent	18000	573.7	595.71		595.83	0.000369	3.77	10136.03	1635.61	0.16	Effective FEMA (USGS)
Reach 1	866	10-Percent	7990	571.5	591.24	580.81	591.37	0.000179	3.24	5406.25	1379.65	0.15	Effective FEMA (USGS)
Reach 1	866	2-Percent	11800	571.5	593.22	582.7	593.36	0.000184	3.58	8790.22	2043.24	0.16	Effective FEMA (USGS)
Reach 1	866	1-Percent	13600	571.5	593.94	583.47	594.08	0.000188	3.72	10396.74	2429.35	0.16	Effective FEMA (USGS)
Reach 1	866	0.2-Percent	18000	571.5	595.42	585.09	595.56	0.00019	3.97	14133.19	2539.3	0.16	Effective FEMA (USGS)
Reach 1	279	10-Percent	7990	571	591.18	579.99	591.27	0.00012	2.78	4691.54	1038.63	0.13	Effective FEMA (USGS)
Reach 1	279	2-Percent	11800	571	593.17	581.73	593.26	0.00012	3.02	6871.17	1257.66	0.13	Effective FEMA (USGS)
Reach 1	279	1-Percent	13600	571	593.89	582.44	593.98	0.00012	3.1	7946.67	1792.75	0.13	Effective FEMA (USGS)
Reach 1	279	0.2-Percent	18000	571	595.36	584	595.46	0.00012	3.27	11127.4	2319.49	0.13	Effective FEMA (USGS)

## **Existing Conditions Model**

Plan: Existing\_Conditions\_UPDATE\_BC

Geometry: Existing\_Conditions\_UPDATE\_BC

Steady Flow Data: USGS BF,10,2,1,0.2-PERCENT-UPDATE-BC

Date: December 2022




Figure 7: Existing Conditions Model Terrain Map




Figure 8: Existing Conditions Model Aerial Map




Figure 9: Existing Conditions Model Street Map




Figure 10: Existing Conditions Model Land Cover Map




Figure 11: USGS StreamStats Steady Flow Data




Figure 12: Existing Conditions Profile Plot

Table 3: Existing Conditions HEC-RAS Output

Alternative	River.Sta	Profile	Q.Total	Min.Ch.El	W.S.Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.ChnL	Flow.Area	Top.Width	Froude...Chl
Existing (USGS)	20483	10-Percent	7990	621.4	631.44		632.23	0.00152	7.14	1149.93	159.75	0.42
Existing (USGS)	20483	2-Percent	11800	621.4	633.13		634.27	0.001801	8.71	1502.7	283.71	0.47
Existing (USGS)	20483	1-Percent	13600	621.4	633.75		635.03	0.001907	9.3	1683.22	292.19	0.49
Existing (USGS)	20483	0.2-Percent	18000	621.4	635.05		636.62	0.002117	10.53	2068.6	300.59	0.52
Existing (USGS)	19313	10-Percent	7990	620.4	628.71		629.8	0.002908	8.44	1044.14	306.61	0.56
Existing (USGS)	19313	2-Percent	11800	620.4	630.2		631.56	0.003003	9.73	1584.75	383.6	0.58
Existing (USGS)	19313	1-Percent	13600	620.4	630.82		632.26	0.002981	10.15	1839	441.87	0.59
Existing (USGS)	19313	0.2-Percent	18000	620.4	632.18	630.62	633.75	0.002879	10.93	2522.14	587.78	0.59
Existing (USGS)	18244	10-Percent	7990	617.6	626.65		627.29	0.001757	6.95	1777.22	467.86	0.44
Existing (USGS)	18244	2-Percent	11800	617.6	628.34		629.05	0.001639	7.65	2590.92	496.45	0.44
Existing (USGS)	18244	1-Percent	13600	617.6	629.04		629.77	0.001597	7.92	2942.21	525.34	0.44
Existing (USGS)	18244	0.2-Percent	18000	617.6	630.55		631.34	0.001514	8.46	3805.28	582.51	0.44
Existing (USGS)	17053	10-Percent	7990	615.5	624.35		625.09	0.001916	7.31	1642.27	449.95	0.46
Existing (USGS)	17053	2-Percent	11800	615.5	625.99		626.9	0.001963	8.38	2445.93	516.05	0.48
Existing (USGS)	17053	1-Percent	13600	615.5	626.65		627.63	0.001977	8.8	2794.51	525.92	0.49
Existing (USGS)	17053	0.2-Percent	18000	615.5	628.13		629.25	0.001985	9.65	3589.78	557.64	0.5
Existing (USGS)	15751	10-Percent	7990	612.8	621.48		622.31	0.002376	7.65	1275.64	297.31	0.5
Existing (USGS)	15751	2-Percent	11800	612.8	622.94		624	0.002512	8.9	1759.86	349.52	0.53
Existing (USGS)	15751	1-Percent	13600	612.8	623.57		624.72	0.002518	9.34	1985.58	360.25	0.54
Existing (USGS)	15751	0.2-Percent	18000	612.8	625.09		626.39	0.002415	10.12	2545.4	374.73	0.54
Existing (USGS)	14403	10-Percent	7990	610.3	619.25		619.71	0.001482	6.2	2234.3	539.57	0.4
Existing (USGS)	14403	2-Percent	11800	610.3	621.12		621.56	0.001194	6.45	3263.7	572.17	0.37
Existing (USGS)	14403	1-Percent	13600	610.3	621.93		622.37	0.001093	6.52	3734.74	594.17	0.36
Existing (USGS)	14403	0.2-Percent	18000	610.3	623.88		624.29	0.00087	6.53	5014.3	708.31	0.33
Existing (USGS)	12986	10-Percent	7990	608.9	617.09		617.64	0.001416	6.23	1736.27	495.45	0.39
Existing (USGS)	12986	2-Percent	11800	608.9	619.49		620	0.001016	6.31	3498.64	888.93	0.35
Existing (USGS)	12986	1-Percent	13600	608.9	620.52		620.99	0.000867	6.22	4438.68	920.06	0.33
Existing (USGS)	12986	0.2-Percent	18000	608.9	622.83		623.23	0.000643	6.07	6623.01	966.59	0.29
Existing (USGS)	12162	10-Percent	7990	604.9	614.98		616.12	0.002284	8.62	955.8	117.56	0.5
Existing (USGS)	12162	2-Percent	11800	604.9	617.01		618.63	0.002504	10.32	1205.03	134.66	0.55
Existing (USGS)	12162	1-Percent	13600	604.9	617.86		619.71	0.002579	11.01	1326.02	158.14	0.56
Existing (USGS)	12162	0.2-Percent	18000	604.9	620.19	615.89	622.17	0.002287	11.67	2144.46	464.7	0.54
Existing (USGS)	11955	10-Percent	7990	605.5	614.34	611.72	615.59	0.00286	8.95	895.71	113.2	0.56
Existing (USGS)	11955	2-Percent	11800	605.5	616.31	613.35	618.05	0.003008	10.62	1120.3	115.54	0.59
Existing (USGS)	11955	1-Percent	13600	605.5	617.14	614.06	619.11	0.003059	11.29	1217.31	121.14	0.6
Existing (USGS)	11955	0.2-Percent	18000	605.5	619.16	615.65	621.59	0.003014	12.55	1459.52	154.88	0.62
Existing (USGS)	11860 Union Rd	Bridge										
Existing (USGS)	11789	10-Percent	7990	605.5	613.21	611.45	614.81	0.004409	10.13	789.56	110.22	0.66
Existing (USGS)	11789	2-Percent	11800	605.5	614.77	613.12	617.12	0.005034	12.32	962.04	111.86	0.73
Existing (USGS)	11789	1-Percent	13600	605.5	615.3	613.85	618.08	0.005496	13.38	1021.68	112.36	0.77
Existing (USGS)	11789	0.2-Percent	18000	605.5	616.4	615.46	620.28	0.00662	15.82	1147.98	117.14	0.86
Existing (USGS)	11675	10-Percent	7990	602.4	613.3		614.14	0.001656	7.39	1090.08	125.8	0.43
Existing (USGS)	11675	2-Percent	11800	602.4	614.93		616.25	0.002073	9.24	1299.03	129.76	0.5
Existing (USGS)	11675	1-Percent	13600	602.4	615.51		617.09	0.002307	10.09	1374.63	131.08	0.53

Table 3: Existing Conditions HEC-RAS Output (*continued*)

Alternative	River.Sta	Profile	Q.Total	Min.Ch.El	W.S.Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.ChnL	Flow.Area	Top.Width	Froude...Chl
Existing (USGS)	11675	0.2-Percent	18000	602.4	616.75		618.98	0.00285	12.02	1539.74	137.59	0.6
Existing (USGS)	10302	10-Percent	7990	603.2	610.26		611.22	0.002817	7.94	1106.57	291.38	0.54
Existing (USGS)	10302	2-Percent	11800	603.2	611.87	609.46	613	0.002633	8.87	1797.88	548.48	0.54
Existing (USGS)	10302	1-Percent	13600	603.2	612.52	610.2	613.66	0.002497	9.09	2170.27	588.78	0.54
Existing (USGS)	10302	0.2-Percent	18000	603.2	613.23	612.13	614.7	0.003059	10.58	2588.13	602.95	0.6
Existing (USGS)	9372	10-Percent	7990	599.6	605.24	604.78	607.03	0.007893	10.72	748.14	158.9	0.86
Existing (USGS)	9372	2-Percent	11800	599.6	606.49	606.07	608.92	0.00795	12.53	955	197.18	0.89
Existing (USGS)	9372	1-Percent	13600	599.6	607	606.96	609.69	0.007957	13.23	1068.29	247.65	0.91
Existing (USGS)	9372	0.2-Percent	18000	599.6	608.87	608.87	611.04	0.005014	12.39	1721.36	525.34	0.75
Existing (USGS)	8312	10-Percent	7990	595.5	605.14		605.3	0.000447	3.66	3982.49	730.2	0.22
Existing (USGS)	8312	2-Percent	11800	595.5	606.69		606.91	0.000496	4.32	5182.56	800.71	0.24
Existing (USGS)	8312	1-Percent	13600	595.5	607.32		607.57	0.000514	4.59	5693.51	807.29	0.25
Existing (USGS)	8312	0.2-Percent	18000	595.5	608.74		609.04	0.000546	5.15	6853.89	828.65	0.26
Existing (USGS)	8145	10-Percent	7990	592.1	605.04	597.15	605.24	0.000278	3.63	2202.52	345.65	0.19
Existing (USGS)	8145	2-Percent	11800	592.1	606.47	598.29	606.82	0.000414	4.77	2471.67	453.22	0.23
Existing (USGS)	8145	1-Percent	13600	592.1	607.04	598.79	607.47	0.000477	5.27	2578.56	465.95	0.25
Existing (USGS)	8145	0.2-Percent	18000	592.1	608.27	599.9	608.91	0.000627	6.4	2810.89	492.36	0.29
Existing (USGS)	8049 Railroad Bridge	Bridge										
Existing (USGS)	7984	10-Percent	7990	592.1	604.61	599.55	605.03	0.000804	5.23	1554.94	372.48	0.3
Existing (USGS)	7984	2-Percent	11800	592.1	605.76	600.86	606.47	0.001171	6.83	1764.87	507.96	0.37
Existing (USGS)	7984	1-Percent	13600	592.1	606.17	601.43	607.05	0.00136	7.56	1841.3	526.78	0.41
Existing (USGS)	7984	0.2-Percent	18000	592.1	606.97	602.7	608.28	0.001866	9.29	1990.1	563.49	0.48
Existing (USGS)	7758	10-Percent	7990	595	604.09	600.48	604.59	0.001188	5.98	1571.37	590.44	0.37
Existing (USGS)	7758	2-Percent	11800	595	605.32	601.71	605.9	0.001253	6.73	2401.71	885.57	0.38
Existing (USGS)	7758	1-Percent	13600	595	605.76	602.23	606.36	0.001276	7	2722.65	917.78	0.39
Existing (USGS)	7758	0.2-Percent	18000	595	606.62	604.85	607.29	0.001392	7.72	3400.69	1141.81	0.41
Existing (USGS)	7564	10-Percent	7990	594.9	603.55		604.07	0.001331	6.15	1647.47	654.17	0.38
Existing (USGS)	7564	2-Percent	11800	594.9	604.89		605.36	0.001164	6.38	2709.59	899.14	0.37
Existing (USGS)	7564	1-Percent	13600	594.9	605.36		605.81	0.001127	6.48	3143.56	968.77	0.37
Existing (USGS)	7564	0.2-Percent	18000	594.9	606.27		606.71	0.001077	6.72	4186.33	1347.21	0.36
Existing (USGS)	7340	10-Percent	7990	594.8	603.1		603.51	0.001239	5.71	1796.74	632.06	0.37
Existing (USGS)	7340	2-Percent	11800	594.8	604.48		604.87	0.001105	6.03	2955.05	1060.08	0.36
Existing (USGS)	7340	1-Percent	13600	594.8	604.97		605.34	0.001032	6.05	3489.11	1124.56	0.35
Existing (USGS)	7340	0.2-Percent	18000	594.8	605.92		606.27	0.000944	6.16	4762.97	1555.32	0.34
Existing (USGS)	7151	10-Percent	7990	594.7	602.26		602.83	0.001746	6.18	1483.84	452.43	0.43
Existing (USGS)	7151	2-Percent	11800	594.7	603.59		604.23	0.001694	6.89	2380.89	921.79	0.43
Existing (USGS)	7151	1-Percent	13600	594.7	604.15		604.76	0.001543	6.88	3000.98	1347.09	0.42
Existing (USGS)	7151	0.2-Percent	18000	594.7	605.45		605.83	0.000991	6.07	5425.2	2124.72	0.34
Existing (USGS)	6890	10-Percent	7990	593	601.33	598.69	601.9	0.001834	6.22	1454.46	1740.54	0.43
Existing (USGS)	6890	2-Percent	11800	593	602.91	600.03	603.4	0.001356	6.2	2450.65	2170.96	0.39
Existing (USGS)	6890	1-Percent	13600	593	603.55	601.1	604.01	0.001183	6.1	2961	2253.58	0.37
Existing (USGS)	6890	0.2-Percent	18000	593	604.89	602.34	605.32	0.00096	6.05	4024.04	2355.92	0.34
Existing (USGS)	6631	10-Percent	7990	592	600	597.85	600.7	0.002435	6.7	1205.33	234.04	0.49
Existing (USGS)	6631	2-Percent	11800	592	601.48	598.95	602.37	0.002359	7.68	1623.36	394.71	0.5

Table 3: Existing Conditions HEC-RAS Output (*continued*)

Alternative	River.Sta	Profile	Q.Total	Min.Ch.El	W.S.Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.ChnL	Flow.Area	Top.Width	Froude...Chl
Existing (USGS)	6631	1-Percent	13600	592	602.08	599.43	603.05	0.00232	8.04	1823.38	528.99	0.51
Existing (USGS)	6631	0.2-Percent	18000	592	603.42	600.53	604.48	0.002135	8.57	2348.22	702.52	0.5
Existing (USGS)	6324	10-Percent	7990	590.5	598.97	595.72	599.5	0.001478	5.88	1400.44	263.72	0.39
Existing (USGS)	6324	2-Percent	11800	590.5	600.39	596.88	601.12	0.001634	7	1779.79	393.51	0.43
Existing (USGS)	6324	1-Percent	13600	590.5	600.97	597.36	601.8	0.001689	7.44	1938.67	449.81	0.44
Existing (USGS)	6324	0.2-Percent	18000	590.5	602.23	598.58	603.26	0.001812	8.41	2285.02	613.67	0.46
Existing (USGS)	6015	10-Percent	7990	588.7	596.99		597.94	0.003251	8.13	1099.3	283.66	0.58
Existing (USGS)	6015	2-Percent	11800	588.7	598.68		599.65	0.002567	8.49	1624.39	329.87	0.53
Existing (USGS)	6015	1-Percent	13600	588.7	599.36		600.35	0.00239	8.66	1856.92	357.28	0.52
Existing (USGS)	6015	0.2-Percent	18000	588.7	600.9		601.88	0.002007	8.86	2577.6	513.4	0.49
Existing (USGS)	5607	10-Percent	7990	587.3	595.55	592.95	596.15	0.001824	6.71	1344.94	274.28	0.44
Existing (USGS)	5607	2-Percent	11800	587.3	597.54	594.02	598.2	0.001489	7.14	2087.52	440.22	0.42
Existing (USGS)	5607	1-Percent	13600	587.3	598.34	594.71	598.99	0.001374	7.25	2438.43	444.34	0.41
Existing (USGS)	5607	0.2-Percent	18000	587.3	600.02	595.81	600.69	0.00123	7.61	3218.07	495.11	0.39
Existing (USGS)	5307	10-Percent	7990	585.8	594.85		595.32	0.001136	5.73	1523.04	273.7	0.36
Existing (USGS)	5307	2-Percent	11800	585.8	596.95		597.49	0.001006	6.29	2276.17	402.5	0.35
Existing (USGS)	5307	1-Percent	13600	585.8	597.75		598.33	0.000987	6.56	2601.53	409.9	0.35
Existing (USGS)	5307	0.2-Percent	18000	585.8	599.42		600.08	0.000993	7.23	3391.44	515.05	0.36
Existing (USGS)	5051	10-Percent	7990	584.3	594.2	590.41	594.7	0.001202	5.74	1436.22	206.59	0.36
Existing (USGS)	5051	2-Percent	11800	584.3	596.26	591.62	596.91	0.001151	6.57	1948.53	301.22	0.37
Existing (USGS)	5051	1-Percent	13600	584.3	597.06	592.13	597.76	0.001113	6.86	2225.73	360.37	0.37
Existing (USGS)	5051	0.2-Percent	18000	584.3	598.75	593.33	599.52	0.001078	7.39	2838.24	366.48	0.37
Existing (USGS)	4786	10-Percent	7990	582.8	593.61	589.12	594.17	0.001084	5.97	1354.02	162.68	0.35
Existing (USGS)	4786	2-Percent	11800	582.8	595.6	590.5	596.36	0.001161	7.07	1761.02	226.8	0.38
Existing (USGS)	4786	1-Percent	13600	582.8	596.36	591.06	597.2	0.001191	7.49	1953.77	261.47	0.39
Existing (USGS)	4786	0.2-Percent	18000	582.8	597.93	592.42	598.95	0.001261	8.38	2367.37	266.15	0.41
Existing (USGS)	4582	10-Percent	7990	582.7	593.03	589.02	593.66	0.001319	6.37	1278.39	165.23	0.38
Existing (USGS)	4582	2-Percent	11800	582.7	594.99	590.43	595.82	0.001372	7.45	1675.35	219.76	0.41
Existing (USGS)	4582	1-Percent	13600	582.7	595.71	591.03	596.65	0.001416	7.92	1836.98	225.28	0.42
Existing (USGS)	4582	0.2-Percent	18000	582.7	597.16	592.41	598.35	0.00156	9.01	2174.87	252.83	0.45
Existing (USGS)	4363	10-Percent	7990	582.5	592.55	588.33	593.14	0.001221	6.16	1312.26	164.05	0.37
Existing (USGS)	4363	2-Percent	11800	582.5	594.45	589.72	595.28	0.00134	7.37	1652.17	369.96	0.4
Existing (USGS)	4363	1-Percent	13600	582.5	595.14	590.3	596.08	0.00141	7.89	1836.59	549.17	0.42
Existing (USGS)	4363	0.2-Percent	18000	582.5	596.59	591.65	597.72	0.0015	8.82	2375.41	958.21	0.44
Existing (USGS)	4182	10-Percent	7990	582.4	592.31	588.27	592.91	0.001282	6.23	1296.47	164.95	0.38
Existing (USGS)	4182	2-Percent	11800	582.4	594.17	589.64	595.03	0.001413	7.48	1626.48	243.93	0.41
Existing (USGS)	4182	1-Percent	13600	582.4	594.83	590.22	595.81	0.001505	8.04	1777.42	377.88	0.43
Existing (USGS)	4182	0.2-Percent	18000	582.4	596.15	591.56	597.41	0.001703	9.23	2152.41	632.12	0.46
Existing (USGS)	3997	10-Percent	7990	582.3	592.12	587.76	592.67	0.001125	5.95	1352.94	190.66	0.36
Existing (USGS)	3997	2-Percent	11800	582.3	593.96	589.1	594.76	0.001283	7.22	1664.48	223.99	0.39
Existing (USGS)	3997	1-Percent	13600	582.3	594.59	589.64	595.53	0.001394	7.82	1802.75	281.59	0.41
Existing (USGS)	3997	0.2-Percent	18000	582.3	595.81	590.98	597.1	0.001689	9.23	2124.72	512.9	0.46
Existing (USGS)	3670	10-Percent	7990	582.1	591.97		592.32	0.000786	5.14	3197.67	1118.11	0.3
Existing (USGS)	3670	2-Percent	11800	582.1	594.03		594.34	0.000623	5.24	5655.63	1230.59	0.28

Table 3: Existing Conditions HEC-RAS Output (*continued*)

Alternative	River.Sta	Profile	Q.Total	Min.Ch.El	W.S.Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.ChnL	Flow.Area	Top.Width	Froude...Chl
Existing (USGS)	3670	1-Percent	13600	582.1	594.75		595.07	0.000605	5.39	6554.79	1256.34	0.28
Existing (USGS)	3670	0.2-Percent	18000	582.1	596.18		596.52	0.000604	5.81	8437.7	1373.85	0.28
Existing (USGS)	2921	10-Percent	7990	576.6	591.5		591.86	0.000498	4.85	1852.73	452.33	0.25
Existing (USGS)	2921	2-Percent	11800	576.6	593.39		593.87	0.000588	5.82	3296.29	1158.38	0.28
Existing (USGS)	2921	1-Percent	13600	576.6	594.11		594.6	0.000591	6.04	4255.27	1414.15	0.28
Existing (USGS)	2921	0.2-Percent	18000	576.6	595.64		596.08	0.000535	6.15	6446.61	1446.59	0.27
Existing (USGS)	1922	10-Percent	7990	573.7	591.43		591.52	0.000159	3.15	6696.9	1308.98	0.15
Existing (USGS)	1922	2-Percent	11800	573.7	593.4		593.49	0.000151	3.34	9344.27	1355.68	0.14
Existing (USGS)	1922	1-Percent	13600	573.7	594.12		594.22	0.000152	3.45	10348.69	1409.83	0.15
Existing (USGS)	1922	0.2-Percent	18000	573.7	595.61		595.71	0.00016	3.74	12703.76	1786.97	0.15
Existing (USGS)	833	10-Percent	7990	571.5	591.31		591.38	9.4e-05	2.65	5431.72	1295.17	0.11
Existing (USGS)	833	2-Percent	11800	571.5	593.29		593.36	8.9e-05	2.77	8382.02	1690.87	0.11
Existing (USGS)	833	1-Percent	13600	571.5	594.02		594.08	8.8e-05	2.82	9641.88	1774.35	0.11
Existing (USGS)	833	0.2-Percent	18000	571.5	595.51		595.58	8.7e-05	2.96	12526.76	2314.31	0.11
Existing (USGS)	279	10-Percent	7990	571	591.21	580.11	591.3	0.00012	2.8	4718.34	1042.68	0.13
Existing (USGS)	279	2-Percent	11800	571	593.19	581.81	593.28	0.00012	3.04	6888.45	1267.82	0.13
Existing (USGS)	279	1-Percent	13600	571	593.91	582.54	594	0.00012	3.12	7968.79	1787.95	0.13
Existing (USGS)	279	0.2-Percent	18000	571	595.4	584.12	595.5	0.00012	3.29	11205.39	2338.5	0.13

Table 4: Existing Conditions with FEMA FIS Discharges HEC-RAS Output

Alternative	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl	Scenario
Reach 1	20483	1-Percent	16000	621.4	634.49		635.94	0.002027	10	1902.02	297.38	0.51	Existing (FIS)
Reach 1	19313	1-Percent	16000	620.4	631.58		633.1	0.002931	10.61	2196.92	494.54	0.59	Existing (FIS)
Reach 1	18244	1-Percent	16000	617.6	629.89		630.65	0.001548	8.22	3422.39	571.57	0.44	Existing (FIS)
Reach 1	17053	1-Percent	16000	615.5	627.48		628.54	0.001986	9.29	3235.15	540.88	0.49	Existing (FIS)
Reach 1	15751	1-Percent	16000	612.8	624.42		625.65	0.002461	9.79	2296.03	369.77	0.54	Existing (FIS)
Reach 1	14403	1-Percent	16000	610.3	623.01		623.44	0.000972	6.57	4412.71	670.73	0.34	Existing (FIS)
Reach 1	12986	1-Percent	16000	608.9	621.83		622.25	0.000722	6.11	5663.96	949.63	0.3	Existing (FIS)
Reach 1	12162	1-Percent	16000	604.9	619.04	615.17	621.08	0.002549	11.65	1632.54	395.32	0.57	Existing (FIS)
Reach 1	11955	1-Percent	16000	605.5	618.24	614.93	620.48	0.003058	12.04	1348.04	142.01	0.61	Existing (FIS)
Reach 1	11860 Union Rd	Bridge											Existing (FIS)
Reach 1	11789	1-Percent	16000	605.5	615.92	614.75	619.3	0.006124	14.75	1092.44	114.72	0.82	Existing (FIS)
Reach 1	11675	1-Percent	16000	602.4	616.21		618.14	0.002611	11.17	1466.56	132.82	0.57	Existing (FIS)
Reach 1	10302	1-Percent	16000	603.2	612.96	611.35	614.27	0.002757	9.86	2431.17	596.02	0.57	Existing (FIS)
Reach 1	9372	1-Percent	16000	599.6	608.1	608.1	610.5	0.006044	12.77	1397.35	341.9	0.81	Existing (FIS)
Reach 1	8312	1-Percent	16000	595.5	608.11		608.39	0.000535	4.91	6334.83	819.39	0.26	Existing (FIS)
Reach 1	8145	1-Percent	16000	592.1	607.73	599.4	608.27	0.00056	5.91	2708.71	482.19	0.27	Existing (FIS)
Reach 1	8049 Railroad Bridge	Bridge											Existing (FIS)
Reach 1	7984	1-Percent	16000	592.1	606.64	602.14	607.74	0.00163	8.51	1927.64	539.94	0.45	Existing (FIS)
Reach 1	7758	1-Percent	16000	595	606.25	603.07	606.89	0.001339	7.4	3091.91	1001.87	0.4	Existing (FIS)
Reach 1	7564	1-Percent	16000	594.9	605.87		606.33	0.001108	6.65	3687.74	1186.97	0.37	Existing (FIS)
Reach 1	7340	1-Percent	16000	594.8	605.51		605.87	0.00099	6.14	4162.6	1389.44	0.34	Existing (FIS)
Reach 1	7151	1-Percent	16000	594.7	604.86		605.36	0.001255	6.55	4233.48	1966.17	0.38	Existing (FIS)
Reach 1	6890	1-Percent	16000	593	604.31	601.79	604.74	0.001046	6.06	3557.09	2330.32	0.35	Existing (FIS)
Reach 1	6631	1-Percent	16000	592	602.83	600	603.85	0.00223	8.37	2106.13	583.18	0.5	Existing (FIS)
Reach 1	6324	1-Percent	16000	590.5	601.66	598.06	602.61	0.001773	8.01	2127.67	511.63	0.45	Existing (FIS)
Reach 1	6015	1-Percent	16000	588.7	600.08		601.14	0.002345	9.05	2169.28	467.59	0.52	Existing (FIS)
Reach 1	5607	1-Percent	16000	587.3	599.05	595.34	599.77	0.001421	7.72	2758.5	462.26	0.42	Existing (FIS)
Reach 1	5307	1-Percent	16000	585.8	598.36		599.05	0.00115	7.34	2867.46	477.83	0.38	Existing (FIS)
Reach 1	5051	1-Percent	16000	584.3	597.56	592.8	598.4	0.001299	7.58	2405.07	362.45	0.4	Existing (FIS)
Reach 1	4786	1-Percent	16000	582.8	596.63	591.8	597.72	0.001508	8.55	2023.89	262.26	0.44	Existing (FIS)
Reach 1	4582	1-Percent	16000	582.7	595.66	591.81	596.97	0.001993	9.37	1825.8	224.88	0.49	Existing (FIS)
Reach 1	4363	1-Percent	16000	582.5	594.63	591.05	596.1	0.00232	9.81	1692.86	427.02	0.53	Existing (FIS)
Reach 1	4182	1-Percent	16000	582.4	593.98	590.96	595.62	0.002773	10.34	1587.04	209.32	0.57	Existing (FIS)
Reach 1	3997	1-Percent	16000	582.3	593.47	590.4	595.11	0.002773	10.29	1577.09	200.73	0.57	Existing (FIS)
Reach 1	3670	1-Percent	16000	582.1	593.5		594.22	0.001464	7.78	5004.32	1219.04	0.42	Existing (FIS)
Reach 1	2921	1-Percent	16000	576.6	591.4		592.85	0.002063	9.82	1804.93	424.55	0.51	Existing (FIS)
Reach 1	1922	1-Percent	16000	573.7	590.77		591.3	0.000865	7.13	5846.89	1291.38	0.34	Existing (FIS)
Reach 1	833	1-Percent	16000	571.5	589.95		590.47	0.000671	6.69	4020.65	913.78	0.3	Existing (FIS)
Reach 1	279	1-Percent	16000	571	588.91	583.43	589.75	0.001201	7.96	2885.9	563.54	0.39	Existing (FIS)

Table 5: Existing Conditions Shear Stress and Velocity HEC-RAS Output

Alternative	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Shear.Chan	Shear.LOB	Shear.ROB	Shear.Total	Vel.Chnl	Vel.Left	Vel.Right	Vel.Total
Ex - SS/VEL	20483	BF	3190	621.4	628.05	0.41	0.05	0.04	0.4	4.61	1.1	0.97	4.59
Ex - SS/VEL	20483	10-Percent	7990	621.4	631.44	0.85	0.09	0.17	0.66	7.14	2.27	2.39	6.95
Ex - SS/VEL	20483	2-Percent	11800	621.4	633.13	1.19	0.12	0.26	0.58	8.71	1.96	3.17	7.85
Ex - SS/VEL	20483	1-Percent	13600	621.4	633.75	1.34	0.2	0.3	0.67	9.3	2.31	3.46	8.08
Ex - SS/VEL	20483	0.2-Percent	18000	621.4	635.05	1.65	0.38	0.4	0.89	10.53	3.27	4.07	8.7
Ex - SS/VEL	19313	BF	3190	620.4	625.93	0.68	0.04	0.05	0.65	5.64	0.86	0.97	5.63
Ex - SS/VEL	19313	10-Percent	7990	620.4	628.71	1.29	0.3	0.11	0.61	8.44	3.21	1.27	7.65
Ex - SS/VEL	19313	2-Percent	11800	620.4	630.2	1.6	0.36	0.34	0.77	9.73	3.98	1.87	7.45
Ex - SS/VEL	19313	1-Percent	13600	620.4	630.82	1.71	0.12	0.45	0.77	10.15	2.55	2.21	7.4
Ex - SS/VEL	19313	0.2-Percent	18000	620.4	632.18	1.89	0.18	0.66	0.76	10.93	1.26	2.87	7.14
Ex - SS/VEL	18244	BF	3190	617.6	623.63	0.57	0.14	0.13	0.47	5.27	2.02	2.16	5.07
Ex - SS/VEL	18244	10-Percent	7990	617.6	626.65	0.85	0.31	0.26	0.41	6.95	3.58	1.51	4.5
Ex - SS/VEL	18244	2-Percent	11800	617.6	628.34	0.96	0.21	0.4	0.53	7.65	2.93	1.95	4.55
Ex - SS/VEL	18244	1-Percent	13600	617.6	629.04	1	0.16	0.46	0.55	7.92	3.17	2.1	4.62
Ex - SS/VEL	18244	0.2-Percent	18000	617.6	630.55	1.1	0.22	0.56	0.61	8.46	2.89	2.4	4.73
Ex - SS/VEL	17053	BF	3190	615.5	621.4	0.55	0.09	0.07	0.31	5.19	1.68	0.6	4.68
Ex - SS/VEL	17053	10-Percent	7990	615.5	624.35	0.93	0.08	0.38	0.43	7.31	1.56	1.34	4.87
Ex - SS/VEL	17053	2-Percent	11800	615.5	625.99	1.15	0.23	0.58	0.58	8.38	1.23	1.74	4.82
Ex - SS/VEL	17053	1-Percent	13600	615.5	626.65	1.24	0.31	0.66	0.65	8.8	1.32	1.89	4.87
Ex - SS/VEL	17053	0.2-Percent	18000	615.5	628.13	1.43	0.44	0.84	0.79	9.65	1.6	2.19	5.01
Ex - SS/VEL	15751	BF	3190	612.8	618.9	0.58	0.06	0.07	0.4	5.26	1.05	1.35	5.05
Ex - SS/VEL	15751	10-Percent	7990	612.8	621.48	1.06	0.34	0.09	0.63	7.65	2.36	3.03	6.26
Ex - SS/VEL	15751	2-Percent	11800	612.8	622.94	1.34	0.55	0.23	0.78	8.9	2.97	1.84	6.71
Ex - SS/VEL	15751	1-Percent	13600	612.8	623.57	1.44	0.64	0.3	0.86	9.34	3.2	1.92	6.85
Ex - SS/VEL	15751	0.2-Percent	18000	612.8	625.09	1.61	0.81	0.48	1.01	10.12	3.63	2.21	7.07
Ex - SS/VEL	14403	BF	3190	610.3	616.39	0.51	0.01	0.15	0.29	4.95	0.31	0.94	3.71
Ex - SS/VEL	14403	10-Percent	7990	610.3	619.25	0.68	0.19	0.33	0.38	6.2	1.4	1.66	3.58
Ex - SS/VEL	14403	2-Percent	11800	610.3	621.12	0.69	0.24	0.4	0.42	6.45	1.86	2.02	3.62
Ex - SS/VEL	14403	1-Percent	13600	610.3	621.93	0.68	0.25	0.42	0.42	6.52	2.04	2.13	3.64
Ex - SS/VEL	14403	0.2-Percent	18000	610.3	623.88	0.65	0.21	0.43	0.38	6.53	2.24	2.29	3.59
Ex - SS/VEL	12986	BF	3190	608.9	613.33	0.61	0.05	0.07	0.45	5.28	0.98	0.44	5.06
Ex - SS/VEL	12986	10-Percent	7990	608.9	617.09	0.68	0.02	0.3	0.31	6.23	1.48	1.25	4.6
Ex - SS/VEL	12986	2-Percent	11800	608.9	619.49	0.64	0.12	0.36	0.25	6.31	0.79	1.47	3.37
Ex - SS/VEL	12986	1-Percent	13600	608.9	620.52	0.6	0.15	0.36	0.26	6.22	0.91	1.5	3.06
Ex - SS/VEL	12986	0.2-Percent	18000	608.9	622.83	0.54	0.19	0.34	0.27	6.07	1.1	1.54	2.72
Ex - SS/VEL	12162	BF	3190	604.9	611.49	0.63	0.04	0.05	0.61	5.66	0.97	0.98	5.65
Ex - SS/VEL	12162	10-Percent	7990	604.9	614.98	1.25	0.31	0.27	1.1	8.62	2.13	3.59	8.36
Ex - SS/VEL	12162	2-Percent	11800	604.9	617.01	1.67	0.33	0.39	1.32	10.32	2.2	4.67	9.79
Ex - SS/VEL	12162	1-Percent	13600	604.9	617.86	1.86	0.28	0.44	1.28	11.01	2.03	5.04	10.26
Ex - SS/VEL	12162	0.2-Percent	18000	604.9	620.19	1.97	0.26	0.47	0.64	11.67	1.46	5.32	8.39
Ex - SS/VEL	11955	BF	3190	605.5	610.92	0.8			0.8	6.2			6.2
Ex - SS/VEL	11955	10-Percent	7990	605.5	614.34	1.4	0.17	0.04	1.33	8.95	2.23	0.87	8.92
Ex - SS/VEL	11955	2-Percent	11800	605.5	616.31	1.83	0.29	0.08	1.68	10.62	3.13	1.27	10.53
Ex - SS/VEL	11955	1-Percent	13600	605.5	617.14	2.01	0.33	0.09	1.82	11.29	3.4	1.43	11.17

Table 5: Existing Conditions Shear Stress and Velocity HEC-RAS Output (*continued*)

Alternative	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Shear.Chan	Shear.LOB	Shear.ROB	Shear.Total	Vel.Chnl	Vel.Left	Vel.Right	Vel.Total
Ex - SS/VEL	11955	0.2-Percent	18000	605.5	619.16	2.35	0.47	0.13	2.04	12.55	4.5	1.85	12.33
Ex - SS/VEL	11860 Union Rd	Bridge											
Ex - SS/VEL	11789	BF	3190	605.5	610	1.15			1.15	7.25			7.25
Ex - SS/VEL	11789	10-Percent	7990	605.5	613.21	1.88	0.06	0.13	1.83	10.13	1.06	1.68	10.12
Ex - SS/VEL	11789	2-Percent	11800	605.5	614.77	2.6	0.15	0.31	2.47	12.32	1.86	2.98	12.27
Ex - SS/VEL	11789	1-Percent	13600	605.5	615.3	3.01	0.2	0.39	2.83	13.38	2.18	3.45	13.31
Ex - SS/VEL	11789	0.2-Percent	18000	605.5	616.4	4.05	0.27	0.61	3.67	15.82	2.63	4.47	15.68
Ex - SS/VEL	11675	BF	3190	602.4	610	0.42			0.42	4.63			4.63
Ex - SS/VEL	11675	10-Percent	7990	602.4	613.3	0.92	0.14	0.09	0.86	7.39	1.18	1.72	7.33
Ex - SS/VEL	11675	2-Percent	11800	602.4	614.93	1.35	0.26	0.18	1.23	9.24	1.53	2.6	9.08
Ex - SS/VEL	11675	1-Percent	13600	602.4	615.51	1.59	0.33	0.22	1.43	10.09	1.69	2.89	9.89
Ex - SS/VEL	11675	0.2-Percent	18000	602.4	616.75	2.17	0.41	0.33	1.88	12.02	1.86	3.49	11.69
Ex - SS/VEL	10302	BF	3190	603.2	607.75	0.58	0.17	0.15	0.54	5.16	1.01	2.27	5.08
Ex - SS/VEL	10302	10-Percent	7990	603.2	610.26	1.16	0.15	0.15	0.66	7.94	0.94	3.28	7.22
Ex - SS/VEL	10302	2-Percent	11800	603.2	611.87	1.35	0.26	0.2	0.54	8.87	1.47	1.98	6.56
Ex - SS/VEL	10302	1-Percent	13600	603.2	612.52	1.38	0.34	0.25	0.57	9.09	1.66	2.26	6.27
Ex - SS/VEL	10302	0.2-Percent	18000	603.2	613.23	1.83	0.55	0.42	0.81	10.58	2.16	3.05	6.95
Ex - SS/VEL	9372	BF	3190	599.6	602.64	2.06			2.06	8.98			8.98
Ex - SS/VEL	9372	10-Percent	7990	599.6	605.24	2.36	0.27	0.32	2.28	10.72	2.53	2.82	10.68
Ex - SS/VEL	9372	2-Percent	11800	599.6	606.49	2.99	0.62	0.14	2.36	12.53	4.38	2.74	12.36
Ex - SS/VEL	9372	1-Percent	13600	599.6	607	3.24	0.74	0.24	2.11	13.23	4.95	2.95	12.73
Ex - SS/VEL	9372	0.2-Percent	18000	599.6	608.87	2.62	0.74	0.34	1.02	12.39	5.34	4.4	10.46
Ex - SS/VEL	8312	BF	3190	595.5	601.8	0.16			0.05	0.08	2.84		0.35
Ex - SS/VEL	8312	10-Percent	7990	595.5	605.14	0.23	0.02	0.12	0.15	3.66	0.85	0.72	2.01
Ex - SS/VEL	8312	2-Percent	11800	595.5	606.69	0.3	0.04	0.18	0.2	4.32	0.86	0.92	2.28
Ex - SS/VEL	8312	1-Percent	13600	595.5	607.32	0.33	0.06	0.2	0.22	4.59	0.95	1	2.39
Ex - SS/VEL	8312	0.2-Percent	18000	595.5	608.74	0.4	0.09	0.26	0.28	5.15	1.18	1.18	2.63
Ex - SS/VEL	8145	BF	3190	592.1	601.8	0.07			0.07	2			2
Ex - SS/VEL	8145	10-Percent	7990	592.1	605.04	0.2			0.2	3.63			3.63
Ex - SS/VEL	8145	2-Percent	11800	592.1	606.47	0.34			0.34	4.77			4.77
Ex - SS/VEL	8145	1-Percent	13600	592.1	607.04	0.4			0.4	5.27			5.27
Ex - SS/VEL	8145	0.2-Percent	18000	592.1	608.27	0.58			0.58	6.4			6.4
Ex - SS/VEL	8049 Railroad Bridge	Bridge											
Ex - SS/VEL	7984	BF	3190	592.1	601.61	0.19	0.03	0.02	0.18	3.14	0.92	0.73	3.12
Ex - SS/VEL	7984	10-Percent	7990	592.1	604.61	0.46	0.19	0.13	0.42	5.23	2.94	2.28	5.14
Ex - SS/VEL	7984	2-Percent	11800	592.1	605.76	0.75	0.36	0.24	0.69	6.83	4.2	3.16	6.69
Ex - SS/VEL	7984	1-Percent	13600	592.1	606.17	0.9	0.45	0.29	0.83	7.56	4.77	3.52	7.39
Ex - SS/VEL	7984	0.2-Percent	18000	592.1	606.97	1.33	0.71	0.43	1.21	9.29	6.11	4.38	9.04
Ex - SS/VEL	7758	BF	3190	595	601.25	0.3	0.15	0.09	0.27	3.92	2.56	1.78	3.75
Ex - SS/VEL	7758	10-Percent	7990	595	604.09	0.61	0.36	0.05	0.21	5.98	4.51	1.48	5.08
Ex - SS/VEL	7758	2-Percent	11800	595	605.32	0.74	0.45	0.12	0.26	6.73	5.22	2.1	4.91
Ex - SS/VEL	7758	1-Percent	13600	595	605.76	0.79	0.47	0.16	0.29	7	5.45	2.44	5
Ex - SS/VEL	7758	0.2-Percent	18000	595	606.62	0.94	0.45	0.2	0.32	7.72	5.89	2.98	5.29
Ex - SS/VEL	7564	BF	3190	594.9	600.79	0.36	0.12	0.08	0.28	4.25	1.97	1.5	3.93

Table 5: Existing Conditions Shear Sress and Velocity HEC-RAS Output (*continued*)

Alternative	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Shear.Chan	Shear.LOB	Shear.ROB	Shear.Total	Vel.Chnl	Vel.Left	Vel.Right	Vel.Total
Ex - SS/VEL	7564	10-Percent	7990	594.9	603.55	0.66	0.29	0.06	0.21	6.15	3.68	1.32	4.85
Ex - SS/VEL	7564	2-Percent	11800	594.9	604.89	0.67	0.15	0.13	0.22	6.38	3.52	2.2	4.35
Ex - SS/VEL	7564	1-Percent	13600	594.9	605.36	0.68	0.14	0.16	0.23	6.48	3.4	2.49	4.33
Ex - SS/VEL	7564	0.2-Percent	18000	594.9	606.27	0.71	0.18	0.14	0.21	6.72	3.47	2.83	4.3
Ex - SS/VEL	7340	BF	3190	594.8	600.32	0.36	0.21	0.08	0.29	4.17	2.54	1.59	3.72
Ex - SS/VEL	7340	10-Percent	7990	594.8	603.1	0.58	0.18	0.08	0.22	5.71	3.62	1.78	4.45
Ex - SS/VEL	7340	2-Percent	11800	594.8	604.48	0.61	0.2	0.1	0.19	6.03	3.39	1.98	3.99
Ex - SS/VEL	7340	1-Percent	13600	594.8	604.97	0.6	0.2	0.12	0.2	6.05	3.4	2.17	3.9
Ex - SS/VEL	7340	0.2-Percent	18000	594.8	605.92	0.61	0.22	0.11	0.18	6.16	3.56	2.36	3.78
Ex - SS/VEL	7151	BF	3190	594.7	599.64	0.4	0.01	0.01	0.4	4.29	0.29	0.43	4.29
Ex - SS/VEL	7151	10-Percent	7990	594.7	602.26	0.71	0.06	0.13	0.36	6.18	1.57	1.22	5.38
Ex - SS/VEL	7151	2-Percent	11800	594.7	603.59	0.83	0.13	0.13	0.27	6.89	2.3	1.47	4.96
Ex - SS/VEL	7151	1-Percent	13600	594.7	604.15	0.81	0.16	0.1	0.21	6.88	2.7	1.52	4.53
Ex - SS/VEL	7151	0.2-Percent	18000	594.7	605.45	0.6	0.18	0.1	0.16	6.07	3.13	1.6	3.32
Ex - SS/VEL	6890	BF	3190	593	598.71	0.44			0.44	4.48			4.48
Ex - SS/VEL	6890	10-Percent	7990	593	601.33	0.72	0.09	0.14	0.35	6.22	1.76	2.33	5.49
Ex - SS/VEL	6890	2-Percent	11800	593	602.91	0.67	0.17	0.1	0.26	6.2	2.93	2.07	4.82
Ex - SS/VEL	6890	1-Percent	13600	593	603.55	0.63	0.2	0.13	0.28	6.1	3.26	2.03	4.59
Ex - SS/VEL	6890	0.2-Percent	18000	593	604.89	0.59	0.24	0.19	0.3	6.05	3.82	2.19	4.47
Ex - SS/VEL	6631	BF	3190	592	597.26	0.63			0.63	5.14			5.14
Ex - SS/VEL	6631	10-Percent	7990	592	600	0.87	0.15	0.21	0.82	6.7	2.04	2.61	6.63
Ex - SS/VEL	6631	2-Percent	11800	592	601.48	1.06	0.16	0.34	0.76	7.68	2.4	3.63	7.27
Ex - SS/VEL	6631	1-Percent	13600	592	602.08	1.13	0.24	0.11	0.71	8.04	3.16	2.41	7.46
Ex - SS/VEL	6631	0.2-Percent	18000	592	603.42	1.22	0.39	0.21	0.76	8.57	4.41	3.16	7.67
Ex - SS/VEL	6324	BF	3190	590.5	596.21	0.33			0.33	3.91			3.91
Ex - SS/VEL	6324	10-Percent	7990	590.5	598.97	0.63	0.02	0.07	0.48	5.88	0.65	1.46	5.71
Ex - SS/VEL	6324	2-Percent	11800	590.5	600.39	0.84	0.05	0.21	0.66	7	1.04	2.93	6.63
Ex - SS/VEL	6324	1-Percent	13600	590.5	600.97	0.93	0.06	0.27	0.73	7.44	1.18	3.46	7.02
Ex - SS/VEL	6324	0.2-Percent	18000	590.5	602.23	1.13	0.09	0.41	0.9	8.41	1.5	4.53	7.88
Ex - SS/VEL	6015	BF	3190	588.7	594.44	0.82	0.05	0.03	0.74	6.02	0.98	0.73	5.98
Ex - SS/VEL	6015	10-Percent	7990	588.7	596.99	1.25	0.32	0.27	0.78	8.13	3.66	3.11	7.27
Ex - SS/VEL	6015	2-Percent	11800	588.7	598.68	1.26	0.46	0.38	0.78	8.49	4.72	4.02	7.26
Ex - SS/VEL	6015	1-Percent	13600	588.7	599.36	1.27	0.51	0.37	0.77	8.66	5.1	4.23	7.32
Ex - SS/VEL	6015	0.2-Percent	18000	588.7	600.9	1.26	0.58	0.31	0.62	8.86	5.69	3.8	6.98
Ex - SS/VEL	5607	BF	3190	587.3	592.37	0.66	0.4	0.16	0.54	5.47	3.9	2.18	5.02
Ex - SS/VEL	5607	10-Percent	7990	587.3	595.55	0.81	0.46	0.15	0.55	6.71	4.98	2.89	5.94
Ex - SS/VEL	5607	2-Percent	11800	587.3	597.54	0.85	0.54	0.16	0.44	7.14	5.41	1.73	5.65
Ex - SS/VEL	5607	1-Percent	13600	587.3	598.34	0.85	0.56	0.21	0.47	7.25	5.53	2.01	5.58
Ex - SS/VEL	5607	0.2-Percent	18000	587.3	600.02	0.89	0.48	0.31	0.5	7.61	5.59	2.56	5.59
Ex - SS/VEL	5307	BF	3190	585.8	591.31	0.45	0.12	0.09	0.36	4.61	2	1.64	4.39
Ex - SS/VEL	5307	10-Percent	7990	585.8	594.85	0.57	0.3	0.11	0.39	5.73	3.98	2.69	5.25
Ex - SS/VEL	5307	2-Percent	11800	585.8	596.95	0.63	0.36	0.14	0.35	6.29	4.69	1.92	5.18
Ex - SS/VEL	5307	1-Percent	13600	585.8	597.75	0.67	0.39	0.19	0.39	6.56	4.93	1.96	5.23
Ex - SS/VEL	5307	0.2-Percent	18000	585.8	599.42	0.78	0.23	0.27	0.41	7.23	4.3	2.21	5.31

Table 5: Existing Conditions Shear Stress and Velocity HEC-RAS Output (*continued*)

Alternative	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Shear.Chan	Shear.LOB	Shear.ROB	Shear.Total	Vel.Chnl	Vel.Left	Vel.Right	Vel.Total
Ex - SS/VEL	5051	BF	3190	584.3	590.43	0.44			0.44	4.5			4.5
Ex - SS/VEL	5051	10-Percent	7990	584.3	594.2	0.58	0.12	0.16	0.52	5.74	1.98	1.19	5.56
Ex - SS/VEL	5051	2-Percent	11800	584.3	596.26	0.7	0.14	0.11	0.46	6.57	2.76	1.37	6.06
Ex - SS/VEL	5051	1-Percent	13600	584.3	597.06	0.74	0.08	0.16	0.43	6.86	2.38	1.77	6.11
Ex - SS/VEL	5051	0.2-Percent	18000	584.3	598.75	0.82	0.18	0.26	0.51	7.39	3.15	2.65	6.34
Ex - SS/VEL	4786	BF	3190	582.8	589.81	0.35	0	0	0.35	4.17	0.13	0.24	4.17
Ex - SS/VEL	4786	10-Percent	7990	582.8	593.61	0.6	0.08	0.12	0.55	5.97	1.55	2.05	5.9
Ex - SS/VEL	4786	2-Percent	11800	582.8	595.6	0.78	0.12	0.11	0.55	7.07	2.27	2.09	6.7
Ex - SS/VEL	4786	1-Percent	13600	582.8	596.36	0.86	0.18	0.09	0.55	7.49	2.87	2.14	6.96
Ex - SS/VEL	4786	0.2-Percent	18000	582.8	597.93	1.03	0.29	0.21	0.68	8.38	3.97	3.25	7.6
Ex - SS/VEL	4582	BF	3190	582.7	589.19	0.45			0.45	4.69			4.69
Ex - SS/VEL	4582	10-Percent	7990	582.7	593.03	0.69	0.16	0.13	0.62	6.37	2.46	2.13	6.25
Ex - SS/VEL	4582	2-Percent	11800	582.7	594.99	0.88	0.16	0.2	0.64	7.45	2.87	2.81	7.04
Ex - SS/VEL	4582	1-Percent	13600	582.7	595.71	0.98	0.22	0.23	0.71	7.92	3.38	2.98	7.4
Ex - SS/VEL	4582	0.2-Percent	18000	582.7	597.16	1.21	0.36	0.18	0.82	9.01	4.51	3.04	8.28
Ex - SS/VEL	4363	BF	3190	582.5	588.59	0.43			0.43	4.56			4.56
Ex - SS/VEL	4363	10-Percent	7990	582.5	592.55	0.64	0.11	0.1	0.59	6.16	1.87	2.04	6.09
Ex - SS/VEL	4363	2-Percent	11800	582.5	594.45	0.86	0.1	0.15	0.65	7.37	2.43	2.93	7.14
Ex - SS/VEL	4363	1-Percent	13600	582.5	595.14	0.97	0.12	0.07	0.53	7.89	2.46	2.11	7.41
Ex - SS/VEL	4363	0.2-Percent	18000	582.5	596.59	1.16	0.11	0.19	0.45	8.82	2.38	3.15	7.58
Ex - SS/VEL	4182	BF	3190	582.4	588.26	0.49			0.49	4.81			4.81
Ex - SS/VEL	4182	10-Percent	7990	582.4	592.31	0.66	0.11	0.12	0.62	6.23	2.12	1.99	6.16
Ex - SS/VEL	4182	2-Percent	11800	582.4	594.17	0.89	0.08	0.16	0.66	7.48	2.31	2.42	7.25
Ex - SS/VEL	4182	1-Percent	13600	582.4	594.83	1.01	0.12	0.1	0.65	8.04	2.26	2.58	7.65
Ex - SS/VEL	4182	0.2-Percent	18000	582.4	596.15	1.29	0.23	0.19	0.76	9.23	2.85	3.11	8.36
Ex - SS/VEL	3997	BF	3190	582.3	587.99	0.43			0.43	4.53			4.53
Ex - SS/VEL	3997	10-Percent	7990	582.3	592.12	0.6	0.08	0.09	0.56	5.95	1.55	1.73	5.91
Ex - SS/VEL	3997	2-Percent	11800	582.3	593.96	0.83	0.13	0.07	0.68	7.22	2.39	2.17	7.09
Ex - SS/VEL	3997	1-Percent	13600	582.3	594.59	0.95	0.06	0.09	0.62	7.82	2.26	1.69	7.54
Ex - SS/VEL	3997	0.2-Percent	18000	582.3	595.81	1.28	0.15	0.22	0.78	9.23	2.17	1.73	8.47
Ex - SS/VEL	3670	BF	3190	582.1	587.49	0.46	0.02	0.06	0.27	4.67	0.55	0.37	4.2
Ex - SS/VEL	3670	10-Percent	7990	582.1	591.97	0.44	0.12	0.09	0.14	5.14	2.49	0.58	2.5
Ex - SS/VEL	3670	2-Percent	11800	582.1	594.03	0.43	0.1	0.14	0.18	5.24	2.38	0.78	2.09
Ex - SS/VEL	3670	1-Percent	13600	582.1	594.75	0.44	0.07	0.17	0.2	5.39	2.09	0.85	2.07
Ex - SS/VEL	3670	0.2-Percent	18000	582.1	596.18	0.5	0.05	0.22	0.23	5.81	1.33	1.01	2.13
Ex - SS/VEL	2921	BF	3190	576.6	587.09	0.18	0.03	0.03	0.17	3.17	1.11	0.95	3.13
Ex - SS/VEL	2921	10-Percent	7990	576.6	591.5	0.36	0.04	0.02	0.13	4.85	1.11	0.81	4.31
Ex - SS/VEL	2921	2-Percent	11800	576.6	593.39	0.49	0.06	0.05	0.1	5.82	1.08	0.57	3.58
Ex - SS/VEL	2921	1-Percent	13600	576.6	594.11	0.52	0.08	0.06	0.11	6.04	1.29	0.63	3.2
Ex - SS/VEL	2921	0.2-Percent	18000	576.6	595.64	0.52	0.12	0.11	0.15	6.15	1.72	0.92	2.79
Ex - SS/VEL	1922	BF	3190	573.7	586.86	0.12	0.01	0.03	0.05	2.68	0.49	0.36	1.64
Ex - SS/VEL	1922	10-Percent	7990	573.7	591.43	0.14	0.04	0.04	0.05	3.15	0.48	0.62	1.19
Ex - SS/VEL	1922	2-Percent	11800	573.7	593.4	0.15	0.05	0.06	0.06	3.34	0.57	0.81	1.26
Ex - SS/VEL	1922	1-Percent	13600	573.7	594.12	0.16	0.05	0.06	0.07	3.45	0.6	0.9	1.31

Table 5: Existing Conditions Shear Sress and Velocity HEC-RAS Output (*continued*)

Alternative	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Shear.Chan	Shear.LOB	Shear.ROB	Shear.Total	Vel.Chnl	Vel.Left	Vel.Right	Vel.Total
Ex - SS/VEL	1922	0.2-Percent	18000	573.7	595.61	0.18	0.03	0.08	0.07	3.74	0.55	1.07	1.42
Ex - SS/VEL	833	BF	3190	571.5	586.74	0.07	0.01	0.01	0.03	2.18	0.58	0.36	1.79
Ex - SS/VEL	833	10-Percent	7990	571.5	591.31	0.1	0.02	0.02	0.02	2.65	0.53	1.03	1.47
Ex - SS/VEL	833	2-Percent	11800	571.5	593.29	0.1	0.02	0.02	0.03	2.77	0.55	1.17	1.41
Ex - SS/VEL	833	1-Percent	13600	571.5	594.02	0.1	0.02	0.03	0.03	2.82	0.55	1.25	1.41
Ex - SS/VEL	833	0.2-Percent	18000	571.5	595.51	0.11	0.02	0.04	0.03	2.96	0.57	1.42	1.44
Ex - SS/VEL	279	BF	3190	571	586.65	0.08	0	0.01	0.03	2.22	0.21	0.27	1.9
Ex - SS/VEL	279	10-Percent	7990	571	591.21	0.11	0.01	0.02	0.03	2.8	0.7	0.88	1.69
Ex - SS/VEL	279	2-Percent	11800	571	593.19	0.13	0	0.04	0.04	3.04	0.4	1.08	1.71
Ex - SS/VEL	279	1-Percent	13600	571	593.91	0.13	0	0.04	0.03	3.12	0.19	1.19	1.71
Ex - SS/VEL	279	0.2-Percent	18000	571	595.4	0.14	0.01	0.05	0.04	3.29	0.2	1.4	1.61

## FEMA Effective versus Existing Conditions Models

### FEMA FIS Peak Discharge for the 1-Percent AEP (100-Year Recurrence) Event




Figure 13: Effective FEMA versus Existing Conditions Profile Plot (FEMA 1-Percent AEP/100-Year Recurrence Event Peak Discharges)

**USGS StreamStats Peak Discharges for the 10-, 2-, 1-, & 0.2-Percent AEP (10-, 50-, 100-, & 500-Year Recurrence) Events**




Figure 14: Effective FEMA versus Existing Conditions Profile Plot (USGS StreamStats 10-, 2-, 1-, & 0.2-Percent AEP Event Peak Discharges)

## **Flood Scenario #1**

### **Flood Bench Configuration: 1a**

Plan: UPDATE-FB-1A-SCHOOL-FULL

Geometry: UPDATE-FB-1A-SCHOOL-FULL

Steady Flow Data: USGS BF,10,2,1,0.2-PERCENT-UPDATE-BC

Date: December 2022




Figure 15: Flood Scenario #1 (1a) Profile Plot

Table 6: Flood Scenario 1 HEC-RAS Output

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl
1 (1a)	20483	10-Percent	7990	621.4	631.44		632.23	0.00152	7.14	1149.93	159.75	0.42
1 (1a)	20483	2-Percent	11800	621.4	633.13		634.27	0.001801	8.71	1502.7	283.71	0.47
1 (1a)	20483	1-Percent	13600	621.4	633.75		635.03	0.001907	9.3	1683.22	292.19	0.49
1 (1a)	20483	0.2-Percent	18000	621.4	635.05		636.62	0.002117	10.53	2068.6	300.59	0.52
1 (1a)	19313	10-Percent	7990	620.4	628.71		629.8	0.002908	8.44	1044.14	306.61	0.56
1 (1a)	19313	2-Percent	11800	620.4	630.2		631.56	0.003003	9.73	1584.75	383.6	0.58
1 (1a)	19313	1-Percent	13600	620.4	630.82		632.26	0.002981	10.15	1839	441.87	0.59
1 (1a)	19313	0.2-Percent	18000	620.4	632.18	630.62	633.75	0.002879	10.93	2522.14	587.78	0.59
1 (1a)	18244	10-Percent	7990	617.6	626.65		627.29	0.001757	6.95	1777.22	467.86	0.44
1 (1a)	18244	2-Percent	11800	617.6	628.34		629.05	0.001639	7.65	2590.92	496.45	0.44
1 (1a)	18244	1-Percent	13600	617.6	629.04		629.77	0.001597	7.92	2942.21	525.34	0.44
1 (1a)	18244	0.2-Percent	18000	617.6	630.55		631.34	0.001514	8.46	3805.28	582.51	0.44
1 (1a)	17053	10-Percent	7990	615.5	624.35		625.09	0.001916	7.31	1642.27	449.95	0.46
1 (1a)	17053	2-Percent	11800	615.5	625.99		626.9	0.001963	8.38	2445.93	516.05	0.48
1 (1a)	17053	1-Percent	13600	615.5	626.65		627.63	0.001977	8.8	2794.51	525.92	0.49
1 (1a)	17053	0.2-Percent	18000	615.5	628.13		629.25	0.001985	9.65	3589.78	557.64	0.5
1 (1a)	15751	10-Percent	7990	612.8	621.48		622.31	0.002376	7.65	1275.64	297.31	0.5
1 (1a)	15751	2-Percent	11800	612.8	622.94		624	0.002512	8.9	1759.86	349.52	0.53
1 (1a)	15751	1-Percent	13600	612.8	623.57		624.72	0.002518	9.34	1985.58	360.25	0.54
1 (1a)	15751	0.2-Percent	18000	612.8	625.09		626.39	0.002415	10.12	2545.4	374.73	0.54
1 (1a)	14403	10-Percent	7990	610.3	619.25		619.71	0.001482	6.2	2234.3	539.57	0.4
1 (1a)	14403	2-Percent	11800	610.3	621.12		621.56	0.001194	6.45	3263.7	572.17	0.37
1 (1a)	14403	1-Percent	13600	610.3	621.93		622.37	0.001093	6.52	3734.74	594.17	0.36
1 (1a)	14403	0.2-Percent	18000	610.3	623.88		624.29	0.00087	6.53	5014.3	708.31	0.33
1 (1a)	12986	10-Percent	7990	608.9	617.09		617.64	0.001416	6.23	1736.27	495.45	0.39
1 (1a)	12986	2-Percent	11800	608.9	619.49		620	0.001016	6.31	3498.64	888.93	0.35
1 (1a)	12986	1-Percent	13600	608.9	620.52		620.99	0.000867	6.22	4438.68	920.06	0.33
1 (1a)	12986	0.2-Percent	18000	608.9	622.83		623.23	0.000643	6.07	6623.01	966.59	0.29
1 (1a)	12162	10-Percent	7990	604.9	614.98		616.12	0.002284	8.62	955.8	117.56	0.5
1 (1a)	12162	2-Percent	11800	604.9	617.01		618.63	0.002504	10.32	1205.03	134.66	0.55
1 (1a)	12162	1-Percent	13600	604.9	617.86		619.71	0.002579	11.01	1326.02	158.14	0.56
1 (1a)	12162	0.2-Percent	18000	604.9	620.19	615.89	622.17	0.002287	11.67	2144.46	464.7	0.54
1 (1a)	11955	10-Percent	7990	605.5	614.34	611.72	615.59	0.00286	8.95	895.71	113.2	0.56
1 (1a)	11955	2-Percent	11800	605.5	616.31	613.35	618.05	0.003008	10.62	1120.3	115.54	0.59
1 (1a)	11955	1-Percent	13600	605.5	617.14	614.06	619.11	0.003059	11.29	1217.31	121.14	0.6
1 (1a)	11955	0.2-Percent	18000	605.5	619.16	615.65	621.59	0.003014	12.55	1459.52	154.88	0.62
1 (1a)	11860 Union Rd	Bridge										
1 (1a)	11789	10-Percent	7990	605.5	613.21	611.45	614.81	0.004409	10.13	789.56	110.22	0.66
1 (1a)	11789	2-Percent	11800	605.5	614.77	613.12	617.12	0.005034	12.32	962.04	111.86	0.73
1 (1a)	11789	1-Percent	13600	605.5	615.3	613.85	618.08	0.005496	13.38	1021.67	112.36	0.77
1 (1a)	11789	0.2-Percent	18000	605.5	616.4	615.46	620.28	0.00662	15.82	1147.98	117.14	0.86
1 (1a)	11675	10-Percent	7990	602.4	613.3		614.14	0.001656	7.39	1090.08	125.8	0.43
1 (1a)	11675	2-Percent	11800	602.4	614.93		616.25	0.002073	9.24	1299.03	129.76	0.5
1 (1a)	11675	1-Percent	13600	602.4	615.51		617.09	0.002307	10.09	1374.62	131.08	0.53

Table 6: Flood Scenario 1 HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl
1 (1a)	11675	0.2-Percent	18000	602.4	616.75		618.98	0.00285	12.02	1539.74	137.59	0.6
1 (1a)	10302	10-Percent	7990	603.2	610.26		611.22	0.002817	7.94	1106.57	291.38	0.54
1 (1a)	10302	2-Percent	11800	603.2	611.87	609.46	613	0.002633	8.87	1797.94	548.49	0.54
1 (1a)	10302	1-Percent	13600	603.2	612.52	610.2	613.66	0.002497	9.09	2170.55	588.79	0.54
1 (1a)	10302	0.2-Percent	18000	603.2	613.23	612.13	614.7	0.003059	10.58	2588.13	602.95	0.6
1 (1a)	9372	10-Percent	7990	599.6	605.24	604.78	607.03	0.007893	10.72	748.14	158.9	0.86
1 (1a)	9372	2-Percent	11800	599.6	606.49	606.07	608.92	0.007952	12.54	954.92	197.16	0.89
1 (1a)	9372	1-Percent	13600	599.6	607	606.96	609.69	0.007961	13.23	1068.05	247.58	0.91
1 (1a)	9372	0.2-Percent	18000	599.6	608.87	608.87	611.04	0.005014	12.39	1721.36	525.34	0.75
1 (1a)	8312	10-Percent	7990	595.5	605.14		605.3	0.000447	3.66	3982.49	730.2	0.22
1 (1a)	8312	2-Percent	11800	595.5	606.69		606.91	0.000496	4.32	5182.22	800.7	0.24
1 (1a)	8312	1-Percent	13600	595.5	607.32		607.57	0.000515	4.59	5692.82	807.28	0.25
1 (1a)	8312	0.2-Percent	18000	595.5	608.74		609.04	0.000546	5.15	6850.91	828.62	0.26
1 (1a)	8145	10-Percent	7990	592.1	605.04	597.15	605.24	0.000278	3.63	2202.52	345.65	0.19
1 (1a)	8145	2-Percent	11800	592.1	606.47	598.29	606.82	0.000414	4.77	2471.56	453.2	0.23
1 (1a)	8145	1-Percent	13600	592.1	607.04	598.79	607.47	0.000477	5.27	2578.39	465.93	0.25
1 (1a)	8145	0.2-Percent	18000	592.1	608.27	599.9	608.91	0.000627	6.41	2810.19	492.25	0.29
1 (1a)	8049 Railroad Bridge	Bridge										
1 (1a)	7984	10-Percent	7990	592.1	604.61	599.55	605.03	0.000804	5.23	1554.94	372.48	0.3
1 (1a)	7984	2-Percent	11800	592.1	605.76	600.86	606.47	0.001172	6.83	1764.73	507.94	0.37
1 (1a)	7984	1-Percent	13600	592.1	606.17	601.43	607.05	0.001361	7.56	1841.08	526.75	0.41
1 (1a)	7984	0.2-Percent	18000	592.1	606.97	602.7	608.28	0.001869	9.29	1989.07	563.29	0.48
1 (1a)	7758	10-Percent	7990	595	604.09	600.48	604.59	0.001188	5.98	1571.37	590.44	0.37
1 (1a)	7758	2-Percent	11800	595	605.32	601.71	605.9	0.001254	6.73	2400.96	885.52	0.38
1 (1a)	7758	1-Percent	13600	595	605.76	602.23	606.36	0.001277	7	2721.16	917.66	0.39
1 (1a)	7758	0.2-Percent	18000	595	606.61	604.85	607.29	0.001399	7.74	3392.85	1140.01	0.41
1 (1a)	7564	10-Percent	7990	594.9	603.55		604.07	0.001331	6.15	1647.39	654.14	0.38
1 (1a)	7564	2-Percent	11800	594.9	604.89		605.36	0.001165	6.38	2708.17	898.97	0.37
1 (1a)	7564	1-Percent	13600	594.9	605.35		605.81	0.00113	6.49	3140.66	968.22	0.37
1 (1a)	7564	0.2-Percent	18000	594.9	606.26		606.71	0.001086	6.75	4169.67	1341.51	0.36
1 (1a)	7340	10-Percent	7990	594.8	603.1		603.51	0.00124	5.71	1796.58	631.98	0.37
1 (1a)	7340	2-Percent	11800	594.8	604.47		604.87	0.001106	6.04	2952.53	1059.96	0.36
1 (1a)	7340	1-Percent	13600	594.8	604.97		605.34	0.001035	6.05	3484.37	1123.68	0.35
1 (1a)	7340	0.2-Percent	18000	594.8	605.9		606.26	0.000955	6.19	4736.98	1541.53	0.34
1 (1a)	7151	10-Percent	7990	594.7	602.26		602.83	0.001747	6.18	1483.65	452.35	0.43
1 (1a)	7151	2-Percent	11800	594.7	603.58		604.23	0.001701	6.9	2375.6	919.93	0.43
1 (1a)	7151	1-Percent	13600	594.7	604.14		604.75	0.001556	6.9	2986.11	1329.37	0.42
1 (1a)	7151	0.2-Percent	18000	594.7	605.42		605.81	0.001016	6.13	5358.67	2116.3	0.35
1 (1a)	6890	10-Percent	7990	593	601.33	598.69	601.9	0.001835	6.22	1454	1740.27	0.43
1 (1a)	6890	2-Percent	11800	593	602.9	600.03	603.39	0.001366	6.21	2442.13	2169.69	0.39
1 (1a)	6890	1-Percent	13600	593	603.54	601.1	604	0.001196	6.12	2947.11	2249.49	0.37
1 (1a)	6890	0.2-Percent	18000	593	604.85	602.34	605.29	0.000981	6.1	3991.83	2354.86	0.34
1 (1a)	6631	10-Percent	7990	592	600	597.85	600.69	0.002439	6.7	1204.75	234.01	0.49
1 (1a)	6631	2-Percent	11800	592	601.45	598.95	602.35	0.002393	7.71	1614.88	392.04	0.51

Table 6: Flood Scenario 1 HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl
1 (1a)	6631	1-Percent	13600	592	602.04	599.43	603.02	0.002373	8.1	1806.96	512.6	0.51
1 (1a)	6631	0.2-Percent	18000	592	603.33	600.53	604.42	0.00223	8.69	2309.4	653.54	0.51
1 (1a)	6324	10-Percent	7990	590.5	598.96	595.72	599.49	0.001483	5.88	1398.98	263.7	0.39
1 (1a)	6324	2-Percent	11800	590.5	600.33	596.88	601.08	0.001673	7.05	1765.54	378.06	0.43
1 (1a)	6324	1-Percent	13600	590.5	600.89	597.36	601.73	0.001751	7.53	1915.19	446	0.45
1 (1a)	6324	0.2-Percent	18000	590.5	602.06	598.58	603.14	0.001927	8.58	2238.53	548.02	0.48
1 (1a)	6015	10-Percent	7990	588.7	596.86		597.88	0.003538	8.37	1063.46	280.4	0.6
1 (1a)	6015	2-Percent	11800	588.7	598.25		599.41	0.003254	9.21	1485.92	321.31	0.59
1 (1a)	6015	1-Percent	13600	588.7	598.86		600.06	0.003094	9.46	1684.48	334.01	0.59
1 (1a)	6015	0.2-Percent	18000	588.7	600.06		601.41	0.003004	10.23	2157.68	466.24	0.59
1 (1a)	5607	10-Percent	7990	587.3	594.64	592.95	595.5	0.003074	7.96	1112.38	234.54	0.56
1 (1a)	5607	2-Percent	11800	587.3	596.16	594.02	597.21	0.002892	8.92	1523.13	319.78	0.56
1 (1a)	5607	1-Percent	13600	587.3	596.8	594.71	597.94	0.00286	9.35	1759.64	433.84	0.57
1 (1a)	5607	0.2-Percent	18000	587.3	598.23	595.81	599.42	0.002526	9.76	2389.82	443.67	0.55
1 (1a)	5307	10-Percent	7990	585.8	593.81		594.25	0.001435	5.87	1683.7	388.08	0.39
1 (1a)	5307	2-Percent	11800	585.8	595.64		596.09	0.001117	6.05	2401.22	395.31	0.36
1 (1a)	5307	1-Percent	13600	585.8	596.36		596.83	0.001059	6.2	2686.8	398.69	0.35
1 (1a)	5307	0.2-Percent	18000	585.8	597.85		598.38	0.001003	6.65	3289.45	411.86	0.35
1 (1a)	5051	10-Percent	7990	584.3	593.59		593.73	0.000524	3.59	3053.94	701.99	0.24
1 (1a)	5051	2-Percent	11800	584.3	595.55		595.68	0.000367	3.53	4438.55	714.44	0.21
1 (1a)	5051	1-Percent	13600	584.3	596.3		596.43	0.000342	3.59	4976.62	727.51	0.2
1 (1a)	5051	0.2-Percent	18000	584.3	597.85		598	0.000311	3.77	6331.34	1024.74	0.2
1 (1a)	4786	10-Percent	7990	582.8	593.31		593.49	0.000503	3.98	2660.56	493.86	0.24
1 (1a)	4786	2-Percent	11800	582.8	595.3		595.49	0.00042	4.17	3759.63	708.75	0.23
1 (1a)	4786	1-Percent	13600	582.8	596.06		596.26	0.000401	4.27	4338.42	815.28	0.22
1 (1a)	4786	0.2-Percent	18000	582.8	597.63		597.83	0.00037	4.47	5870.64	1102.48	0.22
1 (1a)	4582	10-Percent	7990	582.7	593		593.24	0.000663	4.5	2289.38	436.5	0.27
1 (1a)	4582	2-Percent	11800	582.7	595.04		595.29	0.000535	4.67	3379.07	657.76	0.25
1 (1a)	4582	1-Percent	13600	582.7	595.8		596.06	0.00051	4.78	3975.48	857.58	0.25
1 (1a)	4582	0.2-Percent	18000	582.7	597.39		597.65	0.000467	4.99	5490.17	1094.01	0.25
1 (1a)	4363	10-Percent	7990	582.5	592.75	588.87	592.99	0.000588	4.34	2257.81	365.42	0.26
1 (1a)	4363	2-Percent	11800	582.5	594.79	589.88	595.07	0.000534	4.76	3045.66	632.42	0.25
1 (1a)	4363	1-Percent	13600	582.5	595.55	590.29	595.85	0.000535	4.97	3372.01	846.19	0.26
1 (1a)	4363	0.2-Percent	18000	582.5	597.08	591.13	597.44	0.000552	5.49	4262.28	1253.28	0.27
1 (1a)	4182	10-Percent	7990	582.4	592.35	588.44	592.82	0.001061	5.69	1526.98	219.8	0.34
1 (1a)	4182	2-Percent	11800	582.4	594.28	589.77	594.9	0.001088	6.61	1974.52	320.53	0.36
1 (1a)	4182	1-Percent	13600	582.4	594.97	590.3	595.67	0.001134	7.04	2165.03	449.01	0.37
1 (1a)	4182	0.2-Percent	18000	582.4	596.34	591.45	597.24	0.001268	8.05	2566.77	662.13	0.4
1 (1a)	3997	10-Percent	7990	582.3	592.16	587.76	592.63	0.001002	5.63	1509.42	232.42	0.34
1 (1a)	3997	2-Percent	11800	582.3	594.04	589.24	594.7	0.001082	6.67	1900.75	243.83	0.36
1 (1a)	3997	1-Percent	13600	582.3	594.7	589.77	595.45	0.001156	7.17	2050.82	284.39	0.38
1 (1a)	3997	0.2-Percent	18000	582.3	595.98	591.01	596.99	0.001358	8.35	2395.48	550.38	0.42
1 (1a)	3670	10-Percent	7990	582.1	591.97		592.32	0.000786	5.14	3197.67	1118.11	0.3
1 (1a)	3670	2-Percent	11800	582.1	594.03		594.34	0.000623	5.24	5655.63	1230.59	0.28

Table 6: Flood Scenario 1 HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl
1 (1a)	3670	1-Percent	13600	582.1	594.75		595.07	0.000605	5.39	6554.79	1256.34	0.28
1 (1a)	3670	0.2-Percent	18000	582.1	596.18		596.52	0.000604	5.81	8437.7	1373.85	0.28
1 (1a)	2921	10-Percent	7990	576.6	591.5		591.86	0.000498	4.85	1852.73	452.33	0.25
1 (1a)	2921	2-Percent	11800	576.6	593.39		593.87	0.000588	5.82	3296.29	1158.38	0.28
1 (1a)	2921	1-Percent	13600	576.6	594.11		594.6	0.000591	6.04	4255.27	1414.15	0.28
1 (1a)	2921	0.2-Percent	18000	576.6	595.64		596.08	0.000535	6.15	6446.61	1446.59	0.27
1 (1a)	1922	10-Percent	7990	573.7	591.43		591.52	0.000159	3.15	6696.9	1308.98	0.15
1 (1a)	1922	2-Percent	11800	573.7	593.4		593.49	0.000151	3.34	9344.27	1355.68	0.14
1 (1a)	1922	1-Percent	13600	573.7	594.12		594.22	0.000152	3.45	10348.69	1409.83	0.15
1 (1a)	1922	0.2-Percent	18000	573.7	595.61		595.71	0.00016	3.74	12703.76	1786.97	0.15
1 (1a)	833	10-Percent	7990	571.5	591.31		591.38	0.000094	2.65	5431.72	1295.17	0.11
1 (1a)	833	2-Percent	11800	571.5	593.29		593.36	0.000089	2.77	8382.02	1690.87	0.11
1 (1a)	833	1-Percent	13600	571.5	594.02		594.08	0.000088	2.82	9641.88	1774.35	0.11
1 (1a)	833	0.2-Percent	18000	571.5	595.51		595.58	0.000087	2.96	12526.76	2314.31	0.11
1 (1a)	279	10-Percent	7990	571	591.21	580.11	591.3	0.00012	2.8	4718.34	1042.68	0.13
1 (1a)	279	2-Percent	11800	571	593.19	581.81	593.28	0.00012	3.04	6888.45	1267.82	0.13
1 (1a)	279	1-Percent	13600	571	593.91	582.54	594	0.00012	3.12	7968.79	1787.95	0.13
1 (1a)	279	0.2-Percent	18000	571	595.4	584.12	595.5	0.00012	3.29	11205.39	2338.5	0.13

## **Flood Scenario #2**

### **Flood Bench Configuration: 1b**

Plan: UPDATE-FB-1B-SCHOOL-OPEN

Geometry: UPDATE-FB-1B-SCHOOL-OPEN

Steady Flow Data: USGS BF,10,2,1,0.2-PERCENT-UPDATE-BC

Date: December 2022




Figure 16: Flood Scenario #2 (1b) Profile Plot

Table 7: Flood Scenario 2 HEC-RAS Output

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl
2 (1b)	20483	10-Percent	7990	621.4	631.44		632.23	0.00152	7.14	1149.93	159.75	0.42
2 (1b)	20483	2-Percent	11800	621.4	633.13		634.27	0.001801	8.71	1502.7	283.71	0.47
2 (1b)	20483	1-Percent	13600	621.4	633.75		635.03	0.001907	9.3	1683.22	292.19	0.49
2 (1b)	20483	0.2-Percent	18000	621.4	635.05		636.62	0.002117	10.53	2068.6	300.59	0.52
2 (1b)	19313	10-Percent	7990	620.4	628.71		629.8	0.002908	8.44	1044.14	306.61	0.56
2 (1b)	19313	2-Percent	11800	620.4	630.2		631.56	0.003003	9.73	1584.75	383.6	0.58
2 (1b)	19313	1-Percent	13600	620.4	630.82		632.26	0.002981	10.15	1839	441.87	0.59
2 (1b)	19313	0.2-Percent	18000	620.4	632.18	630.62	633.75	0.002879	10.93	2522.14	587.78	0.59
2 (1b)	18244	10-Percent	7990	617.6	626.65		627.29	0.001757	6.95	1777.22	467.86	0.44
2 (1b)	18244	2-Percent	11800	617.6	628.34		629.05	0.001639	7.65	2590.92	496.45	0.44
2 (1b)	18244	1-Percent	13600	617.6	629.04		629.77	0.001597	7.92	2942.21	525.34	0.44
2 (1b)	18244	0.2-Percent	18000	617.6	630.55		631.34	0.001514	8.46	3805.28	582.51	0.44
2 (1b)	17053	10-Percent	7990	615.5	624.35		625.09	0.001916	7.31	1642.27	449.95	0.46
2 (1b)	17053	2-Percent	11800	615.5	625.99		626.9	0.001963	8.38	2445.93	516.05	0.48
2 (1b)	17053	1-Percent	13600	615.5	626.65		627.63	0.001977	8.8	2794.51	525.92	0.49
2 (1b)	17053	0.2-Percent	18000	615.5	628.13		629.25	0.001985	9.65	3589.78	557.64	0.5
2 (1b)	15751	10-Percent	7990	612.8	621.48		622.31	0.002376	7.65	1275.64	297.31	0.5
2 (1b)	15751	2-Percent	11800	612.8	622.94		624	0.002512	8.9	1759.86	349.52	0.53
2 (1b)	15751	1-Percent	13600	612.8	623.57		624.72	0.002518	9.34	1985.58	360.25	0.54
2 (1b)	15751	0.2-Percent	18000	612.8	625.09		626.39	0.002415	10.12	2545.4	374.73	0.54
2 (1b)	14403	10-Percent	7990	610.3	619.25		619.71	0.001482	6.2	2234.3	539.57	0.4
2 (1b)	14403	2-Percent	11800	610.3	621.12		621.56	0.001194	6.45	3263.7	572.17	0.37
2 (1b)	14403	1-Percent	13600	610.3	621.93		622.37	0.001093	6.52	3734.74	594.17	0.36
2 (1b)	14403	0.2-Percent	18000	610.3	623.88		624.29	0.00087	6.53	5014.3	708.31	0.33
2 (1b)	12986	10-Percent	7990	608.9	617.09		617.64	0.001416	6.23	1736.27	495.45	0.39
2 (1b)	12986	2-Percent	11800	608.9	619.49		620	0.001016	6.31	3498.64	888.93	0.35
2 (1b)	12986	1-Percent	13600	608.9	620.52		620.99	0.000867	6.22	4438.68	920.06	0.33
2 (1b)	12986	0.2-Percent	18000	608.9	622.83		623.23	0.000643	6.07	6623.01	966.59	0.29
2 (1b)	12162	10-Percent	7990	604.9	614.98		616.12	0.002284	8.62	955.8	117.56	0.5
2 (1b)	12162	2-Percent	11800	604.9	617.01		618.63	0.002504	10.32	1205.03	134.66	0.55
2 (1b)	12162	1-Percent	13600	604.9	617.86		619.71	0.002579	11.01	1326.02	158.14	0.56
2 (1b)	12162	0.2-Percent	18000	604.9	620.19	615.89	622.17	0.002287	11.67	2144.46	464.7	0.54
2 (1b)	11955	10-Percent	7990	605.5	614.34	611.72	615.59	0.00286	8.95	895.71	113.2	0.56
2 (1b)	11955	2-Percent	11800	605.5	616.31	613.35	618.05	0.003008	10.62	1120.3	115.54	0.59
2 (1b)	11955	1-Percent	13600	605.5	617.14	614.06	619.11	0.003059	11.29	1217.31	121.14	0.6
2 (1b)	11955	0.2-Percent	18000	605.5	619.16	615.65	621.59	0.003014	12.55	1459.52	154.88	0.62
2 (1b)	11860 Union Rd	Bridge										
2 (1b)	11789	10-Percent	7990	605.5	613.21	611.45	614.81	0.004409	10.13	789.56	110.22	0.66
2 (1b)	11789	2-Percent	11800	605.5	614.77	613.12	617.12	0.005034	12.32	962.04	111.86	0.73
2 (1b)	11789	1-Percent	13600	605.5	615.3	613.85	618.08	0.005496	13.38	1021.68	112.36	0.77
2 (1b)	11789	0.2-Percent	18000	605.5	616.4	615.46	620.28	0.00662	15.82	1147.98	117.14	0.86
2 (1b)	11675	10-Percent	7990	602.4	613.3		614.14	0.001656	7.39	1090.08	125.8	0.43
2 (1b)	11675	2-Percent	11800	602.4	614.93		616.25	0.002073	9.24	1299.03	129.76	0.5
2 (1b)	11675	1-Percent	13600	602.4	615.51		617.09	0.002307	10.09	1374.63	131.08	0.53

Table 7: Flood Scenario 2 HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl
2 (1b)	11675	0.2-Percent	18000	602.4	616.75		618.98	0.00285	12.02	1539.74	137.59	0.6
2 (1b)	10302	10-Percent	7990	603.2	610.26		611.22	0.002817	7.94	1106.57	291.38	0.54
2 (1b)	10302	2-Percent	11800	603.2	611.87	609.46	613	0.002633	8.87	1797.94	548.49	0.54
2 (1b)	10302	1-Percent	13600	603.2	612.52	610.2	613.66	0.002497	9.09	2170.41	588.78	0.54
2 (1b)	10302	0.2-Percent	18000	603.2	613.23	612.13	614.7	0.003059	10.58	2588.13	602.95	0.6
2 (1b)	9372	10-Percent	7990	599.6	605.24	604.78	607.03	0.007893	10.72	748.14	158.9	0.86
2 (1b)	9372	2-Percent	11800	599.6	606.49	606.07	608.92	0.007951	12.53	954.94	197.16	0.89
2 (1b)	9372	1-Percent	13600	599.6	607	606.96	609.69	0.007959	13.23	1068.17	247.62	0.91
2 (1b)	9372	0.2-Percent	18000	599.6	608.87	608.87	611.04	0.005014	12.39	1721.36	525.34	0.75
2 (1b)	8312	10-Percent	7990	595.5	605.14		605.3	0.000447	3.66	3982.49	730.2	0.22
2 (1b)	8312	2-Percent	11800	595.5	606.69		606.91	0.000496	4.32	5182.31	800.7	0.24
2 (1b)	8312	1-Percent	13600	595.5	607.32		607.57	0.000514	4.59	5693.11	807.28	0.25
2 (1b)	8312	0.2-Percent	18000	595.5	608.74		609.04	0.000546	5.15	6851.67	828.63	0.26
2 (1b)	8145	10-Percent	7990	592.1	605.04	597.15	605.24	0.000278	3.63	2202.52	345.65	0.19
2 (1b)	8145	2-Percent	11800	592.1	606.47	598.29	606.82	0.000414	4.77	2471.61	453.21	0.23
2 (1b)	8145	1-Percent	13600	592.1	607.04	598.79	607.47	0.000477	5.27	2578.46	465.94	0.25
2 (1b)	8145	0.2-Percent	18000	592.1	608.27	599.9	608.91	0.000627	6.4	2810.36	492.28	0.29
2 (1b)	8049 Railroad Bridge	Bridge										
2 (1b)	7984	10-Percent	7990	592.1	604.61	599.55	605.03	0.000804	5.23	1554.94	372.48	0.3
2 (1b)	7984	2-Percent	11800	592.1	605.76	600.86	606.47	0.001171	6.83	1764.79	507.95	0.37
2 (1b)	7984	1-Percent	13600	592.1	606.17	601.43	607.05	0.001361	7.56	1841.14	526.76	0.41
2 (1b)	7984	0.2-Percent	18000	592.1	606.97	602.7	608.28	0.001868	9.29	1989.32	563.34	0.48
2 (1b)	7758	10-Percent	7990	595	604.09	600.48	604.59	0.001188	5.98	1571.34	590.41	0.37
2 (1b)	7758	2-Percent	11800	595	605.32	601.71	605.9	0.001254	6.73	2401.23	885.54	0.38
2 (1b)	7758	1-Percent	13600	595	605.76	602.23	606.36	0.001277	7	2721.66	917.7	0.39
2 (1b)	7758	0.2-Percent	18000	595	606.61	604.85	607.29	0.001397	7.73	3394.85	1140.43	0.41
2 (1b)	7564	10-Percent	7990	594.9	603.55		604.07	0.001331	6.15	1647.43	654.15	0.38
2 (1b)	7564	2-Percent	11800	594.9	604.89		605.36	0.001165	6.38	2708.66	899.03	0.37
2 (1b)	7564	1-Percent	13600	594.9	605.35		605.81	0.001129	6.49	3141.55	968.39	0.37
2 (1b)	7564	0.2-Percent	18000	594.9	606.26		606.71	0.001083	6.74	4174.01	1343	0.36
2 (1b)	7340	10-Percent	7990	594.8	603.1		603.51	0.00124	5.71	1796.62	632	0.37
2 (1b)	7340	2-Percent	11800	594.8	604.47		604.87	0.001106	6.04	2953.43	1060	0.36
2 (1b)	7340	1-Percent	13600	594.8	604.97		605.34	0.001034	6.05	3485.81	1123.95	0.35
2 (1b)	7340	0.2-Percent	18000	594.8	605.91		606.26	0.000952	6.19	4743.76	1545.29	0.34
2 (1b)	7151	10-Percent	7990	594.7	602.26		602.83	0.001747	6.18	1483.73	452.38	0.43
2 (1b)	7151	2-Percent	11800	594.7	603.58		604.23	0.001698	6.89	2377.46	920.58	0.43
2 (1b)	7151	1-Percent	13600	594.7	604.14		604.75	0.001552	6.9	2990.74	1334.92	0.42
2 (1b)	7151	0.2-Percent	18000	594.7	605.42		605.82	0.001009	6.11	5376.38	2118.76	0.35
2 (1b)	6890	10-Percent	7990	593	601.33	598.69	601.9	0.001835	6.22	1454.23	1740.4	0.43
2 (1b)	6890	2-Percent	11800	593	602.9	600.03	603.4	0.001363	6.21	2445.15	2170.14	0.39
2 (1b)	6890	1-Percent	13600	593	603.54	601.1	604	0.001192	6.11	2951.45	2250.88	0.37
2 (1b)	6890	0.2-Percent	18000	593	604.86	602.34	605.29	0.000975	6.09	4000.39	2355.14	0.34
2 (1b)	6631	10-Percent	7990	592	600	597.85	600.7	0.002437	6.7	1205.05	234.02	0.49
2 (1b)	6631	2-Percent	11800	592	601.46	598.95	602.36	0.002381	7.7	1617.87	392.59	0.51

Table 7: Flood Scenario 2 HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl
2 (1b)	6631	1-Percent	13600	592	602.05	599.43	603.03	0.002356	8.08	1812.13	514.37	0.51
2 (1b)	6631	0.2-Percent	18000	592	603.36	600.53	604.43	0.002204	8.66	2319.91	666.39	0.51
2 (1b)	6324	10-Percent	7990	590.5	598.96	595.72	599.5	0.00148	5.88	1399.73	263.71	0.39
2 (1b)	6324	2-Percent	11800	590.5	600.35	596.88	601.1	0.001659	7.03	1770.58	383.81	0.43
2 (1b)	6324	1-Percent	13600	590.5	600.91	597.36	601.75	0.00173	7.5	1923.18	447.3	0.44
2 (1b)	6324	0.2-Percent	18000	590.5	602.11	598.58	603.17	0.001895	8.53	2251.35	569.17	0.47
2 (1b)	6015	10-Percent	7990	588.7	596.9		597.9	0.003452	8.3	1073.82	281.35	0.59
2 (1b)	6015	2-Percent	11800	588.7	598.46		599.53	0.002888	8.84	1554.37	325.26	0.56
2 (1b)	6015	1-Percent	13600	588.7	599.08		600.18	0.002755	9.09	1759.31	340.31	0.56
2 (1b)	6015	0.2-Percent	18000	588.7	600.44		601.61	0.002503	9.59	2342.88	504.47	0.54
2 (1b)	5607	10-Percent	7990	587.3	595.13	592.95	595.84	0.002302	7.24	1232.57	263.32	0.49
2 (1b)	5607	2-Percent	11800	587.3	596.97	594.02	597.78	0.001975	7.87	1834.76	436.41	0.47
2 (1b)	5607	1-Percent	13600	587.3	597.71	594.71	598.53	0.001827	8.01	2161.59	441.01	0.46
2 (1b)	5607	0.2-Percent	18000	587.3	599.22	595.81	600.09	0.001674	8.47	2839.49	465.28	0.45
2 (1b)	5307	10-Percent	7990	585.8	594.63		594.95	0.000921	5.06	1908.79	357.47	0.32
2 (1b)	5307	2-Percent	11800	585.8	596.64		597	0.000755	5.34	2677.86	400.4	0.3
2 (1b)	5307	1-Percent	13600	585.8	597.41		597.78	0.000734	5.54	2985.7	406.32	0.3
2 (1b)	5307	0.2-Percent	18000	585.8	598.91		599.36	0.000761	6.16	3660.58	492.19	0.31
2 (1b)	5051	10-Percent	7990	584.3	594.17		594.49	0.000854	4.82	1895.88	320.29	0.31
2 (1b)	5051	2-Percent	11800	584.3	596.23		596.6	0.000742	5.26	2565.43	331.57	0.3
2 (1b)	5051	1-Percent	13600	584.3	597		597.4	0.000734	5.5	2867.61	477.89	0.3
2 (1b)	5051	0.2-Percent	18000	584.3	598.52		598.97	0.000717	5.95	3779.32	711.64	0.3
2 (1b)	4786	10-Percent	7990	582.8	593.59		594.05	0.000961	5.61	1529.04	204.32	0.33
2 (1b)	4786	2-Percent	11800	582.8	595.59		596.19	0.000971	6.46	2116.7	457.63	0.34
2 (1b)	4786	1-Percent	13600	582.8	596.36		596.98	0.00096	6.72	2506.75	576.63	0.35
2 (1b)	4786	0.2-Percent	18000	582.8	597.93		598.57	0.000909	7.11	3654.12	826.1	0.34
2 (1b)	4582	10-Percent	7990	582.7	593.03		593.59	0.001217	6.12	1392.88	205.08	0.37
2 (1b)	4582	2-Percent	11800	582.7	595.03		595.72	0.001187	6.95	1994.44	420.6	0.38
2 (1b)	4582	1-Percent	13600	582.7	595.79		596.52	0.001177	7.26	2402.89	618.65	0.38
2 (1b)	4582	0.2-Percent	18000	582.7	597.37		598.14	0.001119	7.72	3533.52	854.73	0.38
2 (1b)	4363	10-Percent	7990	582.5	592.71	588.54	593.12	0.000913	5.39	1641.92	237.07	0.32
2 (1b)	4363	2-Percent	11800	582.5	594.73	589.87	595.26	0.000906	6.17	2161.48	491.57	0.33
2 (1b)	4363	1-Percent	13600	582.5	595.48	590.39	596.06	0.000927	6.52	2387.73	683.43	0.34
2 (1b)	4363	0.2-Percent	18000	582.5	596.99	591.52	597.7	0.000983	7.29	3058.42	1123.5	0.36
2 (1b)	4182	10-Percent	7990	582.4	592.31	588.27	592.91	0.001282	6.23	1296.47	164.95	0.38
2 (1b)	4182	2-Percent	11800	582.4	594.17	589.64	595.03	0.001413	7.48	1626.48	243.93	0.41
2 (1b)	4182	1-Percent	13600	582.4	594.83	590.22	595.81	0.001505	8.04	1777.42	377.88	0.43
2 (1b)	4182	0.2-Percent	18000	582.4	596.15	591.56	597.41	0.001703	9.23	2152.41	632.12	0.46
2 (1b)	3997	10-Percent	7990	582.3	592.12	587.76	592.67	0.001125	5.95	1352.94	190.66	0.36
2 (1b)	3997	2-Percent	11800	582.3	593.96	589.1	594.76	0.001283	7.22	1664.48	223.99	0.39
2 (1b)	3997	1-Percent	13600	582.3	594.59	589.64	595.53	0.001394	7.82	1802.75	281.59	0.41
2 (1b)	3997	0.2-Percent	18000	582.3	595.81	590.98	597.1	0.001689	9.23	2124.72	512.9	0.46
2 (1b)	3670	10-Percent	7990	582.1	591.97		592.32	0.000786	5.14	3197.67	1118.11	0.3
2 (1b)	3670	2-Percent	11800	582.1	594.03		594.34	0.000623	5.24	5655.63	1230.59	0.28

Table 7: Flood Scenario 2 HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl
2 (1b)	3670	1-Percent	13600	582.1	594.75		595.07	0.000605	5.39	6554.79	1256.34	0.28
2 (1b)	3670	0.2-Percent	18000	582.1	596.18		596.52	0.000604	5.81	8437.7	1373.85	0.28
2 (1b)	2921	10-Percent	7990	576.6	591.5		591.86	0.000498	4.85	1852.73	452.33	0.25
2 (1b)	2921	2-Percent	11800	576.6	593.39		593.87	0.000588	5.82	3296.29	1158.38	0.28
2 (1b)	2921	1-Percent	13600	576.6	594.11		594.6	0.000591	6.04	4255.27	1414.15	0.28
2 (1b)	2921	0.2-Percent	18000	576.6	595.64		596.08	0.000535	6.15	6446.61	1446.59	0.27
2 (1b)	1922	10-Percent	7990	573.7	591.43		591.52	0.000159	3.15	6696.9	1308.98	0.15
2 (1b)	1922	2-Percent	11800	573.7	593.4		593.49	0.000151	3.34	9344.27	1355.68	0.14
2 (1b)	1922	1-Percent	13600	573.7	594.12		594.22	0.000152	3.45	10348.69	1409.83	0.15
2 (1b)	1922	0.2-Percent	18000	573.7	595.61		595.71	0.00016	3.74	12703.76	1786.97	0.15
2 (1b)	833	10-Percent	7990	571.5	591.31		591.38	0.000094	2.65	5431.72	1295.17	0.11
2 (1b)	833	2-Percent	11800	571.5	593.29		593.36	0.000089	2.77	8382.02	1690.87	0.11
2 (1b)	833	1-Percent	13600	571.5	594.02		594.08	0.000088	2.82	9641.88	1774.35	0.11
2 (1b)	833	0.2-Percent	18000	571.5	595.51		595.58	0.000087	2.96	12526.76	2314.31	0.11
2 (1b)	279	10-Percent	7990	571	591.21	580.11	591.3	0.00012	2.8	4718.34	1042.68	0.13
2 (1b)	279	2-Percent	11800	571	593.19	581.81	593.28	0.00012	3.04	6888.45	1267.82	0.13
2 (1b)	279	1-Percent	13600	571	593.91	582.54	594	0.00012	3.12	7968.79	1787.95	0.13
2 (1b)	279	0.2-Percent	18000	571	595.4	584.12	595.5	0.00012	3.29	11205.39	2338.5	0.13

## **Flood Scenario #3**

### **Flood Bench Configuration: 1b + 2**

Plan: UPDATE-FB-1B+2-SCHOOL+UNION

Geometry: UPDATE-FB-1B+2-SCHOOL+UNION

Steady Flow Data: USGS BF,10,2,1,0.2-PERCENT-UPDATE-BC

Date: December 2022




Figure 17: Flood Scenario #3 (1b+2) Profile Plot

Table 8: Flood Scenario 3 HEC-RAS Output

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl
3 (1b+2)	20483	10-Percent	7990	621.4	631.44		632.23	0.00152	7.14	1149.93	159.75	0.42
3 (1b+2)	20483	2-Percent	11800	621.4	633.13		634.27	0.001801	8.71	1502.7	283.71	0.47
3 (1b+2)	20483	1-Percent	13600	621.4	633.75		635.03	0.001907	9.3	1683.22	292.19	0.49
3 (1b+2)	20483	0.2-Percent	18000	621.4	635.05		636.62	0.002117	10.53	2068.6	300.59	0.52
3 (1b+2)	19313	10-Percent	7990	620.4	628.71		629.8	0.002908	8.44	1044.14	306.61	0.56
3 (1b+2)	19313	2-Percent	11800	620.4	630.2		631.56	0.003003	9.73	1584.75	383.6	0.58
3 (1b+2)	19313	1-Percent	13600	620.4	630.82		632.26	0.002981	10.15	1839	441.87	0.59
3 (1b+2)	19313	0.2-Percent	18000	620.4	632.18	630.62	633.75	0.002879	10.93	2522.14	587.78	0.59
3 (1b+2)	18244	10-Percent	7990	617.6	626.65		627.29	0.001757	6.95	1777.22	467.86	0.44
3 (1b+2)	18244	2-Percent	11800	617.6	628.34		629.05	0.001639	7.65	2590.92	496.45	0.44
3 (1b+2)	18244	1-Percent	13600	617.6	629.04		629.77	0.001597	7.92	2942.21	525.34	0.44
3 (1b+2)	18244	0.2-Percent	18000	617.6	630.55		631.34	0.001514	8.46	3805.28	582.51	0.44
3 (1b+2)	17053	10-Percent	7990	615.5	624.35		625.09	0.001916	7.31	1642.27	449.95	0.46
3 (1b+2)	17053	2-Percent	11800	615.5	625.99		626.9	0.001963	8.38	2445.93	516.05	0.48
3 (1b+2)	17053	1-Percent	13600	615.5	626.65		627.63	0.001977	8.8	2794.51	525.92	0.49
3 (1b+2)	17053	0.2-Percent	18000	615.5	628.13		629.25	0.001985	9.65	3589.78	557.64	0.5
3 (1b+2)	15751	10-Percent	7990	612.8	621.48		622.31	0.002376	7.65	1275.64	297.31	0.5
3 (1b+2)	15751	2-Percent	11800	612.8	622.94		624	0.002512	8.9	1759.86	349.52	0.53
3 (1b+2)	15751	1-Percent	13600	612.8	623.57		624.72	0.002518	9.34	1985.54	360.25	0.54
3 (1b+2)	15751	0.2-Percent	18000	612.8	625.09		626.39	0.002415	10.12	2545.4	374.73	0.54
3 (1b+2)	14403	10-Percent	7990	610.3	619.25		619.71	0.001482	6.2	2234.3	539.57	0.4
3 (1b+2)	14403	2-Percent	11800	610.3	621.12		621.56	0.001194	6.45	3263.7	572.17	0.37
3 (1b+2)	14403	1-Percent	13600	610.3	621.93		622.37	0.001093	6.52	3734.67	594.16	0.36
3 (1b+2)	14403	0.2-Percent	18000	610.3	623.88		624.29	0.00087	6.53	5014.3	708.31	0.33
3 (1b+2)	12986	10-Percent	7990	608.9	617.09		617.64	0.001416	6.23	1736.24	495.42	0.39
3 (1b+2)	12986	2-Percent	11800	608.9	619.49		620	0.001016	6.31	3498.58	888.92	0.35
3 (1b+2)	12986	1-Percent	13600	608.9	620.52		620.99	0.000867	6.22	4438.57	920.06	0.33
3 (1b+2)	12986	0.2-Percent	18000	608.9	622.83		623.23	0.000643	6.07	6623.01	966.59	0.29
3 (1b+2)	12162	10-Percent	7990	604.9	614.98		616.12	0.002284	8.62	955.79	117.56	0.5
3 (1b+2)	12162	2-Percent	11800	604.9	617.01		618.63	0.002504	10.32	1205.03	134.66	0.55
3 (1b+2)	12162	1-Percent	13600	604.9	617.86		619.71	0.002579	11.01	1325.98	158.12	0.56
3 (1b+2)	12162	0.2-Percent	18000	604.9	620.19	615.89	622.17	0.002287	11.67	2144.46	464.7	0.54
3 (1b+2)	11955	10-Percent	7990	605.5	614.34	611.72	615.59	0.00286	8.95	895.69	113.2	0.56
3 (1b+2)	11955	2-Percent	11800	605.5	616.31	613.35	618.05	0.003009	10.62	1120.29	115.54	0.59
3 (1b+2)	11955	1-Percent	13600	605.5	617.14	614.06	619.11	0.003059	11.29	1217.27	121.13	0.6
3 (1b+2)	11955	0.2-Percent	18000	605.5	619.16	615.65	621.59	0.003014	12.55	1459.52	154.88	0.62
3 (1b+2)	11860 Union Rd	Bridge										
3 (1b+2)	11789	10-Percent	7990	605.5	613.21	611.45	614.81	0.00441	10.13	789.54	110.22	0.66
3 (1b+2)	11789	2-Percent	11800	605.5	614.77	613.12	617.12	0.005034	12.32	962	111.86	0.73
3 (1b+2)	11789	1-Percent	13600	605.5	615.3	613.85	618.08	0.005498	13.39	1021.52	112.36	0.77
3 (1b+2)	11789	0.2-Percent	18000	605.5	616.4	615.46	620.28	0.00662	15.82	1147.98	117.14	0.86
3 (1b+2)	11675	10-Percent	7990	602.4	613.3		614.14	0.001656	7.39	1090.07	125.8	0.43
3 (1b+2)	11675	2-Percent	11800	602.4	614.93		616.25	0.002073	9.24	1298.99	129.76	0.5
3 (1b+2)	11675	1-Percent	13600	602.4	615.51		617.08	0.002308	10.09	1374.45	131.08	0.53

Table 8: Flood Scenario 3 HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl
3 (1b+2)	11675	0.2-Percent	18000	602.4	616.75		618.98	0.00285	12.02	1539.74	137.59	0.6
3 (1b+2)	10302	10-Percent	7990	603.2	610.26		611.22	0.002813	7.94	1107.3	292.29	0.54
3 (1b+2)	10302	2-Percent	11800	603.2	611.88	609.46	613	0.002627	8.87	1800.25	548.94	0.54
3 (1b+2)	10302	1-Percent	13600	603.2	612.53	610.2	613.67	0.002485	9.07	2175.95	588.9	0.54
3 (1b+2)	10302	0.2-Percent	18000	603.2	613.23	612.13	614.7	0.003059	10.58	2588.13	602.95	0.6
3 (1b+2)	9372	10-Percent	7990	599.6	605.24	604.78	607.03	0.007922	10.73	747.32	158.88	0.86
3 (1b+2)	9372	2-Percent	11800	599.6	606.48	606.07	608.92	0.007995	12.56	953.03	196.55	0.9
3 (1b+2)	9372	1-Percent	13600	599.6	606.99	606.96	609.69	0.008041	13.27	1063.57	246.35	0.91
3 (1b+2)	9372	0.2-Percent	18000	599.6	608.87	608.87	611.04	0.005014	12.39	1721.36	525.34	0.75
3 (1b+2)	8312	10-Percent	7990	595.5	605.13		605.3	0.000448	3.66	3977.5	729.99	0.22
3 (1b+2)	8312	2-Percent	11800	595.5	606.68		606.9	0.000498	4.33	5173.91	800.62	0.24
3 (1b+2)	8312	1-Percent	13600	595.5	607.31		607.56	0.000518	4.6	5680.4	807.09	0.25
3 (1b+2)	8312	0.2-Percent	18000	595.5	608.72		609.02	0.000551	5.16	6832.04	828.49	0.26
3 (1b+2)	8145	10-Percent	7990	592.1	605.03	597.15	605.24	0.000279	3.63	2201.23	345.42	0.19
3 (1b+2)	8145	2-Percent	11800	592.1	606.46	598.29	606.81	0.000415	4.78	2469.59	452.94	0.23
3 (1b+2)	8145	1-Percent	13600	592.1	607.02	598.79	607.45	0.000479	5.28	2575.44	465.57	0.25
3 (1b+2)	8145	0.2-Percent	18000	592.1	608.25	599.9	608.89	0.000631	6.42	2805.71	491.81	0.29
3 (1b+2)	8049 Railroad Bridge	Bridge										
3 (1b+2)	7984	10-Percent	7990	592.1	604.6	599.55	605.02	0.000806	5.24	1553.52	372.31	0.3
3 (1b+2)	7984	2-Percent	11800	592.1	605.75	600.86	606.46	0.001177	6.84	1762.38	507.54	0.37
3 (1b+2)	7984	1-Percent	13600	592.1	606.15	601.43	607.03	0.00137	7.58	1837.35	526.21	0.41
3 (1b+2)	7984	0.2-Percent	18000	592.1	606.93	602.7	608.25	0.001888	9.32	1982.55	562.04	0.48
3 (1b+2)	7758	10-Percent	7990	595	604.07	600.48	604.58	0.001196	5.99	1564.85	584.87	0.37
3 (1b+2)	7758	2-Percent	11800	595	605.3	601.71	605.88	0.001269	6.76	2387.08	884.7	0.39
3 (1b+2)	7758	1-Percent	13600	595	605.73	602.23	606.34	0.001296	7.04	2700.41	915.44	0.39
3 (1b+2)	7758	0.2-Percent	18000	595	606.55	604.85	607.25	0.001438	7.82	3345.36	1126.73	0.42
3 (1b+2)	7564	10-Percent	7990	594.9	603.54		604.05	0.001341	6.17	1636.84	650.92	0.38
3 (1b+2)	7564	2-Percent	11800	594.9	604.86		605.34	0.001189	6.43	2681.88	895.78	0.37
3 (1b+2)	7564	1-Percent	13600	594.9	605.31		605.78	0.001163	6.57	3099.05	960.34	0.37
3 (1b+2)	7564	0.2-Percent	18000	594.9	606.18		606.65	0.001143	6.89	4066.84	1304.78	0.37
3 (1b+2)	7340	10-Percent	7990	594.8	603.07		603.49	0.001258	5.74	1781.57	621.76	0.37
3 (1b+2)	7340	2-Percent	11800	594.8	604.43		604.84	0.001143	6.12	2905.99	1058.09	0.36
3 (1b+2)	7340	1-Percent	13600	594.8	604.9		605.29	0.001081	6.16	3415.74	1102.46	0.36
3 (1b+2)	7340	0.2-Percent	18000	594.8	605.8		606.18	0.001025	6.37	4577.88	1475.12	0.35
3 (1b+2)	7151	10-Percent	7990	594.7	602.22		602.8	0.001795	6.24	1463.64	445.93	0.43
3 (1b+2)	7151	2-Percent	11800	594.7	603.47		604.16	0.001829	7.09	2275.9	894.27	0.45
3 (1b+2)	7151	1-Percent	13600	594.7	603.98		604.66	0.001729	7.19	2793.81	1168.31	0.44
3 (1b+2)	7151	0.2-Percent	18000	594.7	605.19		605.67	0.001214	6.6	4894.4	2032.81	0.38
3 (1b+2)	6890	10-Percent	7990	593	601.19	598.69	601.8	0.002024	6.43	1387.67	1693.42	0.45
3 (1b+2)	6890	2-Percent	11800	593	602.67	600.03	603.24	0.001591	6.58	2268.16	2115.82	0.42
3 (1b+2)	6890	1-Percent	13600	593	603.27	601.1	603.8	0.00142	6.53	2734.39	2219.07	0.4
3 (1b+2)	6890	0.2-Percent	18000	593	604.55	602.34	605.05	0.001152	6.48	3753.82	2343.46	0.37
3 (1b+2)	6631	10-Percent	7990	592	599.49	597.85	600.33	0.003348	7.38	1091.73	219.63	0.57
3 (1b+2)	6631	2-Percent	11800	592	600.69	598.95	601.88	0.003598	8.78	1383.69	328.67	0.61

Table 8: Flood Scenario 3 HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl
3 (1b+2)	6631	1-Percent	13600	592	601.2	599.43	602.51	0.003626	9.27	1537.54	373.4	0.62
3 (1b+2)	6631	0.2-Percent	18000	592	602.34	600.53	603.88	0.003579	10.2	1918.42	543.99	0.63
3 (1b+2)	6324	10-Percent	7990	590.5	598.14	595.72	598.7	0.001949	6.2	1424.51	310.4	0.44
3 (1b+2)	6324	2-Percent	11800	590.5	599.22	597.16	600.02	0.002287	7.49	1765.57	319.73	0.49
3 (1b+2)	6324	1-Percent	13600	590.5	599.72	597.59	600.61	0.002347	7.93	1925.24	327.33	0.5
3 (1b+2)	6324	0.2-Percent	18000	590.5	600.87	598.51	601.95	0.002415	8.83	2293.43	493.75	0.52
3 (1b+2)	6015	10-Percent	7990	588.7	596.19		596.89	0.00334	7.52	1383.01	443.78	0.57
3 (1b+2)	6015	2-Percent	11800	588.7	597.71		598.33	0.002284	7.34	2095.37	485.04	0.49
3 (1b+2)	6015	1-Percent	13600	588.7	598.39		598.98	0.001969	7.25	2425.36	489.45	0.46
3 (1b+2)	6015	0.2-Percent	18000	588.7	599.83		600.42	0.001571	7.27	3141.28	502.02	0.43
3 (1b+2)	5607	10-Percent	7990	587.3	595.12	593.15	595.42	0.001235	5.29	2034.49	514.23	0.36
3 (1b+2)	5607	2-Percent	11800	587.3	597.04	593.92	597.32	0.000823	5.11	3032.95	522.27	0.31
3 (1b+2)	5607	1-Percent	13600	587.3	597.8	594.25	598.08	0.00075	5.16	3428.14	524.92	0.3
3 (1b+2)	5607	0.2-Percent	18000	587.3	599.32	594.87	599.63	0.000688	5.46	4239.77	548.12	0.29
3 (1b+2)	5307	10-Percent	7990	585.8	594.67		594.9	0.000686	4.39	2365.25	479.65	0.28
3 (1b+2)	5307	2-Percent	11800	585.8	596.71		596.94	0.000524	4.47	3353.51	487.91	0.25
3 (1b+2)	5307	1-Percent	13600	585.8	597.49		597.73	0.000502	4.6	3732.04	491.75	0.25
3 (1b+2)	5307	0.2-Percent	18000	585.8	599.02		599.3	0.000505	5.05	4553.23	574.48	0.25
3 (1b+2)	5051	10-Percent	7990	584.3	594.17		594.49	0.000854	4.82	1895.88	320.29	0.31
3 (1b+2)	5051	2-Percent	11800	584.3	596.23		596.6	0.000742	5.26	2565.43	331.57	0.3
3 (1b+2)	5051	1-Percent	13600	584.3	597		597.4	0.000734	5.5	2867.61	477.89	0.3
3 (1b+2)	5051	0.2-Percent	18000	584.3	598.52		598.97	0.000717	5.95	3779.32	711.64	0.3
3 (1b+2)	4786	10-Percent	7990	582.8	593.59		594.05	0.000961	5.61	1529.04	204.32	0.33
3 (1b+2)	4786	2-Percent	11800	582.8	595.59		596.19	0.000971	6.46	2116.7	457.63	0.34
3 (1b+2)	4786	1-Percent	13600	582.8	596.36		596.98	0.00096	6.72	2506.75	576.63	0.35
3 (1b+2)	4786	0.2-Percent	18000	582.8	597.93		598.57	0.000909	7.11	3654.12	826.1	0.34
3 (1b+2)	4582	10-Percent	7990	582.7	593.03		593.59	0.001217	6.12	1392.88	205.08	0.37
3 (1b+2)	4582	2-Percent	11800	582.7	595.03		595.72	0.001187	6.95	1994.44	420.6	0.38
3 (1b+2)	4582	1-Percent	13600	582.7	595.79		596.52	0.001177	7.26	2402.89	618.65	0.38
3 (1b+2)	4582	0.2-Percent	18000	582.7	597.37		598.14	0.001119	7.72	3533.52	854.73	0.38
3 (1b+2)	4363	10-Percent	7990	582.5	592.71	588.54	593.12	0.000913	5.39	1641.92	237.07	0.32
3 (1b+2)	4363	2-Percent	11800	582.5	594.73	589.87	595.26	0.000906	6.17	2161.48	491.57	0.33
3 (1b+2)	4363	1-Percent	13600	582.5	595.48	590.39	596.06	0.000927	6.52	2387.73	683.43	0.34
3 (1b+2)	4363	0.2-Percent	18000	582.5	596.99	591.52	597.7	0.000983	7.29	3058.42	1123.5	0.36
3 (1b+2)	4182	10-Percent	7990	582.4	592.31	588.27	592.91	0.001282	6.23	1296.47	164.95	0.38
3 (1b+2)	4182	2-Percent	11800	582.4	594.17	589.64	595.03	0.001413	7.48	1626.48	243.93	0.41
3 (1b+2)	4182	1-Percent	13600	582.4	594.83	590.22	595.81	0.001505	8.04	1777.42	377.88	0.43
3 (1b+2)	4182	0.2-Percent	18000	582.4	596.15	591.56	597.41	0.001703	9.23	2152.41	632.12	0.46
3 (1b+2)	3997	10-Percent	7990	582.3	592.12	587.76	592.67	0.001125	5.95	1352.94	190.66	0.36
3 (1b+2)	3997	2-Percent	11800	582.3	593.96	589.1	594.76	0.001283	7.22	1664.48	223.99	0.39
3 (1b+2)	3997	1-Percent	13600	582.3	594.59	589.64	595.53	0.001394	7.82	1802.75	281.59	0.41
3 (1b+2)	3997	0.2-Percent	18000	582.3	595.81	590.98	597.1	0.001689	9.23	2124.72	512.9	0.46
3 (1b+2)	3670	10-Percent	7990	582.1	591.97		592.32	0.000786	5.14	3197.67	1118.11	0.3
3 (1b+2)	3670	2-Percent	11800	582.1	594.03		594.34	0.000623	5.24	5655.63	1230.59	0.28

Table 8: Flood Scenario 3 HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl
3 (1b+2)	3670	1-Percent	13600	582.1	594.75		595.07	0.000605	5.39	6554.79	1256.34	0.28
3 (1b+2)	3670	0.2-Percent	18000	582.1	596.18		596.52	0.000604	5.81	8437.7	1373.85	0.28
3 (1b+2)	2921	10-Percent	7990	576.6	591.5		591.86	0.000498	4.85	1852.73	452.33	0.25
3 (1b+2)	2921	2-Percent	11800	576.6	593.39		593.87	0.000588	5.82	3296.29	1158.38	0.28
3 (1b+2)	2921	1-Percent	13600	576.6	594.11		594.6	0.000591	6.04	4255.27	1414.15	0.28
3 (1b+2)	2921	0.2-Percent	18000	576.6	595.64		596.08	0.000535	6.15	6446.61	1446.59	0.27
3 (1b+2)	1922	10-Percent	7990	573.7	591.43		591.52	0.000159	3.15	6696.9	1308.98	0.15
3 (1b+2)	1922	2-Percent	11800	573.7	593.4		593.49	0.000151	3.34	9344.27	1355.68	0.14
3 (1b+2)	1922	1-Percent	13600	573.7	594.12		594.22	0.000152	3.45	10348.69	1409.83	0.15
3 (1b+2)	1922	0.2-Percent	18000	573.7	595.61		595.71	0.00016	3.74	12703.76	1786.97	0.15
3 (1b+2)	833	10-Percent	7990	571.5	591.31		591.38	0.000094	2.65	5431.72	1295.17	0.11
3 (1b+2)	833	2-Percent	11800	571.5	593.29		593.36	0.000089	2.77	8382.02	1690.87	0.11
3 (1b+2)	833	1-Percent	13600	571.5	594.02		594.08	0.000088	2.82	9641.88	1774.35	0.11
3 (1b+2)	833	0.2-Percent	18000	571.5	595.51		595.58	0.000087	2.96	12526.76	2314.31	0.11
3 (1b+2)	279	10-Percent	7990	571	591.21	580.11	591.3	0.00012	2.8	4718.34	1042.68	0.13
3 (1b+2)	279	2-Percent	11800	571	593.19	581.81	593.28	0.00012	3.04	6888.45	1267.82	0.13
3 (1b+2)	279	1-Percent	13600	571	593.91	582.54	594	0.00012	3.12	7968.79	1787.95	0.13
3 (1b+2)	279	0.2-Percent	18000	571	595.4	584.12	595.5	0.00012	3.29	11205.39	2338.5	0.13

## **Flood Scenario #4**

### **Flood Bench Configuration: 2 + 3**

Plan: UPDATE-FB-2+3-UNION+CLINTON

Geometry: UPDATE-FB-2+3-UNION+CLINTON

Steady Flow Data: USGS BF,10,2,1,0.2-PERCENT-UPDATE-BC

Date: December 2022




Figure 18: Flood Scenario #4 (2+3) Profile Plot

Table 9: Flood Scenario 4 HEC-RAS Output

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl
4 (2+3)	20483	10-Percent	7990	621.4	631.44		632.23	0.00152	7.14	1149.93	159.75	0.42
4 (2+3)	20483	2-Percent	11800	621.4	633.13		634.27	0.001801	8.71	1502.7	283.71	0.47
4 (2+3)	20483	1-Percent	13600	621.4	633.75		635.03	0.001907	9.3	1683.22	292.19	0.49
4 (2+3)	20483	0.2-Percent	18000	621.4	635.05		636.62	0.002117	10.53	2068.6	300.59	0.52
4 (2+3)	19313	10-Percent	7990	620.4	628.71		629.8	0.002908	8.44	1044.16	306.63	0.56
4 (2+3)	19313	2-Percent	11800	620.4	630.2		631.56	0.003003	9.73	1584.75	383.6	0.58
4 (2+3)	19313	1-Percent	13600	620.4	630.82		632.26	0.002981	10.15	1839	441.87	0.59
4 (2+3)	19313	0.2-Percent	18000	620.4	632.18	630.62	633.75	0.002879	10.93	2522.14	587.78	0.59
4 (2+3)	18244	10-Percent	7990	617.6	626.65		627.29	0.001757	6.95	1777.24	467.86	0.44
4 (2+3)	18244	2-Percent	11800	617.6	628.34		629.05	0.001639	7.65	2590.92	496.45	0.44
4 (2+3)	18244	1-Percent	13600	617.6	629.04		629.77	0.001597	7.92	2942.21	525.34	0.44
4 (2+3)	18244	0.2-Percent	18000	617.6	630.55		631.34	0.001514	8.46	3805.28	582.51	0.44
4 (2+3)	17053	10-Percent	7990	615.5	624.35		625.09	0.001916	7.31	1642.29	449.96	0.46
4 (2+3)	17053	2-Percent	11800	615.5	625.99		626.9	0.001963	8.38	2445.93	516.05	0.48
4 (2+3)	17053	1-Percent	13600	615.5	626.65		627.63	0.001977	8.8	2794.51	525.92	0.49
4 (2+3)	17053	0.2-Percent	18000	615.5	628.13		629.25	0.001985	9.65	3589.78	557.64	0.5
4 (2+3)	15751	10-Percent	7990	612.8	621.48		622.31	0.002377	7.65	1275.62	297.31	0.5
4 (2+3)	15751	2-Percent	11800	612.8	622.94		624	0.002512	8.9	1759.86	349.52	0.53
4 (2+3)	15751	1-Percent	13600	612.8	623.57		624.72	0.002518	9.34	1985.54	360.25	0.54
4 (2+3)	15751	0.2-Percent	18000	612.8	625.09		626.39	0.002415	10.12	2545.4	374.73	0.54
4 (2+3)	14403	10-Percent	7990	610.3	619.25		619.71	0.001482	6.2	2234.26	539.57	0.4
4 (2+3)	14403	2-Percent	11800	610.3	621.12		621.56	0.001194	6.45	3263.52	572.17	0.37
4 (2+3)	14403	1-Percent	13600	610.3	621.93		622.37	0.001093	6.52	3734.63	594.15	0.36
4 (2+3)	14403	0.2-Percent	18000	610.3	623.88		624.29	0.00087	6.53	5014.3	708.31	0.33
4 (2+3)	12986	10-Percent	7990	608.9	617.09		617.64	0.001417	6.23	1736.03	495.23	0.39
4 (2+3)	12986	2-Percent	11800	608.9	619.48		619.99	0.001017	6.31	3497.77	888.88	0.35
4 (2+3)	12986	1-Percent	13600	608.9	620.52		620.99	0.000867	6.22	4438.4	920.05	0.33
4 (2+3)	12986	0.2-Percent	18000	608.9	622.83		623.23	0.000643	6.07	6623.01	966.59	0.29
4 (2+3)	12162	10-Percent	7990	604.9	614.98		616.12	0.002285	8.62	955.66	117.56	0.5
4 (2+3)	12162	2-Percent	11800	604.9	617.01		618.63	0.002506	10.32	1204.74	134.63	0.55
4 (2+3)	12162	1-Percent	13600	604.9	617.86		619.71	0.002579	11.01	1325.92	158.1	0.56
4 (2+3)	12162	0.2-Percent	18000	604.9	620.19	615.89	622.17	0.002287	11.67	2144.46	464.7	0.54
4 (2+3)	11955	10-Percent	7990	605.5	614.34	611.72	615.58	0.002862	8.96	895.5	113.2	0.56
4 (2+3)	11955	2-Percent	11800	605.5	616.3	613.35	618.05	0.003012	10.62	1119.92	115.53	0.59
4 (2+3)	11955	1-Percent	13600	605.5	617.14	614.06	619.11	0.003059	11.29	1217.22	121.11	0.6
4 (2+3)	11955	0.2-Percent	18000	605.5	619.16	615.65	621.59	0.003014	12.55	1459.52	154.88	0.62
4 (2+3)	11860 Union Rd	Bridge										
4 (2+3)	11789	10-Percent	7990	605.5	613.21	611.45	614.81	0.004418	10.14	789.07	110.21	0.66
4 (2+3)	11789	2-Percent	11800	605.5	614.75	613.12	617.12	0.005056	12.33	960.74	111.85	0.73
4 (2+3)	11789	1-Percent	13600	605.5	615.29	613.85	618.08	0.005503	13.39	1021.27	112.36	0.77
4 (2+3)	11789	0.2-Percent	18000	605.5	616.4	615.46	620.28	0.00662	15.82	1147.98	117.14	0.86
4 (2+3)	11675	10-Percent	7990	602.4	613.29		614.14	0.001658	7.4	1089.54	125.79	0.43
4 (2+3)	11675	2-Percent	11800	602.4	614.92		616.24	0.002081	9.25	1297.57	129.74	0.5
4 (2+3)	11675	1-Percent	13600	602.4	615.51		617.08	0.00231	10.09	1374.17	131.07	0.53

Table 9: Flood Scenario 4 HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl
4 (2+3)	11675	0.2-Percent	18000	602.4	616.75		618.98	0.00285	12.02	1539.74	137.59	0.6
4 (2+3)	10302	10-Percent	7990	603.2	610.48		611.37	0.002505	7.65	1175.86	345.04	0.51
4 (2+3)	10302	2-Percent	11800	603.2	612.06	609.46	613.1	0.002394	8.59	1900.99	568.72	0.52
4 (2+3)	10302	1-Percent	13600	603.2	612.55	610.2	613.67	0.002466	9.05	2184.57	589.07	0.53
4 (2+3)	10302	0.2-Percent	18000	603.2	613.23	612.13	614.7	0.003059	10.58	2588.13	602.95	0.6
4 (2+3)	9372	10-Percent	7990	599.6	604.78	604.78	606.96	0.011022	11.85	675.35	156.98	1
4 (2+3)	9372	2-Percent	11800	599.6	606.07	606.07	608.89	0.010151	13.5	880.47	161.34	1
4 (2+3)	9372	1-Percent	13600	599.6	606.96	606.96	609.69	0.008171	13.34	1056.49	244.39	0.92
4 (2+3)	9372	0.2-Percent	18000	599.6	608.87	608.87	611.04	0.005014	12.39	1721.36	525.34	0.75
4 (2+3)	8312	10-Percent	7990	595.5	603.94		604.2	0.00082	4.47	3131.96	697.64	0.3
4 (2+3)	8312	2-Percent	11800	595.5	605.49		605.82	0.000826	5.12	4247.17	748.23	0.31
4 (2+3)	8312	1-Percent	13600	595.5	606.2		606.54	0.000806	5.33	4791.85	794.5	0.31
4 (2+3)	8312	0.2-Percent	18000	595.5	607.86		608.24	0.00074	5.69	6130.08	815.63	0.3
4 (2+3)	8145	10-Percent	7990	592.1	603.85	597.15	604.1	0.000398	4.04	1979.2	263.12	0.22
4 (2+3)	8145	2-Percent	11800	592.1	605.27	598.29	605.69	0.00057	5.26	2245.28	350.63	0.27
4 (2+3)	8145	1-Percent	13600	592.1	605.89	598.79	606.41	0.000638	5.75	2363.3	424.47	0.29
4 (2+3)	8145	0.2-Percent	18000	592.1	607.35	599.9	608.08	0.000775	6.82	2637.65	472.71	0.32
4 (2+3)	8049 Railroad Bridge	Bridge										
4 (2+3)	7984	10-Percent	7990	592.1	603.17	599.55	603.78	0.001431	6.24	1297.73	219.45	0.39
4 (2+3)	7984	2-Percent	11800	592.1	604.14	600.86	605.16	0.002093	8.16	1471.03	343.08	0.49
4 (2+3)	7984	1-Percent	13600	592.1	604.54	601.43	605.78	0.002386	8.97	1543.34	371.05	0.52
4 (2+3)	7984	0.2-Percent	18000	592.1	605.4	602.7	607.19	0.00307	10.81	1699.94	488.39	0.6
4 (2+3)	7758	10-Percent	7990	595	602.82	601.27	603.1	0.001057	5.05	2343.3	710.66	0.34
4 (2+3)	7758	2-Percent	11800	595	603.89	601.98	604.2	0.001055	5.54	3105.06	739.59	0.34
4 (2+3)	7758	1-Percent	13600	595	604.36	602.25	604.69	0.001036	5.7	3446.22	800.62	0.34
4 (2+3)	7758	0.2-Percent	18000	595	605.44	602.81	605.8	0.000987	6.03	4228.38	889.99	0.34
4 (2+3)	7564	10-Percent	7990	594.9	602.37		602.64	0.001138	5.11	2365.61	742.51	0.35
4 (2+3)	7564	2-Percent	11800	594.9	603.46		603.75	0.001082	5.5	3177.26	757.4	0.35
4 (2+3)	7564	1-Percent	13600	594.9	603.95		604.25	0.00104	5.62	3556.4	790.74	0.34
4 (2+3)	7564	0.2-Percent	18000	594.9	605.08		605.39	0.000926	5.77	4544.25	947.08	0.33
4 (2+3)	7340	10-Percent	7990	594.8	601.84		602.13	0.001348	5.28	2354.1	864.7	0.37
4 (2+3)	7340	2-Percent	11800	594.8	603.04		603.3	0.001056	5.25	3447.27	989.11	0.34
4 (2+3)	7340	1-Percent	13600	594.8	603.58		603.82	0.000955	5.23	3993.86	1055.84	0.33
4 (2+3)	7340	0.2-Percent	18000	594.8	604.79		605.02	0.000753	5.1	5303.49	1097.02	0.3
4 (2+3)	7151	10-Percent	7990	594.7	601.36		601.57	0.001071	4.39	2627.07	871.15	0.33
4 (2+3)	7151	2-Percent	11800	594.7	602.68		602.87	0.000781	4.31	3880.22	998.2	0.29
4 (2+3)	7151	1-Percent	13600	594.7	603.26		603.44	0.000697	4.29	4478.38	1099.75	0.28
4 (2+3)	7151	0.2-Percent	18000	594.7	604.55		604.72	0.000541	4.2	6193.56	1818.87	0.25
4 (2+3)	6890	10-Percent	7990	593	600.99	599.04	601.11	0.000652	3.57	3243.08	1872.66	0.26
4 (2+3)	6890	2-Percent	11800	593	602.43	599.53	602.55	0.000448	3.42	4904.01	2139.65	0.22
4 (2+3)	6890	1-Percent	13600	593	603.04	599.74	603.15	0.000396	3.39	5617.5	2196.94	0.21
4 (2+3)	6890	0.2-Percent	18000	593	604.38	600.18	604.49	0.00032	3.37	7206.65	2334.84	0.19
4 (2+3)	6631	10-Percent	7990	592	599.49	597.85	600.33	0.003353	7.38	1091.21	478.37	0.57
4 (2+3)	6631	2-Percent	11800	592	600.71	598.95	601.89	0.003571	8.76	1387.79	568.93	0.61

Table 9: Flood Scenario 4 HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.ChnL	Flow.Area	Top.Width	Froude...Chl
4 (2+3)	6631	1-Percent	13600	592	601.23	599.43	602.52	0.003572	9.23	1546.21	587.51	0.62
4 (2+3)	6631	0.2-Percent	18000	592	602.43	600.53	603.92	0.003416	10.04	1954.26	706.2	0.62
4 (2+3)	6324	10-Percent	7990	590.5	598.13	595.72	598.69	0.001961	6.22	1421.33	310.33	0.44
4 (2+3)	6324	2-Percent	11800	590.5	599.27	597.16	600.05	0.002225	7.42	1781.87	319.78	0.49
4 (2+3)	6324	1-Percent	13600	590.5	599.82	597.59	600.67	0.002237	7.81	1956.12	335.18	0.49
4 (2+3)	6324	0.2-Percent	18000	590.5	601.11	598.51	602.12	0.002178	8.54	2371.73	504.94	0.5
4 (2+3)	6015	10-Percent	7990	588.7	596.26		596.92	0.003156	7.37	1411.89	444.22	0.56
4 (2+3)	6015	2-Percent	11800	588.7	597.94		598.49	0.001964	6.95	2205.94	486.32	0.46
4 (2+3)	6015	1-Percent	13600	588.7	598.68		599.2	0.001657	6.82	2568.55	491.99	0.43
4 (2+3)	6015	0.2-Percent	18000	588.7	600.3		600.81	0.001257	6.73	3378.05	507.78	0.38
4 (2+3)	5607	10-Percent	7990	587.3	595.34	593.15	595.61	0.001057	5	2147.26	515.3	0.34
4 (2+3)	5607	2-Percent	11800	587.3	597.38	593.92	597.63	0.00069	4.8	3212.32	523.39	0.28
4 (2+3)	5607	1-Percent	13600	587.3	598.2	594.25	598.44	0.000624	4.84	3637.94	526.41	0.27
4 (2+3)	5607	0.2-Percent	18000	587.3	599.9	594.87	600.17	0.000553	5.07	4562.11	568.88	0.26
4 (2+3)	5307	10-Percent	7990	585.8	594.96		595.16	0.00058	4.13	2504.06	480.77	0.25
4 (2+3)	5307	2-Percent	11800	585.8	597.11		597.31	0.000441	4.21	3547.23	489.88	0.23
4 (2+3)	5307	1-Percent	13600	585.8	597.94		598.15	0.00042	4.33	3954.66	499.38	0.23
4 (2+3)	5307	0.2-Percent	18000	585.8	599.66		599.9	0.000402	4.66	4927.78	588.01	0.23
4 (2+3)	5051	10-Percent	7990	584.3	594.2	590.41	594.7	0.001202	5.74	1436.22	206.59	0.36
4 (2+3)	5051	2-Percent	11800	584.3	596.26	591.62	596.91	0.001151	6.57	1948.53	301.22	0.37
4 (2+3)	5051	1-Percent	13600	584.3	597.06	592.13	597.76	0.00113	6.86	2225.73	360.37	0.37
4 (2+3)	5051	0.2-Percent	18000	584.3	598.75	593.33	599.52	0.001078	7.39	2838.24	366.48	0.37
4 (2+3)	4786	10-Percent	7990	582.8	593.61	589.12	594.17	0.001084	5.97	1354.02	162.68	0.35
4 (2+3)	4786	2-Percent	11800	582.8	595.6	590.5	596.36	0.001161	7.07	1761.02	226.8	0.38
4 (2+3)	4786	1-Percent	13600	582.8	596.36	591.06	597.2	0.001191	7.49	1953.77	261.47	0.39
4 (2+3)	4786	0.2-Percent	18000	582.8	597.93	592.42	598.95	0.001261	8.38	2367.37	266.15	0.41
4 (2+3)	4582	10-Percent	7990	582.7	593.03	589.02	593.66	0.001319	6.37	1278.39	165.23	0.38
4 (2+3)	4582	2-Percent	11800	582.7	594.99	590.43	595.82	0.001372	7.45	1675.35	219.76	0.41
4 (2+3)	4582	1-Percent	13600	582.7	595.71	591.03	596.65	0.001416	7.92	1836.98	225.28	0.42
4 (2+3)	4582	0.2-Percent	18000	582.7	597.16	592.41	598.35	0.00156	9.01	2174.87	252.83	0.45
4 (2+3)	4363	10-Percent	7990	582.5	592.55	588.33	593.14	0.001221	6.16	1312.26	164.05	0.37
4 (2+3)	4363	2-Percent	11800	582.5	594.45	589.72	595.28	0.00134	7.37	1652.17	369.96	0.4
4 (2+3)	4363	1-Percent	13600	582.5	595.14	590.3	596.08	0.00141	7.89	1836.59	549.17	0.42
4 (2+3)	4363	0.2-Percent	18000	582.5	596.59	591.65	597.72	0.0015	8.82	2375.41	958.21	0.44
4 (2+3)	4182	10-Percent	7990	582.4	592.31	588.27	592.91	0.001282	6.23	1296.47	164.95	0.38
4 (2+3)	4182	2-Percent	11800	582.4	594.17	589.64	595.03	0.001413	7.48	1626.48	243.93	0.41
4 (2+3)	4182	1-Percent	13600	582.4	594.83	590.22	595.81	0.001505	8.04	1777.42	377.88	0.43
4 (2+3)	4182	0.2-Percent	18000	582.4	596.15	591.56	597.41	0.001703	9.23	2152.41	632.12	0.46
4 (2+3)	3997	10-Percent	7990	582.3	592.12	587.76	592.67	0.001125	5.95	1352.94	190.66	0.36
4 (2+3)	3997	2-Percent	11800	582.3	593.96	589.1	594.76	0.001283	7.22	1664.48	223.99	0.39
4 (2+3)	3997	1-Percent	13600	582.3	594.59	589.64	595.53	0.001394	7.82	1802.75	281.59	0.41
4 (2+3)	3997	0.2-Percent	18000	582.3	595.81	590.98	597.1	0.001689	9.23	2124.72	512.9	0.46
4 (2+3)	3670	10-Percent	7990	582.1	591.97		592.32	0.000786	5.14	3197.67	1118.11	0.3
4 (2+3)	3670	2-Percent	11800	582.1	594.03		594.34	0.000623	5.24	5655.63	1230.59	0.28

Table 9: Flood Scenario 4 HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl
4 (2+3)	3670	1-Percent	13600	582.1	594.75		595.07	0.000605	5.39	6554.79	1256.34	0.28
4 (2+3)	3670	0.2-Percent	18000	582.1	596.18		596.52	0.000604	5.81	8437.7	1373.85	0.28
4 (2+3)	2921	10-Percent	7990	576.6	591.5		591.86	0.000498	4.85	1852.73	452.33	0.25
4 (2+3)	2921	2-Percent	11800	576.6	593.39		593.87	0.000588	5.82	3296.29	1158.38	0.28
4 (2+3)	2921	1-Percent	13600	576.6	594.11		594.6	0.000591	6.04	4255.27	1414.15	0.28
4 (2+3)	2921	0.2-Percent	18000	576.6	595.64		596.08	0.000535	6.15	6446.61	1446.59	0.27
4 (2+3)	1922	10-Percent	7990	573.7	591.43		591.52	0.000159	3.15	6696.9	1308.98	0.15
4 (2+3)	1922	2-Percent	11800	573.7	593.4		593.49	0.000151	3.34	9344.27	1355.68	0.14
4 (2+3)	1922	1-Percent	13600	573.7	594.12		594.22	0.000152	3.45	10348.69	1409.83	0.15
4 (2+3)	1922	0.2-Percent	18000	573.7	595.61		595.71	0.00016	3.74	12703.76	1786.97	0.15
4 (2+3)	833	10-Percent	7990	571.5	591.31		591.38	0.000094	2.65	5431.72	1295.17	0.11
4 (2+3)	833	2-Percent	11800	571.5	593.29		593.36	0.000089	2.77	8382.02	1690.87	0.11
4 (2+3)	833	1-Percent	13600	571.5	594.02		594.08	0.000088	2.82	9641.88	1774.35	0.11
4 (2+3)	833	0.2-Percent	18000	571.5	595.51		595.58	0.000087	2.96	12526.76	2314.31	0.11
4 (2+3)	279	10-Percent	7990	571	591.21	580.11	591.3	0.00012	2.8	4718.34	1042.68	0.13
4 (2+3)	279	2-Percent	11800	571	593.19	581.81	593.28	0.00012	3.04	6888.45	1267.82	0.13
4 (2+3)	279	1-Percent	13600	571	593.91	582.54	594	0.00012	3.12	7968.79	1787.95	0.13
4 (2+3)	279	0.2-Percent	18000	571	595.4	584.12	595.5	0.00012	3.29	11205.39	2338.5	0.13

## **Flood Scenario #5**

**Flood Bench Configuration: 1b + 2 + 3**

Plan: UPDATE-FB-1b+2+3-SCHOOL+UNION+CLINTON

Geometry: UPDATE-FB-1b+2+3-SCHOOL+UNION+CLINTON

Steady Flow Data: USGS BF,10,2,1,0.2-PERCENT-UPDATE-BC

Date: December 2022




Figure 19: Flood Scenario #5 (1b+2+3) Profile Plot

Table 10: Flood Scenario 5 HEC-RAS Output

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl
5 (1b+2+3)	20483	10-Percent	7990	621.4	631.44		632.23	0.00152	7.14	1149.93	159.75	0.42
5 (1b+2+3)	20483	2-Percent	11800	621.4	633.13		634.27	0.001801	8.71	1502.7	283.71	0.47
5 (1b+2+3)	20483	1-Percent	13600	621.4	633.75		635.03	0.001907	9.3	1683.22	292.19	0.49
5 (1b+2+3)	20483	0.2-Percent	18000	621.4	635.05		636.62	0.002117	10.53	2068.6	300.59	0.52
5 (1b+2+3)	19313	10-Percent	7990	620.4	628.71		629.8	0.002908	8.44	1044.16	306.63	0.56
5 (1b+2+3)	19313	2-Percent	11800	620.4	630.2		631.56	0.003003	9.73	1584.75	383.6	0.58
5 (1b+2+3)	19313	1-Percent	13600	620.4	630.82		632.26	0.002981	10.15	1839	441.87	0.59
5 (1b+2+3)	19313	0.2-Percent	18000	620.4	632.18	630.62	633.75	0.002879	10.93	2522.14	587.78	0.59
5 (1b+2+3)	18244	10-Percent	7990	617.6	626.65		627.29	0.001757	6.95	1777.24	467.86	0.44
5 (1b+2+3)	18244	2-Percent	11800	617.6	628.34		629.05	0.001639	7.65	2590.92	496.45	0.44
5 (1b+2+3)	18244	1-Percent	13600	617.6	629.04		629.77	0.001597	7.92	2942.21	525.34	0.44
5 (1b+2+3)	18244	0.2-Percent	18000	617.6	630.55		631.34	0.001514	8.46	3805.28	582.51	0.44
5 (1b+2+3)	17053	10-Percent	7990	615.5	624.35		625.09	0.001916	7.31	1642.29	449.96	0.46
5 (1b+2+3)	17053	2-Percent	11800	615.5	625.99		626.9	0.001963	8.38	2445.93	516.05	0.48
5 (1b+2+3)	17053	1-Percent	13600	615.5	626.65		627.63	0.001977	8.8	2794.51	525.92	0.49
5 (1b+2+3)	17053	0.2-Percent	18000	615.5	628.13		629.25	0.001985	9.65	3589.78	557.64	0.5
5 (1b+2+3)	15751	10-Percent	7990	612.8	621.48		622.31	0.002377	7.65	1275.62	297.31	0.5
5 (1b+2+3)	15751	2-Percent	11800	612.8	622.94		624	0.002512	8.9	1759.86	349.52	0.53
5 (1b+2+3)	15751	1-Percent	13600	612.8	623.57		624.72	0.002518	9.34	1985.54	360.25	0.54
5 (1b+2+3)	15751	0.2-Percent	18000	612.8	625.09		626.39	0.002415	10.12	2545.4	374.73	0.54
5 (1b+2+3)	14403	10-Percent	7990	610.3	619.25		619.71	0.001482	6.2	2234.26	539.57	0.4
5 (1b+2+3)	14403	2-Percent	11800	610.3	621.12		621.56	0.001194	6.45	3263.52	572.17	0.37
5 (1b+2+3)	14403	1-Percent	13600	610.3	621.93		622.37	0.001093	6.52	3734.63	594.15	0.36
5 (1b+2+3)	14403	0.2-Percent	18000	610.3	623.88		624.29	0.00087	6.53	5014.3	708.31	0.33
5 (1b+2+3)	12986	10-Percent	7990	608.9	617.09		617.64	0.001417	6.23	1736.03	495.23	0.39
5 (1b+2+3)	12986	2-Percent	11800	608.9	619.48		619.99	0.001017	6.31	3497.77	888.88	0.35
5 (1b+2+3)	12986	1-Percent	13600	608.9	620.52		620.99	0.000867	6.22	4438.4	920.05	0.33
5 (1b+2+3)	12986	0.2-Percent	18000	608.9	622.83		623.23	0.000643	6.07	6623.01	966.59	0.29
5 (1b+2+3)	12162	10-Percent	7990	604.9	614.98		616.12	0.002285	8.62	955.66	117.56	0.5
5 (1b+2+3)	12162	2-Percent	11800	604.9	617.01		618.63	0.002506	10.32	1204.74	134.63	0.55
5 (1b+2+3)	12162	1-Percent	13600	604.9	617.86		619.71	0.002579	11.01	1325.92	158.1	0.56
5 (1b+2+3)	12162	0.2-Percent	18000	604.9	620.19	615.89	622.17	0.002287	11.67	2144.46	464.7	0.54
5 (1b+2+3)	11955	10-Percent	7990	605.5	614.34	611.72	615.58	0.002862	8.96	895.5	113.2	0.56
5 (1b+2+3)	11955	2-Percent	11800	605.5	616.3	613.35	618.05	0.003012	10.62	1119.92	115.53	0.59
5 (1b+2+3)	11955	1-Percent	13600	605.5	617.14	614.06	619.11	0.003059	11.29	1217.22	121.11	0.6
5 (1b+2+3)	11955	0.2-Percent	18000	605.5	619.16	615.65	621.59	0.003014	12.55	1459.52	154.88	0.62
5 (1b+2+3)	11860 Union Rd	Bridge										
5 (1b+2+3)	11789	10-Percent	7990	605.5	613.21	611.45	614.81	0.004418	10.14	789.07	110.21	0.66
5 (1b+2+3)	11789	2-Percent	11800	605.5	614.75	613.12	617.12	0.005056	12.33	960.74	111.85	0.73
5 (1b+2+3)	11789	1-Percent	13600	605.5	615.29	613.85	618.08	0.005503	13.39	1021.27	112.36	0.77
5 (1b+2+3)	11789	0.2-Percent	18000	605.5	616.4	615.46	620.28	0.006662	15.82	1147.98	117.14	0.86
5 (1b+2+3)	11675	10-Percent	7990	602.4	613.29		614.14	0.001658	7.4	1089.54	125.79	0.43
5 (1b+2+3)	11675	2-Percent	11800	602.4	614.92		616.24	0.002081	9.25	1297.57	129.74	0.5
5 (1b+2+3)	11675	1-Percent	13600	602.4	615.51		617.08	0.00231	10.09	1374.17	131.07	0.53

Table 10: Flood Scenario 5 HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl
5 (1b+2+3)	11675	0.2-Percent	18000	602.4	616.75		618.98	0.00285	12.02	1539.74	137.59	0.6
5 (1b+2+3)	10302	10-Percent	7990	603.2	610.48		611.37	0.002505	7.65	1175.86	345.04	0.51
5 (1b+2+3)	10302	2-Percent	11800	603.2	612.06	609.46	613.1	0.002394	8.59	1900.99	568.72	0.52
5 (1b+2+3)	10302	1-Percent	13600	603.2	612.55	610.2	613.67	0.002466	9.05	2184.57	589.07	0.53
5 (1b+2+3)	10302	0.2-Percent	18000	603.2	613.23	612.13	614.7	0.003059	10.58	2588.13	602.95	0.6
5 (1b+2+3)	9372	10-Percent	7990	599.6	604.78	604.78	606.96	0.011022	11.85	675.35	156.98	1
5 (1b+2+3)	9372	2-Percent	11800	599.6	606.07	606.07	608.89	0.010151	13.5	880.47	161.34	1
5 (1b+2+3)	9372	1-Percent	13600	599.6	606.96	606.96	609.69	0.008171	13.34	1056.49	244.39	0.92
5 (1b+2+3)	9372	0.2-Percent	18000	599.6	608.87	608.87	611.04	0.005014	12.39	1721.36	525.34	0.75
5 (1b+2+3)	8312	10-Percent	7990	595.5	603.94		604.2	0.00082	4.47	3132	697.64	0.3
5 (1b+2+3)	8312	2-Percent	11800	595.5	605.49		605.82	0.000826	5.12	4246.62	748.21	0.31
5 (1b+2+3)	8312	1-Percent	13600	595.5	606.2		606.54	0.000807	5.33	4790.59	794.37	0.31
5 (1b+2+3)	8312	0.2-Percent	18000	595.5	607.86		608.23	0.000741	5.7	6125.89	815.56	0.3
5 (1b+2+3)	8145	10-Percent	7990	592.1	603.85	597.15	604.1	0.000398	4.04	1979.22	263.12	0.22
5 (1b+2+3)	8145	2-Percent	11800	592.1	605.26	598.29	605.69	0.00057	5.26	2245.15	350.61	0.27
5 (1b+2+3)	8145	1-Percent	13600	592.1	605.89	598.79	606.41	0.000638	5.76	2362.99	424.34	0.29
5 (1b+2+3)	8145	0.2-Percent	18000	592.1	607.35	599.9	608.07	0.000776	6.83	2636.63	472.62	0.32
5 (1b+2+3)	8049 Railroad Bridge	Bridge										
5 (1b+2+3)	7984	10-Percent	7990	592.1	603.17	599.55	603.78	0.001431	6.24	1297.76	219.46	0.39
5 (1b+2+3)	7984	2-Percent	11800	592.1	604.14	600.86	605.16	0.002094	8.16	1470.83	343	0.49
5 (1b+2+3)	7984	1-Percent	13600	592.1	604.54	601.43	605.78	0.002388	8.98	1542.86	370.99	0.52
5 (1b+2+3)	7984	0.2-Percent	18000	592.1	605.39	602.7	607.19	0.003082	10.82	1697.83	486.81	0.6
5 (1b+2+3)	7758	10-Percent	7990	595	602.82	601.27	603.1	0.001057	5.05	2343.38	710.66	0.34
5 (1b+2+3)	7758	2-Percent	11800	595	603.89	601.98	604.2	0.001056	5.54	3103.96	739.45	0.34
5 (1b+2+3)	7758	1-Percent	13600	595	604.36	602.25	604.69	0.001038	5.71	3443.67	799.22	0.34
5 (1b+2+3)	7758	0.2-Percent	18000	595	605.43	602.81	605.79	0.000995	6.04	4217.86	889.63	0.34
5 (1b+2+3)	7564	10-Percent	7990	594.9	602.37		602.64	0.001138	5.11	2365.74	742.51	0.35
5 (1b+2+3)	7564	2-Percent	11800	594.9	603.45		603.75	0.001083	5.5	3175.64	757.22	0.35
5 (1b+2+3)	7564	1-Percent	13600	594.9	603.94		604.25	0.001044	5.62	3552.59	790.47	0.34
5 (1b+2+3)	7564	0.2-Percent	18000	594.9	605.06		605.37	0.000936	5.79	4526.85	941	0.33
5 (1b+2+3)	7340	10-Percent	7990	594.8	601.84		602.13	0.001347	5.28	2354.42	864.7	0.37
5 (1b+2+3)	7340	2-Percent	11800	594.8	603.04		603.3	0.001058	5.25	3444.25	988.81	0.34
5 (1b+2+3)	7340	1-Percent	13600	594.8	603.57		603.81	0.00096	5.24	3986.84	1055.56	0.33
5 (1b+2+3)	7340	0.2-Percent	18000	594.8	604.77		605	0.000763	5.13	5278.85	1096.4	0.3
5 (1b+2+3)	7151	10-Percent	7990	594.7	601.36		601.57	0.00107	4.39	2627.6	871.16	0.33
5 (1b+2+3)	7151	2-Percent	11800	594.7	602.68		602.87	0.000783	4.32	3876.14	998.06	0.29
5 (1b+2+3)	7151	1-Percent	13600	594.7	603.25		603.43	0.000701	4.3	4469.05	1099.06	0.28
5 (1b+2+3)	7151	0.2-Percent	18000	594.7	604.52		604.69	0.00055	4.23	6145.03	1795.84	0.25
5 (1b+2+3)	6890	10-Percent	7990	593	600.99	599.04	601.11	0.000651	3.57	3244.13	1872.91	0.26
5 (1b+2+3)	6890	2-Percent	11800	593	602.43	599.53	602.54	0.00045	3.42	4898.1	2139.54	0.22
5 (1b+2+3)	6890	1-Percent	13600	593	603.03	599.74	603.14	0.000399	3.39	5605.72	2193.77	0.21
5 (1b+2+3)	6890	0.2-Percent	18000	593	604.35	600.18	604.46	0.000325	3.39	7171.71	2333.01	0.2
5 (1b+2+3)	6631	10-Percent	7990	592	599.49	597.85	600.33	0.003348	7.38	1091.73	478.4	0.57
5 (1b+2+3)	6631	2-Percent	11800	592	600.69	598.95	601.88	0.003598	8.78	1383.69	568.64	0.61

Table 10: Flood Scenario 5 HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl
5 (1b+2+3)	6631	1-Percent	13600	592	601.2	599.43	602.51	0.003626	9.27	1537.54	586.08	0.62
5 (1b+2+3)	6631	0.2-Percent	18000	592	602.34	600.53	603.88	0.003579	10.2	1918.42	700.35	0.63
5 (1b+2+3)	6324	10-Percent	7990	590.5	598.14	595.72	598.7	0.001949	6.2	1424.51	310.4	0.44
5 (1b+2+3)	6324	2-Percent	11800	590.5	599.22	597.16	600.02	0.002287	7.49	1765.57	319.73	0.49
5 (1b+2+3)	6324	1-Percent	13600	590.5	599.72	597.59	600.61	0.002347	7.93	1925.24	327.33	0.5
5 (1b+2+3)	6324	0.2-Percent	18000	590.5	600.87	598.51	601.95	0.002415	8.83	2293.43	493.75	0.52
5 (1b+2+3)	6015	10-Percent	7990	588.7	596.19		596.89	0.00334	7.52	1383.01	443.78	0.57
5 (1b+2+3)	6015	2-Percent	11800	588.7	597.71		598.33	0.002284	7.34	2095.37	485.04	0.49
5 (1b+2+3)	6015	1-Percent	13600	588.7	598.39		598.98	0.001969	7.25	2425.36	489.45	0.46
5 (1b+2+3)	6015	0.2-Percent	18000	588.7	599.83		600.42	0.001571	7.27	3141.28	502.02	0.43
5 (1b+2+3)	5607	10-Percent	7990	587.3	595.12	593.15	595.42	0.001235	5.29	2034.49	514.23	0.36
5 (1b+2+3)	5607	2-Percent	11800	587.3	597.04	593.92	597.32	0.000823	5.11	3032.95	522.27	0.31
5 (1b+2+3)	5607	1-Percent	13600	587.3	597.8	594.25	598.08	0.00075	5.16	3428.14	524.92	0.3
5 (1b+2+3)	5607	0.2-Percent	18000	587.3	599.32	594.87	599.63	0.000688	5.46	4239.77	548.12	0.29
5 (1b+2+3)	5307	10-Percent	7990	585.8	594.67		594.9	0.000686	4.39	2365.25	479.65	0.28
5 (1b+2+3)	5307	2-Percent	11800	585.8	596.71		596.94	0.000524	4.47	3353.51	487.91	0.25
5 (1b+2+3)	5307	1-Percent	13600	585.8	597.49		597.73	0.000502	4.6	3732.04	491.75	0.25
5 (1b+2+3)	5307	0.2-Percent	18000	585.8	599.02		599.3	0.000505	5.05	4553.23	574.48	0.25
5 (1b+2+3)	5051	10-Percent	7990	584.3	594.17		594.49	0.000854	4.82	1895.88	320.29	0.31
5 (1b+2+3)	5051	2-Percent	11800	584.3	596.23		596.6	0.000742	5.26	2565.43	331.57	0.3
5 (1b+2+3)	5051	1-Percent	13600	584.3	597		597.4	0.000734	5.5	2867.61	477.89	0.3
5 (1b+2+3)	5051	0.2-Percent	18000	584.3	598.52		598.97	0.000717	5.95	3779.32	711.64	0.3
5 (1b+2+3)	4786	10-Percent	7990	582.8	593.59		594.05	0.000961	5.61	1529.04	204.32	0.33
5 (1b+2+3)	4786	2-Percent	11800	582.8	595.59		596.19	0.000971	6.46	2116.7	457.63	0.34
5 (1b+2+3)	4786	1-Percent	13600	582.8	596.36		596.98	0.00096	6.72	2506.75	576.63	0.35
5 (1b+2+3)	4786	0.2-Percent	18000	582.8	597.93		598.57	0.000909	7.11	3654.12	826.1	0.34
5 (1b+2+3)	4582	10-Percent	7990	582.7	593.03		593.59	0.001217	6.12	1392.88	205.08	0.37
5 (1b+2+3)	4582	2-Percent	11800	582.7	595.03		595.72	0.001187	6.95	1994.44	420.6	0.38
5 (1b+2+3)	4582	1-Percent	13600	582.7	595.79		596.52	0.001177	7.26	2402.89	618.65	0.38
5 (1b+2+3)	4582	0.2-Percent	18000	582.7	597.37		598.14	0.001119	7.72	3533.52	854.73	0.38
5 (1b+2+3)	4363	10-Percent	7990	582.5	592.71	588.54	593.12	0.000913	5.39	1641.92	237.07	0.32
5 (1b+2+3)	4363	2-Percent	11800	582.5	594.73	589.87	595.26	0.000906	6.17	2161.48	491.57	0.33
5 (1b+2+3)	4363	1-Percent	13600	582.5	595.48	590.39	596.06	0.000927	6.52	2387.73	683.43	0.34
5 (1b+2+3)	4363	0.2-Percent	18000	582.5	596.99	591.52	597.7	0.000983	7.29	3058.42	1123.5	0.36
5 (1b+2+3)	4182	10-Percent	7990	582.4	592.31	588.27	592.91	0.001282	6.23	1296.47	164.95	0.38
5 (1b+2+3)	4182	2-Percent	11800	582.4	594.17	589.64	595.03	0.001413	7.48	1626.48	243.93	0.41
5 (1b+2+3)	4182	1-Percent	13600	582.4	594.83	590.22	595.81	0.001505	8.04	1777.42	377.88	0.43
5 (1b+2+3)	4182	0.2-Percent	18000	582.4	596.15	591.56	597.41	0.001703	9.23	2152.41	632.12	0.46
5 (1b+2+3)	3997	10-Percent	7990	582.3	592.12	587.76	592.67	0.001125	5.95	1352.94	190.66	0.36
5 (1b+2+3)	3997	2-Percent	11800	582.3	593.96	589.1	594.76	0.001283	7.22	1664.48	223.99	0.39
5 (1b+2+3)	3997	1-Percent	13600	582.3	594.59	589.64	595.53	0.001394	7.82	1802.75	281.59	0.41
5 (1b+2+3)	3997	0.2-Percent	18000	582.3	595.81	590.98	597.1	0.001689	9.23	2124.72	512.9	0.46
5 (1b+2+3)	3670	10-Percent	7990	582.1	591.97		592.32	0.000786	5.14	3197.67	1118.11	0.3
5 (1b+2+3)	3670	2-Percent	11800	582.1	594.03		594.34	0.000623	5.24	5655.63	1230.59	0.28

Table 10: Flood Scenario 5 HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl
5 (1b+2+3)	3670	1-Percent	13600	582.1	594.75		595.07	0.000605	5.39	6554.79	1256.34	0.28
5 (1b+2+3)	3670	0.2-Percent	18000	582.1	596.18		596.52	0.000604	5.81	8437.7	1373.85	0.28
5 (1b+2+3)	2921	10-Percent	7990	576.6	591.5		591.86	0.000498	4.85	1852.73	452.33	0.25
5 (1b+2+3)	2921	2-Percent	11800	576.6	593.39		593.87	0.000588	5.82	3296.29	1158.38	0.28
5 (1b+2+3)	2921	1-Percent	13600	576.6	594.11		594.6	0.000591	6.04	4255.27	1414.15	0.28
5 (1b+2+3)	2921	0.2-Percent	18000	576.6	595.64		596.08	0.000535	6.15	6446.61	1446.59	0.27
5 (1b+2+3)	1922	10-Percent	7990	573.7	591.43		591.52	0.000159	3.15	6696.9	1308.98	0.15
5 (1b+2+3)	1922	2-Percent	11800	573.7	593.4		593.49	0.000151	3.34	9344.27	1355.68	0.14
5 (1b+2+3)	1922	1-Percent	13600	573.7	594.12		594.22	0.000152	3.45	10348.69	1409.83	0.15
5 (1b+2+3)	1922	0.2-Percent	18000	573.7	595.61		595.71	0.00016	3.74	12703.76	1786.97	0.15
5 (1b+2+3)	833	10-Percent	7990	571.5	591.31		591.38	0.000094	2.65	5431.72	1295.17	0.11
5 (1b+2+3)	833	2-Percent	11800	571.5	593.29		593.36	0.000089	2.77	8382.02	1690.87	0.11
5 (1b+2+3)	833	1-Percent	13600	571.5	594.02		594.08	0.000088	2.82	9641.88	1774.35	0.11
5 (1b+2+3)	833	0.2-Percent	18000	571.5	595.51		595.58	0.000087	2.96	12526.76	2314.31	0.11
5 (1b+2+3)	279	10-Percent	7990	571	591.21	580.11	591.3	0.00012	2.8	4718.34	1042.68	0.13
5 (1b+2+3)	279	2-Percent	11800	571	593.19	581.81	593.28	0.00012	3.04	6888.45	1267.82	0.13
5 (1b+2+3)	279	1-Percent	13600	571	593.91	582.54	594	0.00012	3.12	7968.79	1787.95	0.13
5 (1b+2+3)	279	0.2-Percent	18000	571	595.4	584.12	595.5	0.00012	3.29	11205.39	2338.5	0.13

## Flood Scenario #6

**Flood Bench Configuration: 2 + 3 + 4**

Plan: UPDATE-FB-2+3+4-UNION+CLINT+UTILI

Geometry: UPDATE-FB-2+3+4-UNION+CLINT+UTILI

Steady Flow Data: USGS BF,10,2,1,0.2-PERCENT-UPDATE-BC

Date: December 2022




Figure 20: Flood Scenario #6 (2+3+4) Profile Plot

Table 11: Flood Scenario 6 HEC-RAS Output

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.ChnL	Flow.Area	Top.Width	Froude...Chl
6 (2+3+4)	20483	10-Percent	7990	621.4	631.44		632.23	0.00152	7.14	1149.93	159.75	0.42
6 (2+3+4)	20483	2-Percent	11800	621.4	633.13		634.27	0.001801	8.71	1502.7	283.71	0.47
6 (2+3+4)	20483	1-Percent	13600	621.4	633.75		635.03	0.001907	9.3	1683.22	292.19	0.49
6 (2+3+4)	20483	0.2-Percent	18000	621.4	635.05		636.62	0.002117	10.53	2068.6	300.59	0.52
6 (2+3+4)	19313	10-Percent	7990	620.4	628.71		629.8	0.002908	8.44	1044.16	306.63	0.56
6 (2+3+4)	19313	2-Percent	11800	620.4	630.2		631.56	0.003003	9.73	1584.75	383.6	0.58
6 (2+3+4)	19313	1-Percent	13600	620.4	630.82		632.26	0.002981	10.15	1839	441.87	0.59
6 (2+3+4)	19313	0.2-Percent	18000	620.4	632.18	630.62	633.75	0.002879	10.93	2522.14	587.78	0.59
6 (2+3+4)	18244	10-Percent	7990	617.6	626.65		627.29	0.001757	6.95	1777.24	467.86	0.44
6 (2+3+4)	18244	2-Percent	11800	617.6	628.34		629.05	0.001639	7.65	2590.92	496.45	0.44
6 (2+3+4)	18244	1-Percent	13600	617.6	629.04		629.77	0.001597	7.92	2942.21	525.34	0.44
6 (2+3+4)	18244	0.2-Percent	18000	617.6	630.55		631.34	0.001514	8.46	3805.28	582.51	0.44
6 (2+3+4)	17053	10-Percent	7990	615.5	624.35		625.09	0.001916	7.31	1642.29	449.96	0.46
6 (2+3+4)	17053	2-Percent	11800	615.5	625.99		626.9	0.001963	8.38	2445.93	516.05	0.48
6 (2+3+4)	17053	1-Percent	13600	615.5	626.65		627.63	0.001977	8.8	2794.51	525.92	0.49
6 (2+3+4)	17053	0.2-Percent	18000	615.5	628.13		629.25	0.001985	9.65	3589.78	557.64	0.5
6 (2+3+4)	15751	10-Percent	7990	612.8	621.48		622.31	0.002377	7.65	1275.62	297.31	0.5
6 (2+3+4)	15751	2-Percent	11800	612.8	622.94		624	0.002512	8.9	1759.86	349.52	0.53
6 (2+3+4)	15751	1-Percent	13600	612.8	623.57		624.72	0.002518	9.34	1985.54	360.25	0.54
6 (2+3+4)	15751	0.2-Percent	18000	612.8	625.09		626.39	0.002415	10.12	2545.4	374.73	0.54
6 (2+3+4)	14403	10-Percent	7990	610.3	619.25		619.71	0.001482	6.2	2234.26	539.57	0.4
6 (2+3+4)	14403	2-Percent	11800	610.3	621.12		621.56	0.001194	6.45	3263.52	572.17	0.37
6 (2+3+4)	14403	1-Percent	13600	610.3	621.93		622.37	0.001093	6.52	3734.63	594.15	0.36
6 (2+3+4)	14403	0.2-Percent	18000	610.3	623.88		624.29	0.00087	6.53	5014.3	708.31	0.33
6 (2+3+4)	12986	10-Percent	7990	608.9	617.09		617.64	0.001417	6.23	1736.03	495.23	0.39
6 (2+3+4)	12986	2-Percent	11800	608.9	619.48		619.99	0.001017	6.31	3497.77	888.88	0.35
6 (2+3+4)	12986	1-Percent	13600	608.9	620.52		620.99	0.000867	6.22	4438.4	920.05	0.33
6 (2+3+4)	12986	0.2-Percent	18000	608.9	622.83		623.23	0.000643	6.07	6623.01	966.59	0.29
6 (2+3+4)	12162	10-Percent	7990	604.9	614.98		616.12	0.002285	8.62	955.66	117.56	0.5
6 (2+3+4)	12162	2-Percent	11800	604.9	617.01		618.63	0.002506	10.32	1204.74	134.63	0.55
6 (2+3+4)	12162	1-Percent	13600	604.9	617.86		619.71	0.002579	11.01	1325.92	158.1	0.56
6 (2+3+4)	12162	0.2-Percent	18000	604.9	620.19	615.89	622.17	0.002287	11.67	2144.46	464.7	0.54
6 (2+3+4)	11955	10-Percent	7990	605.5	614.34	611.72	615.58	0.002862	8.96	895.5	113.2	0.56
6 (2+3+4)	11955	2-Percent	11800	605.5	616.3	613.35	618.05	0.003012	10.62	1119.92	115.53	0.59
6 (2+3+4)	11955	1-Percent	13600	605.5	617.14	614.06	619.11	0.003059	11.29	1217.22	121.11	0.6
6 (2+3+4)	11955	0.2-Percent	18000	605.5	619.16	615.65	621.59	0.003014	12.55	1459.52	154.88	0.62
6 (2+3+4)	11860 Union Rd	Bridge										
6 (2+3+4)	11789	10-Percent	7990	605.5	613.21	611.45	614.81	0.004418	10.14	789.07	110.21	0.66
6 (2+3+4)	11789	2-Percent	11800	605.5	614.75	613.12	617.12	0.005056	12.33	960.74	111.85	0.73
6 (2+3+4)	11789	1-Percent	13600	605.5	615.29	613.85	618.08	0.005503	13.39	1021.27	112.36	0.77
6 (2+3+4)	11789	0.2-Percent	18000	605.5	616.4	615.46	620.28	0.00662	15.82	1147.98	117.14	0.86
6 (2+3+4)	11675	10-Percent	7990	602.4	613.29		614.14	0.001658	7.4	1089.54	125.79	0.43
6 (2+3+4)	11675	2-Percent	11800	602.4	614.92		616.24	0.002081	9.25	1297.57	129.74	0.5
6 (2+3+4)	11675	1-Percent	13600	602.4	615.51		617.08	0.00231	10.09	1374.17	131.07	0.53

Table 11: Flood Scenario 6 HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl
6 (2+3+4)	11675	0.2-Percent	18000	602.4	616.75		618.98	0.00285	12.02	1539.74	137.59	0.6
6 (2+3+4)	10302	10-Percent	7990	603.2	610.48		611.37	0.002505	7.65	1175.86	345.04	0.51
6 (2+3+4)	10302	2-Percent	11800	603.2	612.06	609.46	613.1	0.002394	8.59	1900.99	568.72	0.52
6 (2+3+4)	10302	1-Percent	13600	603.2	612.55	610.2	613.67	0.002466	9.05	2184.57	589.07	0.53
6 (2+3+4)	10302	0.2-Percent	18000	603.2	613.23	612.13	614.7	0.003059	10.58	2588.13	602.95	0.6
6 (2+3+4)	9372	10-Percent	7990	599.6	604.78	604.78	606.96	0.011022	11.85	675.35	156.98	1
6 (2+3+4)	9372	2-Percent	11800	599.6	606.07	606.07	608.89	0.010151	13.5	880.47	161.34	1
6 (2+3+4)	9372	1-Percent	13600	599.6	606.96	606.96	609.69	0.008171	13.34	1056.49	244.39	0.92
6 (2+3+4)	9372	0.2-Percent	18000	599.6	608.87	608.87	611.04	0.005014	12.39	1721.36	525.34	0.75
6 (2+3+4)	8312	10-Percent	7990	595.5	603.91		604.17	0.000834	4.5	3111.22	697.33	0.3
6 (2+3+4)	8312	2-Percent	11800	595.5	605.39		605.73	0.000864	5.2	4173.39	744.96	0.31
6 (2+3+4)	8312	1-Percent	13600	595.5	606.07		606.43	0.000853	5.43	4687.7	786.79	0.31
6 (2+3+4)	8312	0.2-Percent	18000	595.5	607.69		608.08	0.000787	5.81	5988.43	812.9	0.31
6 (2+3+4)	8145	10-Percent	7990	592.1	603.82	597.15	604.07	0.000401	4.05	1973.62	262.54	0.22
6 (2+3+4)	8145	2-Percent	11800	592.1	605.17	598.29	605.6	0.000586	5.3	2226.69	348.48	0.27
6 (2+3+4)	8145	1-Percent	13600	592.1	605.76	598.79	606.28	0.000661	5.82	2338.17	412.95	0.29
6 (2+3+4)	8145	0.2-Percent	18000	592.1	607.17	599.9	607.91	0.000809	6.91	2603.29	468.86	0.33
6 (2+3+4)	8049 Railroad Bridge	Bridge										
6 (2+3+4)	7984	10-Percent	7990	592.1	603.14	599.55	603.74	0.001456	6.27	1290.85	218.39	0.4
6 (2+3+4)	7984	2-Percent	11800	592.1	603.99	600.86	605.05	0.002224	8.31	1443.41	331.69	0.5
6 (2+3+4)	7984	1-Percent	13600	592.1	604.31	601.43	605.62	0.002602	9.22	1501.92	366.27	0.54
6 (2+3+4)	7984	0.2-Percent	18000	592.1	604.97	602.7	606.94	0.003567	11.32	1621.73	409.76	0.64
6 (2+3+4)	7758	10-Percent	7990	595	602.76	601.27	603.05	0.001108	5.14	2301.49	710.29	0.34
6 (2+3+4)	7758	2-Percent	11800	595	603.66	601.98	604.02	0.001233	5.88	2940.69	729.5	0.37
6 (2+3+4)	7758	1-Percent	13600	595	604.03	602.25	604.41	0.00128	6.17	3204.59	757.22	0.38
6 (2+3+4)	7758	0.2-Percent	18000	595	604.86	602.81	605.31	0.001359	6.78	3800.71	864.34	0.4
6 (2+3+4)	7564	10-Percent	7990	594.9	602.27		602.56	0.001235	5.27	2294.86	741.96	0.36
6 (2+3+4)	7564	2-Percent	11800	594.9	603.11		603.47	0.001379	6.03	2919.38	747.37	0.39
6 (2+3+4)	7564	1-Percent	13600	594.9	603.46		603.85	0.001435	6.34	3178.46	757.43	0.4
6 (2+3+4)	7564	0.2-Percent	18000	594.9	604.26		604.72	0.001495	6.9	3812.95	836.02	0.41
6 (2+3+4)	7340	10-Percent	7990	594.8	601.62		601.97	0.001681	5.75	2160.41	863.66	0.41
6 (2+3+4)	7340	2-Percent	11800	594.8	602.45		602.84	0.001695	6.3	2884.99	888.79	0.42
6 (2+3+4)	7340	1-Percent	13600	594.8	602.81		603.21	0.001676	6.48	3224.6	966.68	0.42
6 (2+3+4)	7340	0.2-Percent	18000	594.8	603.66		604.07	0.001573	6.75	4085.71	1059.49	0.42
6 (2+3+4)	7151	10-Percent	7990	594.7	600.88		601.19	0.001731	5.26	2209.49	867.81	0.41
6 (2+3+4)	7151	2-Percent	11800	594.7	601.73		602.07	0.001679	5.73	2948.81	901.78	0.41
6 (2+3+4)	7151	1-Percent	13600	594.7	602.1		602.45	0.00163	5.88	3304.39	972.73	0.41
6 (2+3+4)	7151	0.2-Percent	18000	594.7	603.02		603.38	0.001429	6.02	4225.96	1063.45	0.39
6 (2+3+4)	6890	10-Percent	7990	593	600.1	599.03	600.34	0.001444	4.78	2431.96	1202.88	0.37
6 (2+3+4)	6890	2-Percent	11800	593	601.01	599.51	601.27	0.001323	5.1	3339.75	1879.26	0.37
6 (2+3+4)	6890	1-Percent	13600	593	601.43	599.71	601.69	0.001223	5.13	3813.06	2035.41	0.36
6 (2+3+4)	6890	0.2-Percent	18000	593	602.5	600.16	602.74	0.000958	5.03	5052.9	2141.07	0.32
6 (2+3+4)	6631	10-Percent	7990	592	599.02	598.11	599.36	0.002069	5.45	2015.61	767.74	0.44
6 (2+3+4)	6631	2-Percent	11800	592	600.07	598.65	600.41	0.001699	5.64	2823.1	772.58	0.41

Table 11: Flood Scenario 6 HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl
6 (2+3+4)	6631	1-Percent	13600	592	600.57	598.89	600.91	0.001528	5.65	3225.62	843.45	0.4
6 (2+3+4)	6631	0.2-Percent	18000	592	601.81	599.38	602.14	0.001155	5.54	4295.57	864.39	0.36
6 (2+3+4)	6324	10-Percent	7990	590.5	597.96	595.72	598.3	0.001454	5.25	2041.94	662.66	0.38
6 (2+3+4)	6324	2-Percent	11800	590.5	599.15	597.31	599.5	0.00129	5.59	2830.64	666.57	0.37
6 (2+3+4)	6324	1-Percent	13600	590.5	599.73	597.6	600.09	0.001174	5.62	3222.79	668.5	0.36
6 (2+3+4)	6324	0.2-Percent	18000	590.5	601.14	598.19	601.49	0.000946	5.64	4168.99	673.14	0.33
6 (2+3+4)	6015	10-Percent	7990	588.7	596.26		596.85	0.002877	7.04	1511.66	485.31	0.53
6 (2+3+4)	6015	2-Percent	11800	588.7	597.95		598.43	0.001735	6.54	2378.3	525.84	0.43
6 (2+3+4)	6015	1-Percent	13600	588.7	598.69		599.15	0.001458	6.41	2770.68	530.6	0.4
6 (2+3+4)	6015	0.2-Percent	18000	588.7	600.32		600.75	0.001105	6.32	3641.38	541.6	0.36
6 (2+3+4)	5607	10-Percent	7990	587.3	595.34	593.15	595.6	0.001048	4.98	2155.35	515.3	0.33
6 (2+3+4)	5607	2-Percent	11800	587.3	597.38	593.91	597.63	0.000685	4.79	3220.39	523.39	0.28
6 (2+3+4)	5607	1-Percent	13600	587.3	598.2	594.25	598.44	0.00062	4.83	3646.01	526.41	0.27
6 (2+3+4)	5607	0.2-Percent	18000	587.3	599.9	594.91	600.17	0.00055	5.06	4570.15	568.89	0.26
6 (2+3+4)	5307	10-Percent	7990	585.8	594.96		595.16	0.00058	4.13	2504.06	480.77	0.25
6 (2+3+4)	5307	2-Percent	11800	585.8	597.11		597.31	0.000441	4.21	3547.23	489.88	0.23
6 (2+3+4)	5307	1-Percent	13600	585.8	597.94		598.15	0.00042	4.33	3954.66	499.38	0.23
6 (2+3+4)	5307	0.2-Percent	18000	585.8	599.66		599.9	0.000402	4.66	4927.78	588.01	0.23
6 (2+3+4)	5051	10-Percent	7990	584.3	594.2	590.41	594.7	0.001202	5.74	1436.22	206.59	0.36
6 (2+3+4)	5051	2-Percent	11800	584.3	596.26	591.62	596.91	0.001151	6.57	1948.53	301.22	0.37
6 (2+3+4)	5051	1-Percent	13600	584.3	597.06	592.13	597.76	0.00113	6.86	2225.73	360.37	0.37
6 (2+3+4)	5051	0.2-Percent	18000	584.3	598.75	593.33	599.52	0.001078	7.39	2838.24	366.48	0.37
6 (2+3+4)	4786	10-Percent	7990	582.8	593.61	589.12	594.17	0.001084	5.97	1354.02	162.68	0.35
6 (2+3+4)	4786	2-Percent	11800	582.8	595.6	590.5	596.36	0.001161	7.07	1761.02	226.8	0.38
6 (2+3+4)	4786	1-Percent	13600	582.8	596.36	591.06	597.2	0.001191	7.49	1953.77	261.47	0.39
6 (2+3+4)	4786	0.2-Percent	18000	582.8	597.93	592.42	598.95	0.001261	8.38	2367.37	266.15	0.41
6 (2+3+4)	4582	10-Percent	7990	582.7	593.03	589.02	593.66	0.001319	6.37	1278.39	165.23	0.38
6 (2+3+4)	4582	2-Percent	11800	582.7	594.99	590.43	595.82	0.001372	7.45	1675.35	219.76	0.41
6 (2+3+4)	4582	1-Percent	13600	582.7	595.71	591.03	596.65	0.001416	7.92	1836.98	225.28	0.42
6 (2+3+4)	4582	0.2-Percent	18000	582.7	597.16	592.41	598.35	0.00156	9.01	2174.87	252.83	0.45
6 (2+3+4)	4363	10-Percent	7990	582.5	592.55	588.33	593.14	0.001221	6.16	1312.26	164.05	0.37
6 (2+3+4)	4363	2-Percent	11800	582.5	594.45	589.72	595.28	0.00134	7.37	1652.17	369.96	0.4
6 (2+3+4)	4363	1-Percent	13600	582.5	595.14	590.3	596.08	0.00141	7.89	1836.59	549.17	0.42
6 (2+3+4)	4363	0.2-Percent	18000	582.5	596.59	591.65	597.72	0.0015	8.82	2375.41	958.21	0.44
6 (2+3+4)	4182	10-Percent	7990	582.4	592.31	588.27	592.91	0.001282	6.23	1296.47	164.95	0.38
6 (2+3+4)	4182	2-Percent	11800	582.4	594.17	589.64	595.03	0.001413	7.48	1626.48	243.93	0.41
6 (2+3+4)	4182	1-Percent	13600	582.4	594.83	590.22	595.81	0.001505	8.04	1777.42	377.88	0.43
6 (2+3+4)	4182	0.2-Percent	18000	582.4	596.15	591.56	597.41	0.001703	9.23	2152.41	632.12	0.46
6 (2+3+4)	3997	10-Percent	7990	582.3	592.12	587.76	592.67	0.001125	5.95	1352.94	190.66	0.36
6 (2+3+4)	3997	2-Percent	11800	582.3	593.96	589.1	594.76	0.001283	7.22	1664.48	223.99	0.39
6 (2+3+4)	3997	1-Percent	13600	582.3	594.59	589.64	595.53	0.001394	7.82	1802.75	281.59	0.41
6 (2+3+4)	3997	0.2-Percent	18000	582.3	595.81	590.98	597.1	0.001689	9.23	2124.72	512.9	0.46
6 (2+3+4)	3670	10-Percent	7990	582.1	591.97		592.32	0.000786	5.14	3197.67	1118.11	0.3
6 (2+3+4)	3670	2-Percent	11800	582.1	594.03		594.34	0.000623	5.24	5655.64	1230.59	0.28

Table 11: Flood Scenario 6 HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl
6 (2+3+4)	3670	1-Percent	13600	582.1	594.75		595.07	0.000605	5.39	6554.8	1256.34	0.28
6 (2+3+4)	3670	0.2-Percent	18000	582.1	596.18		596.52	0.000604	5.81	8437.7	1373.85	0.28
6 (2+3+4)	2921	10-Percent	7990	576.6	591.5		591.86	0.000498	4.85	1852.73	452.33	0.25
6 (2+3+4)	2921	2-Percent	11800	576.6	593.39		593.87	0.000588	5.82	3296.29	1158.38	0.28
6 (2+3+4)	2921	1-Percent	13600	576.6	594.11		594.6	0.000591	6.04	4255.27	1414.15	0.28
6 (2+3+4)	2921	0.2-Percent	18000	576.6	595.64		596.08	0.000535	6.15	6446.61	1446.59	0.27
6 (2+3+4)	1922	10-Percent	7990	573.7	591.43		591.52	0.000159	3.15	6696.9	1308.98	0.15
6 (2+3+4)	1922	2-Percent	11800	573.7	593.4		593.49	0.000151	3.34	9344.27	1355.68	0.14
6 (2+3+4)	1922	1-Percent	13600	573.7	594.12		594.22	0.000152	3.45	10348.69	1409.83	0.15
6 (2+3+4)	1922	0.2-Percent	18000	573.7	595.61		595.71	0.00016	3.74	12703.76	1786.97	0.15
6 (2+3+4)	833	10-Percent	7990	571.5	591.31		591.38	0.000094	2.65	5431.72	1295.17	0.11
6 (2+3+4)	833	2-Percent	11800	571.5	593.29		593.36	0.000089	2.77	8382.02	1690.87	0.11
6 (2+3+4)	833	1-Percent	13600	571.5	594.02		594.08	0.000088	2.82	9641.88	1774.35	0.11
6 (2+3+4)	833	0.2-Percent	18000	571.5	595.51		595.58	0.000087	2.96	12526.76	2314.31	0.11
6 (2+3+4)	279	10-Percent	7990	571	591.21	580.11	591.3	0.00012	2.8	4718.34	1042.68	0.13
6 (2+3+4)	279	2-Percent	11800	571	593.19	581.81	593.28	0.00012	3.04	6888.45	1267.82	0.13
6 (2+3+4)	279	1-Percent	13600	571	593.91	582.54	594	0.00012	3.12	7968.79	1787.95	0.13
6 (2+3+4)	279	0.2-Percent	18000	571	595.4	584.12	595.5	0.00012	3.29	11205.39	2338.5	0.13

## Flood Scenario #7

**Flood Bench Configuration: 1b + 2 + 3 + 4**

Plan: UPDATE-FB-1b+2+3+4-SCH+UNION+CLINT+UTILI

Geometry: UPDATE-FB-1b+2+3+4-SCH+UNION+CLINT+UTILI

Steady Flow Data: USGS BF,10,2,1,0.2-PERCENT-UPDATE-BC

Date: December 2022




Figure 21: Flood Scenario #7 (1b+2+3+4) Profile Plot

Table 12: Flood Scenario 7 HEC-RAS Output

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl
7 (1b+2+3+4)	20483	10-Percent	7990	621.4	631.44		632.23	0.00152	7.14	1149.93	159.75	0.42
7 (1b+2+3+4)	20483	2-Percent	11800	621.4	633.13		634.27	0.001801	8.71	1502.7	283.71	0.47
7 (1b+2+3+4)	20483	1-Percent	13600	621.4	633.75		635.03	0.001907	9.3	1683.22	292.19	0.49
7 (1b+2+3+4)	20483	0.2-Percent	18000	621.4	635.05		636.62	0.002117	10.53	2068.6	300.59	0.52
7 (1b+2+3+4)	19313	10-Percent	7990	620.4	628.71		629.8	0.002908	8.44	1044.16	306.63	0.56
7 (1b+2+3+4)	19313	2-Percent	11800	620.4	630.2		631.56	0.003003	9.73	1584.75	383.6	0.58
7 (1b+2+3+4)	19313	1-Percent	13600	620.4	630.82		632.26	0.002981	10.15	1839	441.87	0.59
7 (1b+2+3+4)	19313	0.2-Percent	18000	620.4	632.18	630.62	633.75	0.002879	10.93	2522.14	587.78	0.59
7 (1b+2+3+4)	18244	10-Percent	7990	617.6	626.65		627.29	0.001757	6.95	1777.24	467.86	0.44
7 (1b+2+3+4)	18244	2-Percent	11800	617.6	628.34		629.05	0.001639	7.65	2590.92	496.45	0.44
7 (1b+2+3+4)	18244	1-Percent	13600	617.6	629.04		629.77	0.001597	7.92	2942.21	525.34	0.44
7 (1b+2+3+4)	18244	0.2-Percent	18000	617.6	630.55		631.34	0.001514	8.46	3805.28	582.51	0.44
7 (1b+2+3+4)	17053	10-Percent	7990	615.5	624.35		625.09	0.001916	7.31	1642.29	449.96	0.46
7 (1b+2+3+4)	17053	2-Percent	11800	615.5	625.99		626.9	0.001963	8.38	2445.93	516.05	0.48
7 (1b+2+3+4)	17053	1-Percent	13600	615.5	626.65		627.63	0.001977	8.8	2794.51	525.92	0.49
7 (1b+2+3+4)	17053	0.2-Percent	18000	615.5	628.13		629.25	0.001985	9.65	3589.78	557.64	0.5
7 (1b+2+3+4)	15751	10-Percent	7990	612.8	621.48		622.31	0.002377	7.65	1275.62	297.31	0.5
7 (1b+2+3+4)	15751	2-Percent	11800	612.8	622.94		624	0.002512	8.9	1759.86	349.52	0.53
7 (1b+2+3+4)	15751	1-Percent	13600	612.8	623.57		624.72	0.002518	9.34	1985.54	360.25	0.54
7 (1b+2+3+4)	15751	0.2-Percent	18000	612.8	625.09		626.39	0.002415	10.12	2545.4	374.73	0.54
7 (1b+2+3+4)	14403	10-Percent	7990	610.3	619.25		619.71	0.001482	6.2	2234.26	539.57	0.4
7 (1b+2+3+4)	14403	2-Percent	11800	610.3	621.12		621.56	0.001194	6.45	3263.52	572.17	0.37
7 (1b+2+3+4)	14403	1-Percent	13600	610.3	621.93		622.37	0.001093	6.52	3734.63	594.15	0.36
7 (1b+2+3+4)	14403	0.2-Percent	18000	610.3	623.88		624.29	0.00087	6.53	5014.3	708.31	0.33
7 (1b+2+3+4)	12986	10-Percent	7990	608.9	617.09		617.64	0.001417	6.23	1736.03	495.23	0.39
7 (1b+2+3+4)	12986	2-Percent	11800	608.9	619.48		619.99	0.001017	6.31	3497.77	888.88	0.35
7 (1b+2+3+4)	12986	1-Percent	13600	608.9	620.52		620.99	0.000867	6.22	4438.4	920.05	0.33
7 (1b+2+3+4)	12986	0.2-Percent	18000	608.9	622.83		623.23	0.000643	6.07	6623.01	966.59	0.29
7 (1b+2+3+4)	12162	10-Percent	7990	604.9	614.98		616.12	0.002285	8.62	955.66	117.56	0.5
7 (1b+2+3+4)	12162	2-Percent	11800	604.9	617.01		618.63	0.002506	10.32	1204.74	134.63	0.55
7 (1b+2+3+4)	12162	1-Percent	13600	604.9	617.86		619.71	0.002579	11.01	1325.92	158.1	0.56
7 (1b+2+3+4)	12162	0.2-Percent	18000	604.9	620.19	615.89	622.17	0.002287	11.67	2144.46	464.7	0.54
7 (1b+2+3+4)	11955	10-Percent	7990	605.5	614.34	611.72	615.58	0.002862	8.96	895.5	113.2	0.56
7 (1b+2+3+4)	11955	2-Percent	11800	605.5	616.3	613.35	618.05	0.003012	10.62	1119.92	115.53	0.59
7 (1b+2+3+4)	11955	1-Percent	13600	605.5	617.14	614.06	619.11	0.003059	11.29	1217.22	121.11	0.6
7 (1b+2+3+4)	11955	0.2-Percent	18000	605.5	619.16	615.65	621.59	0.003014	12.55	1459.52	154.88	0.62
7 (1b+2+3+4)	11860 Union Rd	Bridge										
7 (1b+2+3+4)	11789	10-Percent	7990	605.5	613.21	611.45	614.81	0.004418	10.14	789.07	110.21	0.66
7 (1b+2+3+4)	11789	2-Percent	11800	605.5	614.75	613.12	617.12	0.005056	12.33	960.74	111.85	0.73
7 (1b+2+3+4)	11789	1-Percent	13600	605.5	615.29	613.85	618.08	0.005503	13.39	1021.27	112.36	0.77
7 (1b+2+3+4)	11789	0.2-Percent	18000	605.5	616.4	615.46	620.28	0.00662	15.82	1147.98	117.14	0.86
7 (1b+2+3+4)	11675	10-Percent	7990	602.4	613.29		614.14	0.001658	7.4	1089.54	125.79	0.43
7 (1b+2+3+4)	11675	2-Percent	11800	602.4	614.92		616.24	0.002081	9.25	1297.57	129.74	0.5
7 (1b+2+3+4)	11675	1-Percent	13600	602.4	615.51		617.08	0.00231	10.09	1374.17	131.07	0.53

Table 12: Flood Scenario 7 HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl
7 (1b+2+3+4)	11675	0.2-Percent	18000	602.4	616.75		618.98	0.00285	12.02	1539.74	137.59	0.6
7 (1b+2+3+4)	10302	10-Percent	7990	603.2	610.48		611.37	0.002505	7.65	1175.86	345.04	0.51
7 (1b+2+3+4)	10302	2-Percent	11800	603.2	612.06	609.46	613.1	0.002394	8.59	1900.99	568.72	0.52
7 (1b+2+3+4)	10302	1-Percent	13600	603.2	612.55	610.2	613.67	0.002466	9.05	2184.57	589.07	0.53
7 (1b+2+3+4)	10302	0.2-Percent	18000	603.2	613.23	612.13	614.7	0.003059	10.58	2588.13	602.95	0.6
7 (1b+2+3+4)	9372	10-Percent	7990	599.6	604.78	604.78	606.96	0.011022	11.85	675.35	156.98	1
7 (1b+2+3+4)	9372	2-Percent	11800	599.6	606.07	606.07	608.89	0.010151	13.5	880.47	161.34	1
7 (1b+2+3+4)	9372	1-Percent	13600	599.6	606.96	606.96	609.69	0.008171	13.34	1056.49	244.39	0.92
7 (1b+2+3+4)	9372	0.2-Percent	18000	599.6	608.87	608.87	611.04	0.005014	12.39	1721.36	525.34	0.75
7 (1b+2+3+4)	8312	10-Percent	7990	595.5	603.91		604.17	0.000834	4.5	3111.22	697.33	0.3
7 (1b+2+3+4)	8312	2-Percent	11800	595.5	605.39		605.73	0.000864	5.2	4173.21	744.96	0.31
7 (1b+2+3+4)	8312	1-Percent	13600	595.5	606.07		606.43	0.000853	5.43	4687.08	786.74	0.31
7 (1b+2+3+4)	8312	0.2-Percent	18000	595.5	607.68		608.08	0.000788	5.81	5985.6	812.84	0.31
7 (1b+2+3+4)	8145	10-Percent	7990	592.1	603.82	597.15	604.07	0.000401	4.05	1973.62	262.54	0.22
7 (1b+2+3+4)	8145	2-Percent	11800	592.1	605.17	598.29	605.6	0.000586	5.3	2226.64	348.48	0.27
7 (1b+2+3+4)	8145	1-Percent	13600	592.1	605.76	598.79	606.28	0.000661	5.82	2338.03	412.74	0.29
7 (1b+2+3+4)	8145	0.2-Percent	18000	592.1	607.17	599.9	607.91	0.00081	6.92	2602.6	468.79	0.33
7 (1b+2+3+4)	8049 Railroad Bridge	Bridge										
7 (1b+2+3+4)	7984	10-Percent	7990	592.1	603.14	599.55	603.74	0.001456	6.27	1290.85	218.39	0.4
7 (1b+2+3+4)	7984	2-Percent	11800	592.1	603.99	600.86	605.05	0.002224	8.31	1443.34	331.64	0.5
7 (1b+2+3+4)	7984	1-Percent	13600	592.1	604.31	601.43	605.62	0.002604	9.22	1501.69	366.25	0.54
7 (1b+2+3+4)	7984	0.2-Percent	18000	592.1	604.96	602.7	606.93	0.00358	11.33	1619.94	407.15	0.65
7 (1b+2+3+4)	7758	10-Percent	7990	595	602.76	601.27	603.05	0.001108	5.14	2301.49	710.29	0.34
7 (1b+2+3+4)	7758	2-Percent	11800	595	603.66	601.98	604.02	0.001233	5.88	2940.29	729.49	0.37
7 (1b+2+3+4)	7758	1-Percent	13600	595	604.03	602.25	604.41	0.001281	6.18	3203.23	756.91	0.38
7 (1b+2+3+4)	7758	0.2-Percent	18000	595	604.84	602.81	605.3	0.00137	6.8	3789.76	863.29	0.4
7 (1b+2+3+4)	7564	10-Percent	7990	594.9	602.27		602.56	0.001235	5.27	2294.86	741.96	0.36
7 (1b+2+3+4)	7564	2-Percent	11800	594.9	603.11		603.47	0.00138	6.03	2918.6	747.36	0.39
7 (1b+2+3+4)	7564	1-Percent	13600	594.9	603.45		603.85	0.001439	6.34	3176.1	757.17	0.4
7 (1b+2+3+4)	7564	0.2-Percent	18000	594.9	604.24		604.7	0.001516	6.94	3793.36	826.92	0.42
7 (1b+2+3+4)	7340	10-Percent	7990	594.8	601.62		601.97	0.001681	5.75	2160.41	863.66	0.41
7 (1b+2+3+4)	7340	2-Percent	11800	594.8	602.45		602.84	0.001698	6.3	2882.99	887.56	0.42
7 (1b+2+3+4)	7340	1-Percent	13600	594.8	602.81		603.2	0.001685	6.49	3217.99	966.26	0.43
7 (1b+2+3+4)	7340	0.2-Percent	18000	594.8	603.62		604.04	0.001618	6.83	4043.2	1057.79	0.42
7 (1b+2+3+4)	7151	10-Percent	7990	594.7	600.88		601.19	0.001731	5.26	2209.49	867.81	0.41
7 (1b+2+3+4)	7151	2-Percent	11800	594.7	601.72		602.06	0.001686	5.74	2944.25	901.23	0.41
7 (1b+2+3+4)	7151	1-Percent	13600	594.7	602.09		602.44	0.001649	5.9	3290.56	971.98	0.41
7 (1b+2+3+4)	7151	0.2-Percent	18000	594.7	602.95		603.32	0.0015	6.13	4152.13	1048.76	0.4
7 (1b+2+3+4)	6890	10-Percent	7990	593	600.1	599.03	600.34	0.001444	4.78	2432.02	1202.93	0.37
7 (1b+2+3+4)	6890	2-Percent	11800	593	601	599.51	601.26	0.001337	5.12	3327.04	1875.37	0.37
7 (1b+2+3+4)	6890	1-Percent	13600	593	601.4	599.71	601.67	0.001251	5.17	3781.56	2028.18	0.36
7 (1b+2+3+4)	6890	0.2-Percent	18000	593	602.39	600.16	602.65	0.001035	5.18	4922.04	2138.51	0.33
7 (1b+2+3+4)	6631	10-Percent	7990	592	599.02	598.11	599.36	0.002069	5.44	2015.71	767.74	0.44
7 (1b+2+3+4)	6631	2-Percent	11800	592	600.04	598.65	600.39	0.00174	5.68	2800.7	772.45	0.42

Table 12: Flood Scenario 7 HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl
7 (1b+2+3+4)	6631	1-Percent	13600	592	600.5	598.89	600.86	0.0016	5.74	3173.54	834.93	0.41
7 (1b+2+3+4)	6631	0.2-Percent	18000	592	601.63	599.38	601.98	0.001294	5.77	4136.17	863.38	0.37
7 (1b+2+3+4)	6324	10-Percent	7990	590.5	597.96	595.72	598.3	0.001452	5.25	2042.58	662.66	0.38
7 (1b+2+3+4)	6324	2-Percent	11800	590.5	599.07	597.31	599.45	0.001355	5.69	2782.47	666.33	0.38
7 (1b+2+3+4)	6324	1-Percent	13600	590.5	599.61	597.6	599.98	0.00127	5.78	3137.78	668.08	0.37
7 (1b+2+3+4)	6324	0.2-Percent	18000	590.5	600.86	598.19	601.25	0.001093	5.93	3977.22	672.2	0.35
7 (1b+2+3+4)	6015	10-Percent	7990	588.7	596.19		596.81	0.003063	7.2	1477.88	484.91	0.55
7 (1b+2+3+4)	6015	2-Percent	11800	588.7	597.72		598.26	0.002022	6.91	2258.24	524.66	0.46
7 (1b+2+3+4)	6015	1-Percent	13600	588.7	598.4		598.91	0.001734	6.81	2615.97	528.62	0.44
7 (1b+2+3+4)	6015	0.2-Percent	18000	588.7	599.85		600.36	0.00138	6.83	3388.42	538.42	0.4
7 (1b+2+3+4)	5607	10-Percent	7990	587.3	595.12	593.15	595.42	0.001224	5.27	2042.59	514.24	0.36
7 (1b+2+3+4)	5607	2-Percent	11800	587.3	597.04	593.91	597.31	0.000817	5.09	3041.05	522.27	0.31
7 (1b+2+3+4)	5607	1-Percent	13600	587.3	597.8	594.25	598.08	0.000745	5.14	3436.21	524.93	0.3
7 (1b+2+3+4)	5607	0.2-Percent	18000	587.3	599.32	594.91	599.63	0.000684	5.45	4247.87	548.12	0.29
7 (1b+2+3+4)	5307	10-Percent	7990	585.8	594.67		594.9	0.000686	4.39	2365.25	479.65	0.28
7 (1b+2+3+4)	5307	2-Percent	11800	585.8	596.71		596.94	0.000524	4.47	3353.51	487.91	0.25
7 (1b+2+3+4)	5307	1-Percent	13600	585.8	597.49		597.73	0.000502	4.6	3732.04	491.75	0.25
7 (1b+2+3+4)	5307	0.2-Percent	18000	585.8	599.02		599.3	0.000505	5.05	4553.23	574.48	0.25
7 (1b+2+3+4)	5051	10-Percent	7990	584.3	594.17		594.49	0.000854	4.82	1895.88	320.29	0.31
7 (1b+2+3+4)	5051	2-Percent	11800	584.3	596.23		596.6	0.000742	5.26	2565.43	331.57	0.3
7 (1b+2+3+4)	5051	1-Percent	13600	584.3	597		597.4	0.000734	5.5	2867.61	477.89	0.3
7 (1b+2+3+4)	5051	0.2-Percent	18000	584.3	598.52		598.97	0.000717	5.95	3779.32	711.64	0.3
7 (1b+2+3+4)	4786	10-Percent	7990	582.8	593.59		594.05	0.000961	5.61	1529.04	204.32	0.33
7 (1b+2+3+4)	4786	2-Percent	11800	582.8	595.59		596.19	0.000971	6.46	2116.7	457.63	0.34
7 (1b+2+3+4)	4786	1-Percent	13600	582.8	596.36		596.98	0.00096	6.72	2506.75	576.63	0.35
7 (1b+2+3+4)	4786	0.2-Percent	18000	582.8	597.93		598.57	0.000909	7.11	3654.12	826.1	0.34
7 (1b+2+3+4)	4582	10-Percent	7990	582.7	593.03		593.59	0.001217	6.12	1392.88	205.08	0.37
7 (1b+2+3+4)	4582	2-Percent	11800	582.7	595.03		595.72	0.001187	6.95	1994.44	420.6	0.38
7 (1b+2+3+4)	4582	1-Percent	13600	582.7	595.79		596.52	0.001177	7.26	2402.89	618.65	0.38
7 (1b+2+3+4)	4582	0.2-Percent	18000	582.7	597.37		598.14	0.001119	7.72	3533.52	854.73	0.38
7 (1b+2+3+4)	4363	10-Percent	7990	582.5	592.71	588.54	593.12	0.000913	5.39	1641.92	237.07	0.32
7 (1b+2+3+4)	4363	2-Percent	11800	582.5	594.73	589.87	595.26	0.000906	6.17	2161.48	491.57	0.33
7 (1b+2+3+4)	4363	1-Percent	13600	582.5	595.48	590.39	596.06	0.000927	6.52	2387.73	683.43	0.34
7 (1b+2+3+4)	4363	0.2-Percent	18000	582.5	596.99	591.52	597.7	0.000983	7.29	3058.42	1123.5	0.36
7 (1b+2+3+4)	4182	10-Percent	7990	582.4	592.31	588.27	592.91	0.001282	6.23	1296.47	164.95	0.38
7 (1b+2+3+4)	4182	2-Percent	11800	582.4	594.17	589.64	595.03	0.001413	7.48	1626.48	243.93	0.41
7 (1b+2+3+4)	4182	1-Percent	13600	582.4	594.83	590.22	595.81	0.001505	8.04	1777.42	377.88	0.43
7 (1b+2+3+4)	4182	0.2-Percent	18000	582.4	596.15	591.56	597.41	0.001703	9.23	2152.41	632.12	0.46
7 (1b+2+3+4)	3997	10-Percent	7990	582.3	592.12	587.76	592.67	0.001125	5.95	1352.94	190.66	0.36
7 (1b+2+3+4)	3997	2-Percent	11800	582.3	593.96	589.1	594.76	0.001283	7.22	1664.48	223.99	0.39
7 (1b+2+3+4)	3997	1-Percent	13600	582.3	594.59	589.64	595.53	0.001394	7.82	1802.75	281.59	0.41
7 (1b+2+3+4)	3997	0.2-Percent	18000	582.3	595.81	590.98	597.1	0.001689	9.23	2124.72	512.9	0.46
7 (1b+2+3+4)	3670	10-Percent	7990	582.1	591.97		592.32	0.000786	5.14	3197.67	1118.11	0.3
7 (1b+2+3+4)	3670	2-Percent	11800	582.1	594.03		594.34	0.000623	5.24	5655.63	1230.59	0.28

Table 12: Flood Scenario 7 HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl
7 (1b+2+3+4)	3670	1-Percent	13600	582.1	594.75		595.07	0.000605	5.39	6554.79	1256.34	0.28
7 (1b+2+3+4)	3670	0.2-Percent	18000	582.1	596.18		596.52	0.000604	5.81	8437.7	1373.85	0.28
7 (1b+2+3+4)	2921	10-Percent	7990	576.6	591.5		591.86	0.000498	4.85	1852.73	452.33	0.25
7 (1b+2+3+4)	2921	2-Percent	11800	576.6	593.39		593.87	0.000588	5.82	3296.29	1158.38	0.28
7 (1b+2+3+4)	2921	1-Percent	13600	576.6	594.11		594.6	0.000591	6.04	4255.27	1414.15	0.28
7 (1b+2+3+4)	2921	0.2-Percent	18000	576.6	595.64		596.08	0.000535	6.15	6446.61	1446.59	0.27
7 (1b+2+3+4)	1922	10-Percent	7990	573.7	591.43		591.52	0.000159	3.15	6696.9	1308.98	0.15
7 (1b+2+3+4)	1922	2-Percent	11800	573.7	593.4		593.49	0.000151	3.34	9344.27	1355.68	0.14
7 (1b+2+3+4)	1922	1-Percent	13600	573.7	594.12		594.22	0.000152	3.45	10348.69	1409.83	0.15
7 (1b+2+3+4)	1922	0.2-Percent	18000	573.7	595.61		595.71	0.00016	3.74	12703.76	1786.97	0.15
7 (1b+2+3+4)	833	10-Percent	7990	571.5	591.31		591.38	0.000094	2.65	5431.72	1295.17	0.11
7 (1b+2+3+4)	833	2-Percent	11800	571.5	593.29		593.36	0.000089	2.77	8382.02	1690.87	0.11
7 (1b+2+3+4)	833	1-Percent	13600	571.5	594.02		594.08	0.000088	2.82	9641.88	1774.35	0.11
7 (1b+2+3+4)	833	0.2-Percent	18000	571.5	595.51		595.58	0.000087	2.96	12526.76	2314.31	0.11
7 (1b+2+3+4)	279	10-Percent	7990	571	591.21	580.11	591.3	0.00012	2.8	4718.34	1042.68	0.13
7 (1b+2+3+4)	279	2-Percent	11800	571	593.19	581.81	593.28	0.00012	3.04	6888.45	1267.82	0.13
7 (1b+2+3+4)	279	1-Percent	13600	571	593.91	582.54	594	0.00012	3.12	7968.79	1787.95	0.13
7 (1b+2+3+4)	279	0.2-Percent	18000	571	595.4	584.12	595.5	0.00012	3.29	11205.39	2338.5	0.13

## Flood Scenario #8

**Flood Bench Configuration: 5 + 6**

Plan: UPDATE-FB-5+6-UTILITY-UP+DOWN-LEFT

Geometry: UPDATE-FB-5+6-UTILITY-UP+DOWN-LEFT

Steady Flow Data: USGS BF,10,2,1,0.2-PERCENT-UPDATE-BC

Date: December 2022




Figure 22: Flood Scenario #8 (5+6) Profile Plot

Table 13: Flood Scenario 8 HEC-RAS Output

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl
8 (5+6)	20483	10-Percent	7990	621.4	631.44		632.23	0.00152	7.14	1149.93	159.75	0.42
8 (5+6)	20483	2-Percent	11800	621.4	633.13		634.27	0.001801	8.71	1502.7	283.71	0.47
8 (5+6)	20483	1-Percent	13600	621.4	633.75		635.03	0.001907	9.3	1683.22	292.19	0.49
8 (5+6)	20483	0.2-Percent	18000	621.4	635.05		636.62	0.002117	10.53	2068.6	300.59	0.52
8 (5+6)	19313	10-Percent	7990	620.4	628.71		629.8	0.002908	8.44	1044.16	306.63	0.56
8 (5+6)	19313	2-Percent	11800	620.4	630.2		631.56	0.003003	9.73	1584.75	383.6	0.58
8 (5+6)	19313	1-Percent	13600	620.4	630.82		632.26	0.002981	10.15	1839	441.87	0.59
8 (5+6)	19313	0.2-Percent	18000	620.4	632.18	630.62	633.75	0.002879	10.93	2522.14	587.78	0.59
8 (5+6)	18244	10-Percent	7990	617.6	626.65		627.29	0.001757	6.95	1777.24	467.86	0.44
8 (5+6)	18244	2-Percent	11800	617.6	628.34		629.05	0.001639	7.65	2590.92	496.45	0.44
8 (5+6)	18244	1-Percent	13600	617.6	629.04		629.77	0.001597	7.92	2942.21	525.34	0.44
8 (5+6)	18244	0.2-Percent	18000	617.6	630.55		631.34	0.001514	8.46	3805.28	582.51	0.44
8 (5+6)	17053	10-Percent	7990	615.5	624.35		625.09	0.001916	7.31	1642.29	449.96	0.46
8 (5+6)	17053	2-Percent	11800	615.5	625.99		626.9	0.001963	8.38	2445.93	516.05	0.48
8 (5+6)	17053	1-Percent	13600	615.5	626.65		627.63	0.001977	8.8	2794.51	525.92	0.49
8 (5+6)	17053	0.2-Percent	18000	615.5	628.13		629.25	0.001985	9.65	3589.78	557.64	0.5
8 (5+6)	15751	10-Percent	7990	612.8	621.48		622.31	0.002377	7.65	1275.62	297.31	0.5
8 (5+6)	15751	2-Percent	11800	612.8	622.94		624	0.002512	8.9	1759.86	349.52	0.53
8 (5+6)	15751	1-Percent	13600	612.8	623.57		624.72	0.002518	9.34	1985.54	360.25	0.54
8 (5+6)	15751	0.2-Percent	18000	612.8	625.09		626.39	0.002415	10.12	2545.4	374.73	0.54
8 (5+6)	14403	10-Percent	7990	610.3	619.25		619.71	0.001482	6.2	2234.26	539.57	0.4
8 (5+6)	14403	2-Percent	11800	610.3	621.12		621.56	0.001194	6.45	3263.52	572.17	0.37
8 (5+6)	14403	1-Percent	13600	610.3	621.93		622.37	0.001093	6.52	3734.63	594.15	0.36
8 (5+6)	14403	0.2-Percent	18000	610.3	623.88		624.29	0.00087	6.53	5014.3	708.31	0.33
8 (5+6)	12986	10-Percent	7990	608.9	617.09		617.64	0.001416	6.23	1736.09	495.28	0.39
8 (5+6)	12986	2-Percent	11800	608.9	619.48		619.99	0.001017	6.31	3497.77	888.88	0.35
8 (5+6)	12986	1-Percent	13600	608.9	620.52		620.99	0.000867	6.22	4438.4	920.05	0.33
8 (5+6)	12986	0.2-Percent	18000	608.9	622.83		623.23	0.000643	6.07	6623.01	966.59	0.29
8 (5+6)	12162	10-Percent	7990	604.9	614.98		616.12	0.002285	8.62	955.69	117.56	0.5
8 (5+6)	12162	2-Percent	11800	604.9	617.01		618.63	0.002506	10.32	1204.75	134.63	0.55
8 (5+6)	12162	1-Percent	13600	604.9	617.86		619.71	0.002579	11.01	1325.92	158.1	0.56
8 (5+6)	12162	0.2-Percent	18000	604.9	620.19	615.89	622.17	0.002287	11.67	2144.46	464.7	0.54
8 (5+6)	11955	10-Percent	7990	605.5	614.34	611.72	615.58	0.002861	8.96	895.56	113.2	0.56
8 (5+6)	11955	2-Percent	11800	605.5	616.3	613.35	618.05	0.003012	10.62	1119.93	115.53	0.59
8 (5+6)	11955	1-Percent	13600	605.5	617.14	614.06	619.11	0.003059	11.29	1217.22	121.11	0.6
8 (5+6)	11955	0.2-Percent	18000	605.5	619.16	615.65	621.59	0.003014	12.55	1459.52	154.88	0.62
8 (5+6)	11860 Union Rd	Bridge										
8 (5+6)	11789	10-Percent	7990	605.5	613.21	611.45	614.81	0.004416	10.14	789.17	110.21	0.66
8 (5+6)	11789	2-Percent	11800	605.5	614.76	613.12	617.12	0.005055	12.33	960.8	111.85	0.73
8 (5+6)	11789	1-Percent	13600	605.5	615.29	613.85	618.08	0.005503	13.39	1021.27	112.36	0.77
8 (5+6)	11789	0.2-Percent	18000	605.5	616.4	615.46	620.28	0.00662	15.82	1147.98	117.14	0.86
8 (5+6)	11675	10-Percent	7990	602.4	613.29		614.14	0.001658	7.4	1089.64	125.79	0.43
8 (5+6)	11675	2-Percent	11800	602.4	614.92		616.24	0.00208	9.24	1297.64	129.74	0.5
8 (5+6)	11675	1-Percent	13600	602.4	615.51		617.08	0.00231	10.09	1374.17	131.07	0.53

Table 13: Flood Scenario 8 HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl
8 (5+6)	11675	0.2-Percent	18000	602.4	616.75		618.98	0.00285	12.02	1539.74	137.59	0.6
8 (5+6)	10302	10-Percent	7990	603.2	610.42		611.33	0.002587	7.73	1155.84	322.87	0.52
8 (5+6)	10302	2-Percent	11800	603.2	612.05	609.46	613.1	0.002403	8.6	1896.93	568.55	0.52
8 (5+6)	10302	1-Percent	13600	603.2	612.55	610.2	613.67	0.002466	9.05	2184.57	589.07	0.53
8 (5+6)	10302	0.2-Percent	18000	603.2	613.23	612.13	614.7	0.003059	10.58	2588.13	602.95	0.6
8 (5+6)	9372	10-Percent	7990	599.6	604.9	604.78	606.97	0.010108	11.55	693.47	157.47	0.96
8 (5+6)	9372	2-Percent	11800	599.6	606.08	606.07	608.89	0.010059	13.46	882.96	161.39	0.99
8 (5+6)	9372	1-Percent	13600	599.6	606.96	606.96	609.69	0.008171	13.34	1056.49	244.39	0.92
8 (5+6)	9372	0.2-Percent	18000	599.6	608.87	608.87	611.04	0.005014	12.39	1721.36	525.34	0.75
8 (5+6)	8312	10-Percent	7990	595.5	604.62		604.82	0.000573	3.97	3609.06	708.21	0.25
8 (5+6)	8312	2-Percent	11800	595.5	606.22		606.48	0.000601	4.61	4810.25	796.84	0.27
8 (5+6)	8312	1-Percent	13600	595.5	606.88		607.16	0.00061	4.86	5338.27	803	0.27
8 (5+6)	8312	0.2-Percent	18000	595.5	608.38		608.71	0.000617	5.36	6553.45	823.41	0.28
8 (5+6)	8145	10-Percent	7990	592.1	604.52	597.15	604.75	0.000324	3.79	2105.43	320.91	0.2
8 (5+6)	8145	2-Percent	11800	592.1	606	598.29	606.38	0.000467	4.95	2383.16	433.12	0.25
8 (5+6)	8145	1-Percent	13600	592.1	606.59	598.79	607.05	0.000533	5.45	2493.94	456.19	0.26
8 (5+6)	8145	0.2-Percent	18000	592.1	607.89	599.9	608.56	0.000683	6.57	2739.44	485.14	0.3
8 (5+6)	8049 Railroad Bridge	Bridge										
8 (5+6)	7984	10-Percent	7990	592.1	604	599.55	604.49	0.001013	5.62	1446.29	333.45	0.34
8 (5+6)	7984	2-Percent	11800	592.1	605.17	600.86	605.97	0.001433	7.27	1656.34	454.41	0.41
8 (5+6)	7984	1-Percent	13600	592.1	605.58	601.43	606.56	0.001652	8.02	1732.01	498.22	0.44
8 (5+6)	7984	0.2-Percent	18000	592.1	606.39	602.7	607.86	0.002228	9.8	1880.97	531.84	0.52
8 (5+6)	7758	10-Percent	7990	595	603.58	600.75	604	0.001166	5.68	1765.57	517.4	0.36
8 (5+6)	7758	2-Percent	11800	595	604.77	601.96	605.25	0.001232	6.42	2597.86	895.83	0.38
8 (5+6)	7758	1-Percent	13600	595	605.23	602.4	605.73	0.001219	6.6	2989.94	961	0.38
8 (5+6)	7758	0.2-Percent	18000	595	606.2	603.63	606.71	0.001191	6.96	3836.31	1005.24	0.38
8 (5+6)	7564	10-Percent	7990	594.9	603.04		603.48	0.001328	5.88	1760.5	580.98	0.38
8 (5+6)	7564	2-Percent	11800	594.9	604.28		604.73	0.001241	6.29	2728.26	888.08	0.38
8 (5+6)	7564	1-Percent	13600	594.9	604.78		605.21	0.00117	6.34	3188.47	956.78	0.37
8 (5+6)	7564	0.2-Percent	18000	594.9	605.8		606.21	0.001063	6.48	4206.16	1148.27	0.36
8 (5+6)	7340	10-Percent	7990	594.8	602.58		602.92	0.001219	5.41	1918.63	557.34	0.36
8 (5+6)	7340	2-Percent	11800	594.8	603.83		604.21	0.001158	5.88	2801.8	838.11	0.36
8 (5+6)	7340	1-Percent	13600	594.8	604.34		604.72	0.001113	6	3285.38	1061.04	0.36
8 (5+6)	7340	0.2-Percent	18000	594.8	605.41		605.77	0.000978	6.07	4510.8	1368.02	0.34
8 (5+6)	7151	10-Percent	7990	594.7	601.76		602.25	0.001806	5.96	1615.56	495.11	0.43
8 (5+6)	7151	2-Percent	11800	594.7	603.02		603.57	0.001697	6.56	2385.25	758.37	0.43
8 (5+6)	7151	1-Percent	13600	594.7	603.56		604.11	0.001601	6.68	2847.1	923.97	0.42
8 (5+6)	7151	0.2-Percent	18000	594.7	604.8		605.27	0.001237	6.48	4620	1951.07	0.38
8 (5+6)	6890	10-Percent	7990	593	600.97	599.04	601.35	0.001515	5.43	1792.8	1612.24	0.39
8 (5+6)	6890	2-Percent	11800	593	602.34	599.89	602.75	0.00132	5.82	2559.51	2043.63	0.38
8 (5+6)	6890	1-Percent	13600	593	602.93	600.26	603.34	0.001221	5.89	3000.3	2173.66	0.37
8 (5+6)	6890	0.2-Percent	18000	593	604.26	601.08	604.67	0.001027	5.99	4050.43	2326.3	0.35
8 (5+6)	6631	10-Percent	7990	592	599.58	597.98	600.22	0.002637	6.62	1311.82	303.24	0.51
8 (5+6)	6631	2-Percent	11800	592	600.89	598.94	601.7	0.002555	7.55	1712.09	357.49	0.52

Table 13: Flood Scenario 8 HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl
8 (5+6)	6631	1-Percent	13600	592	601.45	599.33	602.33	0.002518	7.91	1885.08	391.95	0.52
8 (5+6)	6631	0.2-Percent	18000	592	602.71	600.25	603.75	0.002421	8.64	2330.78	569.64	0.52
8 (5+6)	6324	10-Percent	7990	590.5	598.4	595.89	598.9	0.001668	5.9	1486.39	323.05	0.41
8 (5+6)	6324	2-Percent	11800	590.5	599.68	597.02	600.35	0.001787	6.9	1928.75	356.62	0.44
8 (5+6)	6324	1-Percent	13600	590.5	600.27	597.43	600.99	0.001772	7.22	2136.33	447.5	0.44
8 (5+6)	6324	0.2-Percent	18000	590.5	601.61	598.5	602.44	0.001713	7.84	2614.81	588.64	0.45
8 (5+6)	6015	10-Percent	7990	588.7	596.68		597.36	0.002808	7.3	1360.52	391.88	0.53
8 (5+6)	6015	2-Percent	11800	588.7	598.38		599	0.001945	7.2	2057.87	427.06	0.46
8 (5+6)	6015	1-Percent	13600	588.7	599.08		599.71	0.001739	7.22	2364.65	441.4	0.44
8 (5+6)	6015	0.2-Percent	18000	588.7	600.65		601.26	0.001422	7.33	3203.25	606.4	0.41
8 (5+6)	5607	10-Percent	7990	587.3	595.5	593.07	595.92	0.001409	5.87	1640.26	345.06	0.39
8 (5+6)	5607	2-Percent	11800	587.3	597.51	593.97	597.94	0.00108	6.06	2520.6	508.9	0.35
8 (5+6)	5607	1-Percent	13600	587.3	598.3	594.38	598.74	0.000987	6.13	2927.75	511.89	0.34
8 (5+6)	5607	0.2-Percent	18000	587.3	599.98	595.27	600.44	0.000867	6.38	3791.69	522.27	0.33
8 (5+6)	5307	10-Percent	7990	585.8	594.91		595.27	0.000929	5.21	1814.73	351.72	0.32
8 (5+6)	5307	2-Percent	11800	585.8	597.05		597.43	0.00076	5.5	2755.62	478.86	0.3
8 (5+6)	5307	1-Percent	13600	585.8	597.86		598.26	0.00073	5.68	3149.5	484.78	0.3
8 (5+6)	5307	0.2-Percent	18000	585.8	599.56		600	0.000702	6.12	3985.14	519.96	0.3
8 (5+6)	5051	10-Percent	7990	584.3	594.2	590.41	594.7	0.001202	5.74	1436.22	206.59	0.36
8 (5+6)	5051	2-Percent	11800	584.3	596.26	591.62	596.91	0.001151	6.57	1948.53	301.22	0.37
8 (5+6)	5051	1-Percent	13600	584.3	597.06	592.13	597.76	0.00113	6.86	2225.73	360.37	0.37
8 (5+6)	5051	0.2-Percent	18000	584.3	598.75	593.33	599.52	0.001078	7.39	2838.24	366.48	0.37
8 (5+6)	4786	10-Percent	7990	582.8	593.61	589.12	594.17	0.001084	5.97	1354.02	162.68	0.35
8 (5+6)	4786	2-Percent	11800	582.8	595.6	590.5	596.36	0.001161	7.07	1761.02	226.8	0.38
8 (5+6)	4786	1-Percent	13600	582.8	596.36	591.06	597.2	0.001191	7.49	1953.77	261.47	0.39
8 (5+6)	4786	0.2-Percent	18000	582.8	597.93	592.42	598.95	0.001261	8.38	2367.37	266.15	0.41
8 (5+6)	4582	10-Percent	7990	582.7	593.03	589.02	593.66	0.001319	6.37	1278.39	165.23	0.38
8 (5+6)	4582	2-Percent	11800	582.7	594.99	590.43	595.82	0.001372	7.45	1675.35	219.76	0.41
8 (5+6)	4582	1-Percent	13600	582.7	595.71	591.03	596.65	0.001416	7.92	1836.98	225.28	0.42
8 (5+6)	4582	0.2-Percent	18000	582.7	597.16	592.41	598.35	0.00156	9.01	2174.87	252.83	0.45
8 (5+6)	4363	10-Percent	7990	582.5	592.55	588.33	593.14	0.001221	6.16	1312.26	164.05	0.37
8 (5+6)	4363	2-Percent	11800	582.5	594.45	589.72	595.28	0.00134	7.37	1652.17	369.96	0.4
8 (5+6)	4363	1-Percent	13600	582.5	595.14	590.3	596.08	0.00141	7.89	1836.59	549.17	0.42
8 (5+6)	4363	0.2-Percent	18000	582.5	596.59	591.65	597.72	0.0015	8.82	2375.41	958.21	0.44
8 (5+6)	4182	10-Percent	7990	582.4	592.31	588.27	592.91	0.001282	6.23	1296.47	164.95	0.38
8 (5+6)	4182	2-Percent	11800	582.4	594.17	589.64	595.03	0.001413	7.48	1626.48	243.93	0.41
8 (5+6)	4182	1-Percent	13600	582.4	594.83	590.22	595.81	0.001505	8.04	1777.42	377.88	0.43
8 (5+6)	4182	0.2-Percent	18000	582.4	596.15	591.56	597.41	0.001703	9.23	2152.41	632.12	0.46
8 (5+6)	3997	10-Percent	7990	582.3	592.12	587.76	592.67	0.001125	5.95	1352.94	190.66	0.36
8 (5+6)	3997	2-Percent	11800	582.3	593.96	589.1	594.76	0.001283	7.22	1664.48	223.99	0.39
8 (5+6)	3997	1-Percent	13600	582.3	594.59	589.64	595.53	0.001394	7.82	1802.75	281.59	0.41
8 (5+6)	3997	0.2-Percent	18000	582.3	595.81	590.98	597.1	0.001689	9.23	2124.72	512.9	0.46
8 (5+6)	3670	10-Percent	7990	582.1	591.97		592.32	0.000786	5.14	3197.67	1118.11	0.3
8 (5+6)	3670	2-Percent	11800	582.1	594.03		594.34	0.000623	5.24	5655.63	1230.59	0.28

Table 13: Flood Scenario 8 HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl
8 (5+6)	3670	1-Percent	13600	582.1	594.75		595.07	0.000605	5.39	6554.79	1256.34	0.28
8 (5+6)	3670	0.2-Percent	18000	582.1	596.18		596.52	0.000604	5.81	8437.7	1373.85	0.28
8 (5+6)	2921	10-Percent	7990	576.6	591.5		591.86	0.000498	4.85	1852.73	452.33	0.25
8 (5+6)	2921	2-Percent	11800	576.6	593.39		593.87	0.000588	5.82	3296.29	1158.38	0.28
8 (5+6)	2921	1-Percent	13600	576.6	594.11		594.6	0.000591	6.04	4255.27	1414.15	0.28
8 (5+6)	2921	0.2-Percent	18000	576.6	595.64		596.08	0.000535	6.15	6446.61	1446.59	0.27
8 (5+6)	1922	10-Percent	7990	573.7	591.43		591.52	0.000159	3.15	6696.9	1308.98	0.15
8 (5+6)	1922	2-Percent	11800	573.7	593.4		593.49	0.000151	3.34	9344.27	1355.68	0.14
8 (5+6)	1922	1-Percent	13600	573.7	594.12		594.22	0.000152	3.45	10348.69	1409.83	0.15
8 (5+6)	1922	0.2-Percent	18000	573.7	595.61		595.71	0.00016	3.74	12703.76	1786.97	0.15
8 (5+6)	833	10-Percent	7990	571.5	591.31		591.38	0.000094	2.65	5431.72	1295.17	0.11
8 (5+6)	833	2-Percent	11800	571.5	593.29		593.36	0.000089	2.77	8382.02	1690.87	0.11
8 (5+6)	833	1-Percent	13600	571.5	594.02		594.08	0.000088	2.82	9641.88	1774.35	0.11
8 (5+6)	833	0.2-Percent	18000	571.5	595.51		595.58	0.000087	2.96	12526.76	2314.31	0.11
8 (5+6)	279	10-Percent	7990	571	591.21	580.11	591.3	0.00012	2.8	4718.34	1042.68	0.13
8 (5+6)	279	2-Percent	11800	571	593.19	581.81	593.28	0.00012	3.04	6888.45	1267.82	0.13
8 (5+6)	279	1-Percent	13600	571	593.91	582.54	594	0.00012	3.12	7968.79	1787.95	0.13
8 (5+6)	279	0.2-Percent	18000	571	595.4	584.12	595.5	0.00012	3.29	11205.39	2338.5	0.13

## Flood Scenario #9

**Flood Bench Configuration: 1b + 2 + 3 + 4 + 5 + 6**

Plan: UPDATE-FB-1b+2+3+4+5+6-FULL-SUITE

Geometry: UPDATE-FB-1b+2+3+4+5+6-FULL-SUITE

Steady Flow Data: USGS BF,10,2,1,0.2-PERCENT-UPDATE-BC

Date: December 2022




Figure 23: Flood Scenario #9 (1b+2+3+4+5+6) Profile Plot

Table 14: Flood Scenario 9 HEC-RAS Output

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.ChnL	Flow.Area	Top.Width	Froude...Chl
9 (1b+2+3+4+5+6)	20483	10-Percent	7990	621.4	631.44		632.23	0.00152	7.14	1149.93	159.75	0.42
9 (1b+2+3+4+5+6)	20483	2-Percent	11800	621.4	633.13		634.27	0.001801	8.71	1502.7	283.71	0.47
9 (1b+2+3+4+5+6)	20483	1-Percent	13600	621.4	633.75		635.03	0.001907	9.3	1683.22	292.19	0.49
9 (1b+2+3+4+5+6)	20483	0.2-Percent	18000	621.4	635.05		636.62	0.002117	10.53	2068.6	300.59	0.52
9 (1b+2+3+4+5+6)	19313	10-Percent	7990	620.4	628.71		629.8	0.002908	8.44	1044.16	306.63	0.56
9 (1b+2+3+4+5+6)	19313	2-Percent	11800	620.4	630.2		631.56	0.003003	9.73	1584.75	383.6	0.58
9 (1b+2+3+4+5+6)	19313	1-Percent	13600	620.4	630.82		632.26	0.002981	10.15	1839	441.87	0.59
9 (1b+2+3+4+5+6)	19313	0.2-Percent	18000	620.4	632.18	630.62	633.75	0.002879	10.93	2522.14	587.78	0.59
9 (1b+2+3+4+5+6)	18244	10-Percent	7990	617.6	626.65		627.29	0.001757	6.95	1777.24	467.86	0.44
9 (1b+2+3+4+5+6)	18244	2-Percent	11800	617.6	628.34		629.05	0.001639	7.65	2590.92	496.45	0.44
9 (1b+2+3+4+5+6)	18244	1-Percent	13600	617.6	629.04		629.77	0.001597	7.92	2942.21	525.34	0.44
9 (1b+2+3+4+5+6)	18244	0.2-Percent	18000	617.6	630.55		631.34	0.001514	8.46	3805.28	582.51	0.44
9 (1b+2+3+4+5+6)	17053	10-Percent	7990	615.5	624.35		625.09	0.001916	7.31	1642.29	449.96	0.46
9 (1b+2+3+4+5+6)	17053	2-Percent	11800	615.5	625.99		626.9	0.001963	8.38	2445.93	516.05	0.48
9 (1b+2+3+4+5+6)	17053	1-Percent	13600	615.5	626.65		627.63	0.001977	8.8	2794.51	525.92	0.49
9 (1b+2+3+4+5+6)	17053	0.2-Percent	18000	615.5	628.13		629.25	0.001985	9.65	3589.78	557.64	0.5
9 (1b+2+3+4+5+6)	15751	10-Percent	7990	612.8	621.48		622.31	0.002377	7.65	1275.62	297.31	0.5
9 (1b+2+3+4+5+6)	15751	2-Percent	11800	612.8	622.94		624	0.002512	8.9	1759.86	349.52	0.53
9 (1b+2+3+4+5+6)	15751	1-Percent	13600	612.8	623.57		624.72	0.002518	9.34	1985.54	360.25	0.54
9 (1b+2+3+4+5+6)	15751	0.2-Percent	18000	612.8	625.09		626.39	0.002415	10.12	2545.4	374.73	0.54
9 (1b+2+3+4+5+6)	14403	10-Percent	7990	610.3	619.25		619.71	0.001482	6.2	2234.26	539.57	0.4
9 (1b+2+3+4+5+6)	14403	2-Percent	11800	610.3	621.12		621.56	0.001194	6.45	3263.52	572.17	0.37
9 (1b+2+3+4+5+6)	14403	1-Percent	13600	610.3	621.93		622.37	0.001093	6.52	3734.63	594.15	0.36
9 (1b+2+3+4+5+6)	14403	0.2-Percent	18000	610.3	623.88		624.29	0.00087	6.53	5014.3	708.31	0.33
9 (1b+2+3+4+5+6)	12986	10-Percent	7990	608.9	617.09		617.64	0.001417	6.23	1736.03	495.23	0.39
9 (1b+2+3+4+5+6)	12986	2-Percent	11800	608.9	619.48		619.99	0.001017	6.31	3497.77	888.88	0.35
9 (1b+2+3+4+5+6)	12986	1-Percent	13600	608.9	620.52		620.99	0.000867	6.22	4438.4	920.05	0.33
9 (1b+2+3+4+5+6)	12986	0.2-Percent	18000	608.9	622.83		623.23	0.000643	6.07	6623.01	966.59	0.29
9 (1b+2+3+4+5+6)	12162	10-Percent	7990	604.9	614.98		616.12	0.002285	8.62	955.66	117.56	0.5
9 (1b+2+3+4+5+6)	12162	2-Percent	11800	604.9	617.01		618.63	0.002506	10.32	1204.74	134.63	0.55
9 (1b+2+3+4+5+6)	12162	1-Percent	13600	604.9	617.86		619.71	0.002579	11.01	1325.92	158.1	0.56
9 (1b+2+3+4+5+6)	12162	0.2-Percent	18000	604.9	620.19	615.89	622.17	0.002287	11.67	2144.46	464.7	0.54
9 (1b+2+3+4+5+6)	11955	10-Percent	7990	605.5	614.34	611.72	615.58	0.002862	8.96	895.5	113.2	0.56
9 (1b+2+3+4+5+6)	11955	2-Percent	11800	605.5	616.3	613.35	618.05	0.003012	10.62	1119.92	115.53	0.59
9 (1b+2+3+4+5+6)	11955	1-Percent	13600	605.5	617.14	614.06	619.11	0.003059	11.29	1217.22	121.11	0.6
9 (1b+2+3+4+5+6)	11955	0.2-Percent	18000	605.5	619.16	615.65	621.59	0.003014	12.55	1459.52	154.88	0.62
9 (1b+2+3+4+5+6)	11860 Union Rd	Bridge										
9 (1b+2+3+4+5+6)	11789	10-Percent	7990	605.5	613.21	611.45	614.81	0.004418	10.14	789.07	110.21	0.66
9 (1b+2+3+4+5+6)	11789	2-Percent	11800	605.5	614.75	613.12	617.12	0.005056	12.33	960.74	111.85	0.73
9 (1b+2+3+4+5+6)	11789	1-Percent	13600	605.5	615.29	613.85	618.08	0.005503	13.39	1021.27	112.36	0.77
9 (1b+2+3+4+5+6)	11789	0.2-Percent	18000	605.5	616.4	615.46	620.28	0.00662	15.82	1147.98	117.14	0.86
9 (1b+2+3+4+5+6)	11675	10-Percent	7990	602.4	613.29		614.14	0.001658	7.4	1089.54	125.79	0.43
9 (1b+2+3+4+5+6)	11675	2-Percent	11800	602.4	614.92		616.24	0.002081	9.25	1297.57	129.74	0.5
9 (1b+2+3+4+5+6)	11675	1-Percent	13600	602.4	615.51		617.08	0.00231	10.09	1374.17	131.07	0.53

Table 14: Flood Scenario 9 HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl
9 (1b+2+3+4+5+6)	11675	0.2-Percent	18000	602.4	616.75		618.98	0.00285	12.02	1539.74	137.59	0.6
9 (1b+2+3+4+5+6)	10302	10-Percent	7990	603.2	610.48		611.37	0.002505	7.65	1175.86	345.04	0.51
9 (1b+2+3+4+5+6)	10302	2-Percent	11800	603.2	612.06	609.46	613.1	0.002394	8.59	1900.99	568.72	0.52
9 (1b+2+3+4+5+6)	10302	1-Percent	13600	603.2	612.55	610.2	613.67	0.002466	9.05	2184.57	589.07	0.53
9 (1b+2+3+4+5+6)	10302	0.2-Percent	18000	603.2	613.23	612.13	614.7	0.003059	10.58	2588.13	602.95	0.6
9 (1b+2+3+4+5+6)	9372	10-Percent	7990	599.6	604.78	604.78	606.96	0.011022	11.85	675.35	156.98	1
9 (1b+2+3+4+5+6)	9372	2-Percent	11800	599.6	606.07	606.07	608.89	0.010151	13.5	880.47	161.34	1
9 (1b+2+3+4+5+6)	9372	1-Percent	13600	599.6	606.96	606.96	609.69	0.008171	13.34	1056.49	244.39	0.92
9 (1b+2+3+4+5+6)	9372	0.2-Percent	18000	599.6	608.87	608.87	611.04	0.005014	12.39	1721.36	525.34	0.75
9 (1b+2+3+4+5+6)	8312	10-Percent	7990	595.5	603.77		604.05	0.000899	4.61	3018.02	695.93	0.31
9 (1b+2+3+4+5+6)	8312	2-Percent	11800	595.5	605.24		605.59	0.00093	5.33	4055.5	735.74	0.32
9 (1b+2+3+4+5+6)	8312	1-Percent	13600	595.5	605.91		606.28	0.000914	5.56	4562.1	773.05	0.32
9 (1b+2+3+4+5+6)	8312	0.2-Percent	18000	595.5	607.56		607.96	0.000826	5.9	5883.15	810.61	0.32
9 (1b+2+3+4+5+6)	8145	10-Percent	7990	592.1	603.69	597.15	603.95	0.000419	4.1	1948.56	259.94	0.22
9 (1b+2+3+4+5+6)	8145	2-Percent	11800	592.1	605.01	598.29	605.46	0.000613	5.37	2196.84	344.66	0.28
9 (1b+2+3+4+5+6)	8145	1-Percent	13600	592.1	605.6	598.79	606.14	0.000691	5.89	2307.53	382.67	0.3
9 (1b+2+3+4+5+6)	8145	0.2-Percent	18000	592.1	607.03	599.9	607.79	0.000837	6.98	2577.65	465.84	0.33
9 (1b+2+3+4+5+6)	8049 Railroad Bridge	Bridge										
9 (1b+2+3+4+5+6)	7984	10-Percent	7990	592.1	602.96	599.55	603.6	0.001574	6.42	1259.48	197.13	0.41
9 (1b+2+3+4+5+6)	7984	2-Percent	11800	592.1	603.73	600.86	604.86	0.002466	8.58	1397.39	307.81	0.52
9 (1b+2+3+4+5+6)	7984	1-Percent	13600	592.1	604.01	601.43	605.42	0.002922	9.55	1448.28	334.66	0.57
9 (1b+2+3+4+5+6)	7984	0.2-Percent	18000	592.1	604.57	602.7	606.72	0.004138	11.84	1548.07	371.63	0.69
9 (1b+2+3+4+5+6)	7758	10-Percent	7990	595	602.59	601.29	602.86	0.001116	5.07	2455.9	845.94	0.34
9 (1b+2+3+4+5+6)	7758	2-Percent	11800	595	603.43	601.93	603.75	0.001221	5.73	3171.32	856.25	0.37
9 (1b+2+3+4+5+6)	7758	1-Percent	13600	595	603.77	602.17	604.11	0.001261	6	3463.53	858.51	0.37
9 (1b+2+3+4+5+6)	7758	0.2-Percent	18000	595	604.54	602.68	604.93	0.001328	6.54	4120.78	925.23	0.39
9 (1b+2+3+4+5+6)	7564	10-Percent	7990	594.9	602.1		602.37	0.001238	5.19	2432.35	873.43	0.36
9 (1b+2+3+4+5+6)	7564	2-Percent	11800	594.9	602.88		603.21	0.001364	5.87	3124.49	885.95	0.38
9 (1b+2+3+4+5+6)	7564	1-Percent	13600	594.9	603.21		603.56	0.001407	6.14	3411.07	887.9	0.39
9 (1b+2+3+4+5+6)	7564	0.2-Percent	18000	594.9	603.95		604.35	0.001462	6.66	4070.2	896.43	0.41
9 (1b+2+3+4+5+6)	7340	10-Percent	7990	594.8	601.48		601.79	0.001588	5.51	2304.36	999.1	0.4
9 (1b+2+3+4+5+6)	7340	2-Percent	11800	594.8	602.26		602.6	0.001627	6.05	3082.99	1015.12	0.41
9 (1b+2+3+4+5+6)	7340	1-Percent	13600	594.8	602.58		602.94	0.001619	6.23	3415.33	1025.66	0.41
9 (1b+2+3+4+5+6)	7340	0.2-Percent	18000	594.8	603.35		603.72	0.001552	6.53	4210.64	1063.02	0.41
9 (1b+2+3+4+5+6)	7151	10-Percent	7990	594.7	600.72		601.02	0.001818	5.28	2283.63	992.8	0.42
9 (1b+2+3+4+5+6)	7151	2-Percent	11800	594.7	601.5		601.83	0.001764	5.73	3060.81	1006.13	0.42
9 (1b+2+3+4+5+6)	7151	1-Percent	13600	594.7	601.84		602.18	0.001719	5.87	3410.87	1069.43	0.42
9 (1b+2+3+4+5+6)	7151	0.2-Percent	18000	594.7	602.67		603.02	0.001536	6.04	4312.61	1097.17	0.4
9 (1b+2+3+4+5+6)	6890	10-Percent	7990	593	599.98	598.99	600.19	0.001332	4.52	2700.11	1321.2	0.36
9 (1b+2+3+4+5+6)	6890	2-Percent	11800	593	600.81	599.42	601.03	0.001248	4.84	3618.08	1860.98	0.35
9 (1b+2+3+4+5+6)	6890	1-Percent	13600	593	601.18	599.6	601.41	0.001192	4.93	4043.34	2012.64	0.35
9 (1b+2+3+4+5+6)	6890	0.2-Percent	18000	593	602.11	599.98	602.34	0.001019	5	5120.79	2125.54	0.33
9 (1b+2+3+4+5+6)	6631	10-Percent	7990	592	598.88	598.09	599.22	0.002199	5.5	2048.72	845.94	0.45
9 (1b+2+3+4+5+6)	6631	2-Percent	11800	592	599.8	598.61	600.15	0.0019	5.77	2833.63	856.02	0.43

Table 14: Flood Scenario 9 HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl
9 (1b+2+3+4+5+6)	6631	1-Percent	13600	592	600.23	598.8	600.59	0.00175	5.83	3202.73	857.62	0.42
9 (1b+2+3+4+5+6)	6631	0.2-Percent	18000	592	601.29	599.27	601.65	0.001417	5.85	4118.1	861.57	0.39
9 (1b+2+3+4+5+6)	6324	10-Percent	7990	590.5	597.72	596.49	598.07	0.001592	5.35	2061.51	735.17	0.39
9 (1b+2+3+4+5+6)	6324	2-Percent	11800	590.5	598.74	597.24	599.11	0.001501	5.79	2817.51	749.45	0.39
9 (1b+2+3+4+5+6)	6324	1-Percent	13600	590.5	599.26	597.51	599.63	0.001368	5.82	3212.3	751.33	0.38
9 (1b+2+3+4+5+6)	6324	0.2-Percent	18000	590.5	600.52	598.04	600.88	0.001113	5.83	4155.59	755.8	0.35
9 (1b+2+3+4+5+6)	6015	10-Percent	7990	588.7	596.02		596.55	0.002894	6.85	1655.77	616.74	0.53
9 (1b+2+3+4+5+6)	6015	2-Percent	11800	588.7	597.59		597.98	0.001661	6.18	2635.11	629.4	0.42
9 (1b+2+3+4+5+6)	6015	1-Percent	13600	588.7	598.28		598.65	0.001384	6.02	3070.18	631.55	0.39
9 (1b+2+3+4+5+6)	6015	0.2-Percent	18000	588.7	599.73		600.1	0.001071	5.96	3991.84	636.06	0.35
9 (1b+2+3+4+5+6)	5607	10-Percent	7990	587.3	595.08	593.12	595.32	0.001031	4.82	2303.08	587.02	0.33
9 (1b+2+3+4+5+6)	5607	2-Percent	11800	587.3	597.01	593.76	597.22	0.000663	4.58	3440.82	591.55	0.28
9 (1b+2+3+4+5+6)	5607	1-Percent	13600	587.3	597.77	594.06	597.98	0.0006	4.61	3889.67	593.32	0.27
9 (1b+2+3+4+5+6)	5607	0.2-Percent	18000	587.3	599.29	594.64	599.54	0.000542	4.84	4797.04	596.9	0.26
9 (1b+2+3+4+5+6)	5307	10-Percent	7990	585.8	594.68		594.87	0.000602	4.11	2629.68	557.59	0.26
9 (1b+2+3+4+5+6)	5307	2-Percent	11800	585.8	596.73		596.92	0.000441	4.11	3779.72	564.11	0.23
9 (1b+2+3+4+5+6)	5307	1-Percent	13600	585.8	597.51		597.7	0.000417	4.2	4218.63	566.57	0.23
9 (1b+2+3+4+5+6)	5307	0.2-Percent	18000	585.8	599.05		599.27	0.000406	4.53	5093.81	575.01	0.23
9 (1b+2+3+4+5+6)	5051	10-Percent	7990	584.3	594.17		594.49	0.000854	4.82	1895.88	320.29	0.31
9 (1b+2+3+4+5+6)	5051	2-Percent	11800	584.3	596.23		596.6	0.000742	5.26	2565.43	331.57	0.3
9 (1b+2+3+4+5+6)	5051	1-Percent	13600	584.3	597		597.4	0.000734	5.5	2867.61	477.89	0.3
9 (1b+2+3+4+5+6)	5051	0.2-Percent	18000	584.3	598.52		598.97	0.000717	5.95	3779.32	711.64	0.3
9 (1b+2+3+4+5+6)	4786	10-Percent	7990	582.8	593.59		594.05	0.000961	5.61	1529.04	204.32	0.33
9 (1b+2+3+4+5+6)	4786	2-Percent	11800	582.8	595.59		596.19	0.000971	6.46	2116.7	457.63	0.34
9 (1b+2+3+4+5+6)	4786	1-Percent	13600	582.8	596.36		596.98	0.00096	6.72	2506.75	576.63	0.35
9 (1b+2+3+4+5+6)	4786	0.2-Percent	18000	582.8	597.93		598.57	0.000909	7.11	3654.12	826.1	0.34
9 (1b+2+3+4+5+6)	4582	10-Percent	7990	582.7	593.03		593.59	0.001217	6.12	1392.88	205.08	0.37
9 (1b+2+3+4+5+6)	4582	2-Percent	11800	582.7	595.03		595.72	0.001187	6.95	1994.44	420.6	0.38
9 (1b+2+3+4+5+6)	4582	1-Percent	13600	582.7	595.79		596.52	0.001177	7.26	2402.89	618.65	0.38
9 (1b+2+3+4+5+6)	4582	0.2-Percent	18000	582.7	597.37		598.14	0.001119	7.72	3533.52	854.73	0.38
9 (1b+2+3+4+5+6)	4363	10-Percent	7990	582.5	592.71	588.54	593.12	0.000913	5.39	1641.92	237.07	0.32
9 (1b+2+3+4+5+6)	4363	2-Percent	11800	582.5	594.73	589.87	595.26	0.000906	6.17	2161.48	491.57	0.33
9 (1b+2+3+4+5+6)	4363	1-Percent	13600	582.5	595.48	590.39	596.06	0.000927	6.52	2387.73	683.43	0.34
9 (1b+2+3+4+5+6)	4363	0.2-Percent	18000	582.5	596.99	591.52	597.7	0.000983	7.29	3058.42	1123.5	0.36
9 (1b+2+3+4+5+6)	4182	10-Percent	7990	582.4	592.31	588.27	592.91	0.001282	6.23	1296.47	164.95	0.38
9 (1b+2+3+4+5+6)	4182	2-Percent	11800	582.4	594.17	589.64	595.03	0.001413	7.48	1626.48	243.93	0.41
9 (1b+2+3+4+5+6)	4182	1-Percent	13600	582.4	594.83	590.22	595.81	0.001505	8.04	1777.42	377.88	0.43
9 (1b+2+3+4+5+6)	4182	0.2-Percent	18000	582.4	596.15	591.56	597.41	0.001703	9.23	2152.41	632.12	0.46
9 (1b+2+3+4+5+6)	3997	10-Percent	7990	582.3	592.12	587.76	592.67	0.001125	5.95	1352.94	190.66	0.36
9 (1b+2+3+4+5+6)	3997	2-Percent	11800	582.3	593.96	589.1	594.76	0.001283	7.22	1664.48	223.99	0.39
9 (1b+2+3+4+5+6)	3997	1-Percent	13600	582.3	594.59	589.64	595.53	0.001394	7.82	1802.75	281.59	0.41
9 (1b+2+3+4+5+6)	3997	0.2-Percent	18000	582.3	595.81	590.98	597.1	0.001689	9.23	2124.72	512.9	0.46
9 (1b+2+3+4+5+6)	3670	10-Percent	7990	582.1	591.97		592.32	0.000786	5.14	3197.67	1118.11	0.3
9 (1b+2+3+4+5+6)	3670	2-Percent	11800	582.1	594.03		594.34	0.000623	5.24	5655.63	1230.59	0.28

Table 14: Flood Scenario 9 HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl
9 (1b+2+3+4+5+6)	3670	1-Percent	13600	582.1	594.75		595.07	0.000605	5.39	6554.79	1256.34	0.28
9 (1b+2+3+4+5+6)	3670	0.2-Percent	18000	582.1	596.18		596.52	0.000604	5.81	8437.7	1373.85	0.28
9 (1b+2+3+4+5+6)	2921	10-Percent	7990	576.6	591.5		591.86	0.000498	4.85	1852.73	452.33	0.25
9 (1b+2+3+4+5+6)	2921	2-Percent	11800	576.6	593.39		593.87	0.000588	5.82	3296.29	1158.38	0.28
9 (1b+2+3+4+5+6)	2921	1-Percent	13600	576.6	594.11		594.6	0.000591	6.04	4255.27	1414.15	0.28
9 (1b+2+3+4+5+6)	2921	0.2-Percent	18000	576.6	595.64		596.08	0.000535	6.15	6446.61	1446.59	0.27
9 (1b+2+3+4+5+6)	1922	10-Percent	7990	573.7	591.43		591.52	0.000159	3.15	6696.9	1308.98	0.15
9 (1b+2+3+4+5+6)	1922	2-Percent	11800	573.7	593.4		593.49	0.000151	3.34	9344.27	1355.68	0.14
9 (1b+2+3+4+5+6)	1922	1-Percent	13600	573.7	594.12		594.22	0.000152	3.45	10348.69	1409.83	0.15
9 (1b+2+3+4+5+6)	1922	0.2-Percent	18000	573.7	595.61		595.71	0.00016	3.74	12703.76	1786.97	0.15
9 (1b+2+3+4+5+6)	833	10-Percent	7990	571.5	591.31		591.38	0.000094	2.65	5431.72	1295.17	0.11
9 (1b+2+3+4+5+6)	833	2-Percent	11800	571.5	593.29		593.36	0.000089	2.77	8382.02	1690.87	0.11
9 (1b+2+3+4+5+6)	833	1-Percent	13600	571.5	594.02		594.08	0.000088	2.82	9641.88	1774.35	0.11
9 (1b+2+3+4+5+6)	833	0.2-Percent	18000	571.5	595.51		595.58	0.000087	2.96	12526.76	2314.31	0.11
9 (1b+2+3+4+5+6)	279	10-Percent	7990	571	591.21	580.11	591.3	0.00012	2.8	4718.34	1042.68	0.13
9 (1b+2+3+4+5+6)	279	2-Percent	11800	571	593.19	581.81	593.28	0.00012	3.04	6888.45	1267.82	0.13
9 (1b+2+3+4+5+6)	279	1-Percent	13600	571	593.91	582.54	594	0.00012	3.12	7968.79	1787.95	0.13
9 (1b+2+3+4+5+6)	279	0.2-Percent	18000	571	595.4	584.12	595.5	0.00012	3.29	11205.39	2338.5	0.13

1-D HEC-RAS Hydraulic & Hydrologic Model  
Ice-Jam Simulations for Existing and Proposed Conditions Models  
Buffalo Creek - Town of West Seneca, Erie County, NY  
Ramboll Americas Engineering Solutions, Inc.

December 20, 2022

## Contents

FEMA Effective Model with Ice Cover . . . . .	87
Existing Conditions Model with Ice Cover . . . . .	93
FEMA Effective versus Existing Conditions Models with Ice Cover . . . . .	100
Flood Scenario #1 with Ice Cover . . . . .	102
Flood Scenario #2 with Ice Cover . . . . .	108
Flood Scenario #3 with Ice Cover . . . . .	114
Flood Scenario #4 with Ice Cover . . . . .	120
Flood Scenario #5 with Ice Cover . . . . .	126
Flood Scenario #6 with Ice Cover . . . . .	132
Flood Scenario #7 with Ice Cover . . . . .	138
Flood Scenario #8 with Ice Cover . . . . .	144
Flood Scenario #9 with Ice Cover . . . . .	150

## FEMA Effective Model with Ice Cover

Plan: Effective\_FEMA\_BC\_ICE  
Geometry: Effective\_FEMA\_BC\_ICE  
Steady Flow Data: FEMA FIS 1-Percent  
Date: December 2022




Figure 24: Effective FEMA Profile Plot

Edit Ice Cover Data

River: Buffalo Creek     Edit Interpolated XS's

Reach: Reach 1

Selected Area Edit Options

	ver Statn	LOB ice	Chan ice	ROB ice	LOB ice	Chan ice	ROB ice	Ice Specific Gravity	Ice Jam chan (y/n)	Ice Jam OB (y/n)	Friction Angle	Porosity	Stress K1 ratio	Max Velocity	Ice Cohesion	Fixed Mann n (y/n)
		Thickness	Thickness	Thickness	Mann n	Mann n	Mann n									
1	20473							0.916	n	n	45	0	0.33	5	0	y
2	19313							0.916	n	n	45	0	0.33	5	0	y
3	18263							0.916	n	n	45	0	0.33	5	0	y
4	17053							0.916	n	n	45	0	0.33	5	0	y
5	15733							0.916	n	n	45	0	0.33	5	0	y
6	14399							0.916	n	n	45	0	0.33	5	0	y
7	12984							0.916	n	n	45	0	0.33	5	0	y
8	11955							0.916	n	n	45	0	0.33	5	0	y
9	11899							0.916	n	n	45	0	0.33	5	0	y
10	11850	Bridge														
11	11826	1	1	0.02	0.02	0.02	0.916	y	n	45	0	0.33	5	0	n	
12	11682	1	1	0.02	0.02	0.02	0.916	y	n	45	0	0.33	5	0	n	
13	10330	1	1	0.02	0.02	0.02	0.916	y	n	45	0	0.33	5	0	n	
14	9376	1	1	0.02	0.02	0.02	0.916	y	n	45	0	0.33	5	0	n	
15	8312	1	1	0.02	0.02	0.02	0.916	y	n	45	0	0.33	5	0	n	
16	8081	1	1	0.02	0.02	0.02	0.916	y	n	45	0	0.33	5	0	n	
17	8050	Bridge														
18	8016	1	1	0.02	0.02	0.02	0.916	y	n	45	0	0.33	5	0	n	
19	7906	1	1	0.02	0.02	0.02	0.916	y	n	45	0	0.33	5	0	n	
20	7140	1	1	0.02	0.02	0.02	0.916	y	n	45	0	0.33	5	0	n	
21	6009	1	1	0.02	0.02	0.02	0.916	y	n	45	0	0.33	5	0	n	
22	4785	1	1	0.02	0.02	0.02	0.916	y	n	45	0	0.33	5	0	n	
23	3686	1	1	0.02	0.02	0.02	0.916	y	n	45	0	0.33	5	0	n	
24	2949	1	1	0.02	0.02	0.02	0.916	y	n	45	0	0.33	5	0	n	
25	1922	1	1	0.02	0.02	0.02	0.916	y	n	45	0	0.33	5	0	n	
26	866	1	1	0.02	0.02	0.02	0.916	y	n	45	0	0.33	5	0	n	
27	279	1	1	0.02	0.02	0.02	0.916	n	n	45	0	0.33	5	0	n	

OK Cancel Help

Figure 25: Ice Cover Data Table

Table 1: Effective FEMA with Ice Cover HEC-RAS Output

Alternative	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chn
Effective FEMA (FIS)	20473	1-Percent	16000	621.4	635.1	630.06	636.14	0.002422	8.44	2339.4	363.98	0.42	
Effective FEMA (FIS)	19313	1-Percent	16000	620.4	631.83	629.79	633.19	0.002611	9.92	2282.72	560.78	0.56	
Effective FEMA (FIS)	18263	1-Percent	16000	617.6	629.96		630.41	0.00219	6.11	3644.22	573.42	0.33	
Effective FEMA (FIS)	17053	1-Percent	16000	615.5	628.24		628.59	0.001069	4.99	4138.64	632.76	0.28	
Effective FEMA (FIS)	15733	1-Percent	16000	612.8	625.83		626.36	0.003008	5.98	2955.98	381.32	0.34	
Effective FEMA (FIS)	14399	1-Percent	16000	610.3	624.61		624.74	0.000583	2.88	5954.18	750.26	0.16	
Effective FEMA (FIS)	12984	1-Percent	16000	608.9	624.06	615.52	624.14	0.000307	2.64	10513.81	1614.9	0.13	
Effective FEMA (FIS)	11955	1-Percent	16000	604.9	622.13	615.38	623.45	0.001286	9.28	1888.5	429.9	0.42	
Effective FEMA (FIS)	11899	1-Percent	16000	605.5	622.07	614.87	623.37	0.001164	9.15	1747.96	151.61	0.4	
Effective FEMA (FIS)	11850		Bridge										
Effective FEMA (FIS)	11826	1-Percent	16000	605.5	621.16	615.75	622.82	0.004406	10.34	1547.06	141.67	0.49	1
Effective FEMA (FIS)	11682	1-Percent	16000	602.4	620.84	613.71	621.8	0.004836	7.98	2325.7	366.38	0.36	1
Effective FEMA (FIS)	10330	1-Percent	16000	603.2	616.34		616.76	0.002799	5.67	3808.96	670.4	0.33	1
Effective FEMA (FIS)	9376	1-Percent	16000	599.6	613.24	610.97	613.84	0.003324	7.59	4276.3	1259.6	0.41	1
Effective FEMA (FIS)	8312	1-Percent	16000	595.5	609.53	604.94	609.88	0.004037	0.7	3556.4	584.46	0.1	12.93
Effective FEMA (FIS)	8081	1-Percent	16000	592.1	608.42	602.41	609.31	0.000993	7.58	2111.77	260.68	0.38	1
Effective FEMA (FIS)	8050		Bridge										
Effective FEMA (FIS)	8016	1-Percent	16000	592.1	608.35	602.41	609.25	0.001012	7.62	2099.92	323.33	0.38	1
Effective FEMA (FIS)	7906	1-Percent	16000	595.2	608.38	603.55	608.89	0.002332	6.34	4366.1	1036.53	0.34	1
Effective FEMA (FIS)	7140	1-Percent	16000	594.7	606.12	603.39	606.61	0.003903	6.33	4321.31	1404.51	0.4	1
Effective FEMA (FIS)	6009	1-Percent	16000	588.7	602.18	597.64	602.8	0.002921	6.47	3148.32	957.35	0.37	1
Effective FEMA (FIS)	4785	1-Percent	16000	582.8	600.51	593.05	600.79	0.000968	4.8	6474.99	1491.53	0.23	1
Effective FEMA (FIS)	3686	1-Percent	16000	582.1	597.3	593.17	598.62	0.005097	9.26	1904.8	1506.92	0.5	1
Effective FEMA (FIS)	2949	1-Percent	16000	576.6	595.92	588.34	596.23	0.001797	5.2	5830.47	1435.89	0.24	1
Effective FEMA (FIS)	1922	1-Percent	16000	573.7	594.03		594.15	0.002169	3.87	6209.09	977.3	0.22	7.26
Effective FEMA (FIS)	866	1-Percent	16000	571.5	591.87	585.35	592.27	0.001453	6.02	5251.94	1208.37	0.29	1
Effective FEMA (FIS)	279	1-Percent	16000	571	590.94	584.27	591.48	0.001201	6.66	3591.4	789.43	0.31	1

Table 2: Effective FEMA with Ice Cover using USGS StreamStats Discharges HEC-RAS Output

Alternative	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.ChnL	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chan
Effective FEMA (USGS)	20473	10-Percent	7990	621.4	631.86	627.21	632.43	0.001879	6.06	1357.15	185.89	0.36	
Effective FEMA (USGS)	20473	2-Percent	11800	621.4	633.59	628.68	634.42	0.0022	7.37	1814.75	337.25	0.4	
Effective FEMA (USGS)	20473	1-Percent	13600	621.4	634.28	629.31	635.2	0.002305	7.86	2050.13	348.33	0.41	
Effective FEMA (USGS)	20473	0.2-Percent	18000	621.4	635.67	630.7	636.83	0.002553	8.93	2542.47	429.62	0.44	
Effective FEMA (USGS)	19313	10-Percent	7990	620.4	629.04	626.42	629.94	0.002401	7.64	1188.13	371.99	0.5	
Effective FEMA (USGS)	19313	2-Percent	11800	620.4	630.47	627.85	631.63	0.00257	8.92	1738.49	394.03	0.54	
Effective FEMA (USGS)	19313	1-Percent	13600	620.4	631.08	628.77	632.33	0.002593	9.38	1979.32	439.39	0.55	
Effective FEMA (USGS)	19313	0.2-Percent	18000	620.4	632.44	630.34	633.85	0.002541	10.19	2730.41	617.63	0.55	
Effective FEMA (USGS)	18263	10-Percent	7990	617.6	626.72		627.1	0.002729	5.31	1960.44	490.74	0.35	
Effective FEMA (USGS)	18263	2-Percent	11800	617.6	628.39		628.8	0.002398	5.73	2792.41	506.35	0.34	
Effective FEMA (USGS)	18263	1-Percent	13600	617.6	629.09		629.52	0.002302	5.91	3154.29	533.93	0.34	
Effective FEMA (USGS)	18263	0.2-Percent	18000	617.6	630.72		631.17	0.002056	6.2	4079.84	585.62	0.33	
Effective FEMA (USGS)	17053	10-Percent	7990	615.5	624.83		625.09	0.001084	4.13	2129.69	511.75	0.28	
Effective FEMA (USGS)	17053	2-Percent	11800	615.5	626.56		626.87	0.001107	4.64	3106.21	592.82	0.28	
Effective FEMA (USGS)	17053	1-Percent	13600	615.5	627.31		627.64	0.00109	4.8	3559.13	610.66	0.28	
Effective FEMA (USGS)	17053	0.2-Percent	18000	615.5	629.1		629.45	0.001007	5.06	4691.25	653.13	0.27	
Effective FEMA (USGS)	15733	10-Percent	7990	612.8	622.13		622.54	0.0043	5.15	1621.19	340.6	0.38	
Effective FEMA (USGS)	15733	2-Percent	11800	612.8	623.98		624.45	0.003549	5.62	2266.7	360.87	0.36	
Effective FEMA (USGS)	15733	1-Percent	13600	612.8	624.82		625.31	0.003245	5.77	2576.35	370.19	0.35	
Effective FEMA (USGS)	15733	0.2-Percent	18000	612.8	626.89		627.41	0.002606	5.97	3367.08	393.01	0.32	
Effective FEMA (USGS)	14399	10-Percent	7990	610.3	620.28		620.39	0.00079	2.58	3125.48	564.55	0.19	
Effective FEMA (USGS)	14399	2-Percent	11800	610.3	622.49		622.61	0.00067	2.74	4455.94	654.92	0.17	
Effective FEMA (USGS)	14399	1-Percent	13600	610.3	623.49		623.61	0.000617	2.79	5134.41	703.34	0.16	
Effective FEMA (USGS)	14399	0.2-Percent	18000	610.3	625.89		626.01	0.000495	2.82	6944.43	796.45	0.15	
Effective FEMA (USGS)	12984	10-Percent	7990	608.9	619.32	613.62	619.43	0.000581	2.8	3696.84	1122.82	0.17	
Effective FEMA (USGS)	12984	2-Percent	11800	608.9	621.73	614.63	621.84	0.000447	2.84	5915.19	1356.16	0.16	
Effective FEMA (USGS)	12984	1-Percent	13600	608.9	622.79	615.06	622.9	0.000414	2.88	6990.31	1557.67	0.15	
Effective FEMA (USGS)	12984	0.2-Percent	18000	608.9	625.46	615.87	625.53	0.00024	2.48	12805.66	1667.27	0.12	
Effective FEMA (USGS)	11955	10-Percent	7990	604.9	618.01	612.1	618.64	0.000917	6.37	1282.16	123.24	0.33	
Effective FEMA (USGS)	11955	2-Percent	11800	604.9	620.08	613.77	621.05	0.001137	7.94	1543.06	225.23	0.38	
Effective FEMA (USGS)	11955	1-Percent	13600	604.9	620.99	614.48	622.12	0.00121	8.55	1664.82	289.92	0.4	
Effective FEMA (USGS)	11955	0.2-Percent	18000	604.9	623.59	616.1	624.93	0.001174	9.41	2285.2	616.21	0.4	
Effective FEMA (USGS)	11899	10-Percent	7990	605.5	617.98	611.65	618.57	0.000781	6.15	1298.8	134.64	0.32	
Effective FEMA (USGS)	11899	2-Percent	11800	605.5	620.04	613.28	620.97	0.000998	7.74	1525.09	137.47	0.37	
Effective FEMA (USGS)	11899	1-Percent	13600	605.5	620.94	613.99	622.03	0.001074	8.37	1624.31	142.18	0.38	
Effective FEMA (USGS)	11899	0.2-Percent	18000	605.5	623.66	615.6	624.72	0.001279	8.27	2417.39	441.97	0.35	
Effective FEMA (USGS)	11850		Bridge										
Effective FEMA (USGS)	11826	10-Percent	7990	605.5	617.73	612.56	618.45	0.002792	6.83	1169.5	135.66	0.37	1
Effective FEMA (USGS)	11826	2-Percent	11800	605.5	619.61	614.2	620.75	0.003539	8.57	1376.3	138.93	0.43	1
Effective FEMA (USGS)	11826	1-Percent	13600	605.5	620.35	614.91	621.7	0.003882	9.33	1457.68	140.22	0.45	1
Effective FEMA (USGS)	11826	0.2-Percent	18000	605.5	621.77	616.52	623.71	0.004833	11.15	1614.94	142.82	0.51	1
Effective FEMA (USGS)	11682	10-Percent	7990	602.4	617.45	610.59	617.89	0.003019	5.31	1528.4	144.23	0.28	1
Effective FEMA (USGS)	11682	2-Percent	11800	602.4	619.28	612.2	619.99	0.004009	6.75	1806.39	218.41	0.33	1

Table 2: Effective FEMA with Ice Cover using USGS StreamStats Discharges HEC-RAS Output (continued)

Alternative	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.ChnL	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chn
Effective FEMA (USGS)	11682	1-Percent	13600	602.4	620.01	612.88	620.84	0.004411	7.34	2024.53	357.48	0.34	1
Effective FEMA (USGS)	11682	0.2-Percent	18000	602.4	621.5	614.37	622.55	0.005102	8.44	2567.73	373.49	0.38	1
Effective FEMA (USGS)	10330	10-Percent	7990	603.2	613.83		614.11	0.002534	4.44	229.07	595.04	0.31	1
Effective FEMA (USGS)	10330	2-Percent	11800	603.2	615.16		615.51	0.002658	5.07	3043.76	626.64	0.32	1
Effective FEMA (USGS)	10330	1-Percent	13600	603.2	615.66		616.04	0.002772	5.37	3358.01	644.97	0.33	1
Effective FEMA (USGS)	10330	0.2-Percent	18000	603.2	616.76		617.22	0.002953	5.99	4139.29	854.94	0.34	1
Effective FEMA (USGS)	9376	10-Percent	7990	599.6	610.59	607.52	611.15	0.003799	6.52	1846.1	633.49	0.4	1
Effective FEMA (USGS)	9376	2-Percent	11800	599.6	611.97	609.73	612.56	0.003571	7.14	2743.38	925.28	0.41	1
Effective FEMA (USGS)	9376	1-Percent	13600	599.6	612.52	610.31	613.1	0.003409	7.28	3421.29	1072.58	0.4	1
Effective FEMA (USGS)	9376	0.2-Percent	18000	599.6	613.74	611.35	614.31	0.00312	7.62	4917.27	1273.64	0.4	1
Effective FEMA (USGS)	8312	10-Percent	7990	595.5	609.3	603.51	609.36	0.000833	0.98	4394.07	689.07	0.08	7.54
Effective FEMA (USGS)	8312	2-Percent	11800	595.5	608.12	604.2	608.41	0.004091	0.57	2881.95	548.9	0.09	11.93
Effective FEMA (USGS)	8312	1-Percent	13600	595.5	608.75	604.54	609.07	0.004055	0.63	3182.07	565.22	0.1	12.37
Effective FEMA (USGS)	8312	0.2-Percent	18000	595.5	610.12	605.26	610.51	0.004032	0.75	3856.67	600.02	0.1	13.34
Effective FEMA (USGS)	8081	10-Percent	7990	592.1	608.71	603.27	609.1	0.000627	5	1597.92	262.44	0.29	4.66
Effective FEMA (USGS)	8081	2-Percent	11800	592.1	607.43	601.2	608	0.00071	6.06	1945.81	253.43	0.31	1
Effective FEMA (USGS)	8081	1-Percent	13600	592.1	607.89	601.74	608.59	0.000827	6.72	2023.44	256.82	0.34	1
Effective FEMA (USGS)	8081	0.2-Percent	18000	592.1	608.79	602.94	609.85	0.001141	8.28	2173.99	263.39	0.41	1
Effective FEMA (USGS)	8050	Bridge											
Effective FEMA (USGS)	8016	10-Percent	7990	592.1	608.55	603.11	608.94	0.000627	5	1598.2	326.08	0.29	4.48
Effective FEMA (USGS)	8016	2-Percent	11800	592.1	607.38	601.21	607.96	0.00072	6.09	1937.4	294.75	0.32	1
Effective FEMA (USGS)	8016	1-Percent	13600	592.1	607.83	601.74	608.54	0.000841	6.75	2013.75	305.38	0.34	1
Effective FEMA (USGS)	8016	0.2-Percent	18000	592.1	608.71	602.94	609.78	0.001165	8.33	2160.37	336.93	0.41	1
Effective FEMA (USGS)	7906	10-Percent	7990	595.2	608.57	605.34	608.66	0.002617	3.02	3905.66	1052.63	0.19	4.9
Effective FEMA (USGS)	7906	2-Percent	11800	595.2	607.33	602.32	607.75	0.002107	5.57	3336.89	911.47	0.31	1
Effective FEMA (USGS)	7906	1-Percent	13600	595.2	607.82	602.87	608.27	0.002206	5.92	3797.04	980.01	0.33	1
Effective FEMA (USGS)	7906	0.2-Percent	18000	595.2	608.79	604.31	609.34	0.002443	6.68	4799.33	1077.58	0.35	1
Effective FEMA (USGS)	7140	10-Percent	7990	594.7	607.05	604.31	607.15	0.001546	3.35	4610.52	1352.35	0.24	5.54
Effective FEMA (USGS)	7140	2-Percent	11800	594.7	604.92	601.55	605.44	0.00459	6.16	2824.62	1082.28	0.42	1
Effective FEMA (USGS)	7140	1-Percent	13600	594.7	605.51	602.24	606.01	0.004149	6.19	3505.2	1239.5	0.4	1
Effective FEMA (USGS)	7140	0.2-Percent	18000	594.7	606.56	604.73	607.04	0.003701	6.39	4945.29	1406.4	0.39	1
Effective FEMA (USGS)	6009	10-Percent	7990	588.7	604.38	601.87	604.44	0.004168	2.38	4266.48	1510.3	0.18	8.19
Effective FEMA (USGS)	6009	2-Percent	11800	588.7	601.08	596.47	601.57	0.002647	5.6	2154.49	632.88	0.34	1
Effective FEMA (USGS)	6009	1-Percent	13600	588.7	601.64	596.93	602.2	0.002783	6.04	2326.45	796.05	0.35	1
Effective FEMA (USGS)	6009	0.2-Percent	18000	588.7	602.98	598.07	603.57	0.002566	6.46	4007.12	1176.47	0.35	1
Effective FEMA (USGS)	4785	10-Percent	7990	582.8	599.37	596.32	599.46	0.003963	3.01	3794.83	1314.54	0.2	7.28
Effective FEMA (USGS)	4785	2-Percent	11800	582.8	599.6	591.77	599.81	0.000834	4.11	5157.2	1358.47	0.21	1.06
Effective FEMA (USGS)	4785	1-Percent	13600	582.8	600.23	592.3	600.45	0.000794	4.28	6051.94	1449.82	0.21	1
Effective FEMA (USGS)	4785	0.2-Percent	18000	582.8	601.7	593.62	601.92	0.000745	4.5	8421.34	1787.86	0.21	1
Effective FEMA (USGS)	3686	10-Percent	7990	582.1	595.63	590.3	596.11	0.002375	5.54	1443.42	1171.26	0.32	1
Effective FEMA (USGS)	3686	2-Percent	11800	582.1	597.64	591.75	598.3	0.002443	6.57	2089.89	1627.63	0.35	1
Effective FEMA (USGS)	3686	1-Percent	13600	582.1	598.18	592.37	598.94	0.002646	7.1	2425.09	1719.77	0.37	1
Effective FEMA (USGS)	3686	0.2-Percent	18000	582.1	599.55	593.78	600.44	0.002756	7.9	3741.48	2361.78	0.39	1

Table 2: Effective FEMA with Ice Cover using USGS StreamStats Discharges HEC-RAS  
Output (*continued*)

Alternative	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.ChnL	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chn
Effective FEMA (USGS)	2949	10-Percent	7990	576.6	594.26	587.83	594.49	0.001859	4.19	2514.97	1011.06	0.23	4
Effective FEMA (USGS)	2949	2-Percent	11800	576.6	596.33	592	596.48	0.002109	4.15	5550.47	1472.24	0.24	7.49
Effective FEMA (USGS)	2949	1-Percent	13600	576.6	597.05	592.4	597.18	0.001738	4	6665.69	1536.8	0.22	7.3
Effective FEMA (USGS)	2949	0.2-Percent	18000	576.6	598.66	593.18	598.78	0.001435	4	9340.39	2155.21	0.2	7.3
Effective FEMA (USGS)	1922	10-Percent	7990	573.7	593.67		593.71	0.000368	2.03	6505.83	965.33	0.09	2.18
Effective FEMA (USGS)	1922	2-Percent	11800	573.7	595.62		595.67	0.000387	2.29	8494.53	1046.87	0.1	1.86
Effective FEMA (USGS)	1922	1-Percent	13600	573.7	596.36		596.41	0.0004	2.41	9611.28	1605.78	0.1	1.8
Effective FEMA (USGS)	1922	0.2-Percent	18000	573.7	597.92		597.98	0.00047	2.76	12409.46	1895	0.11	1.85
Effective FEMA (USGS)	866	10-Percent	7990	571.5	593.35	581.88	593.41	0.00022	2.38	7333.96	1622.03	0.11	1.16
Effective FEMA (USGS)	866	2-Percent	11800	571.5	595.31	583.93	595.36	0.000227	2.5	11484.28	2531.31	0.11	1.33
Effective FEMA (USGS)	866	1-Percent	13600	571.5	596.06	584.73	596.1	0.000219	2.52	13373.41	2537.43	0.11	1.35
Effective FEMA (USGS)	866	0.2-Percent	18000	571.5	597.61	586.63	597.66	0.00021	2.57	17323.23	2547.76	0.1	1.43
Effective FEMA (USGS)	279	10-Percent	7990	571	593.26	580.94	593.32	0.00012	2.33	5938.97	1086.65	0.1	1
Effective FEMA (USGS)	279	2-Percent	11800	571	595.21	582.65	595.27	0.00012	2.51	8729.02	2120.86	0.1	1
Effective FEMA (USGS)	279	1-Percent	13600	571	595.95	583.39	596.01	0.00012	2.58	10371.94	2265.81	0.1	1
Effective FEMA (USGS)	279	0.2-Percent	18000	571	597.5	584.99	597.56	0.00012	2.72	14251.54	2754.56	0.11	1

## Existing Conditions Model with Ice Cover

Plan: Existing\_Conditions\_UPDATE\_BC\_ICE

Geometry: Existing\_Conditions\_UPDATE\_BC\_ICE

Steady Flow Data: USGS BF,10,2,1,0.2-PERCENT-UPDATE-BC

Date: December 2022




Figure 26: Existing Conditions Profile Plot

Table 3: Existing Conditions with Ice Cover HEC-RAS Output

Alternative	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.ChnL	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chn
Existing (USGS)	20483	10-Percent	7990	621.4	631.44		632.23	0.00152	7.14	1149.93	159.75	0.42	
Existing (USGS)	20483	2-Percent	11800	621.4	633.13		634.27	0.001801	8.71	1502.7	283.71	0.47	
Existing (USGS)	20483	1-Percent	13600	621.4	633.75		635.03	0.001907	9.3	1683.2	292.19	0.49	
Existing (USGS)	20483	0.2-Percent	18000	621.4	635.05		636.62	0.002117	10.53	2068.75	300.59	0.52	
Existing (USGS)													
Existing (USGS)	19313	10-Percent	7990	620.4	628.71		629.8	0.002908	8.44	1044.14	306.61	0.56	
Existing (USGS)	19313	2-Percent	11800	620.4	630.2		631.56	0.003003	9.73	1584.78	383.6	0.58	
Existing (USGS)	19313	1-Percent	13600	620.4	630.82		632.26	0.00298	10.15	1839.24	441.9	0.59	
Existing (USGS)	19313	0.2-Percent	18000	620.4	632.19	630.62	633.75	0.002869	10.92	2526.91	588.68	0.59	
Existing (USGS)													
Existing (USGS)	18244	10-Percent	7990	617.6	626.65		627.29	0.001757	6.95	1777.22	467.86	0.44	
Existing (USGS)	18244	2-Percent	11800	617.6	628.34		629.05	0.001639	7.65	2591.04	496.46	0.44	
Existing (USGS)	18244	1-Percent	13600	617.6	629.04		629.77	0.001595	7.91	2943.68	525.83	0.44	
Existing (USGS)	18244	0.2-Percent	18000	617.6	630.58		631.36	0.001502	8.43	3818.19	582.92	0.43	
Existing (USGS)													
Existing (USGS)	17053	10-Percent	7990	615.5	624.35		625.09	0.001916	7.31	1642.13	449.92	0.46	
Existing (USGS)	17053	2-Percent	11800	615.5	625.99		626.9	0.001962	8.38	2446.6	516.1	0.48	
Existing (USGS)	17053	1-Percent	13600	615.5	626.66		627.64	0.001967	8.79	2801.03	526.03	0.49	
Existing (USGS)	17053	0.2-Percent	18000	615.5	628.2		629.3	0.001934	9.57	3631.51	561.19	0.49	
Existing (USGS)													
Existing (USGS)	15751	10-Percent	7990	612.8	621.5		622.32	0.002353	7.63	1281.07	298.43	0.5	
Existing (USGS)	15751	2-Percent	11800	612.8	623.1		624.11	0.002331	8.68	1817.77	352.78	0.52	
Existing (USGS)	15751	1-Percent	13600	612.8	623.84		624.9	0.002251	9	2081.97	364.33	0.51	
Existing (USGS)	15751	0.2-Percent	18000	612.8	625.57		626.72	0.00203	9.55	2727.68	378.08	0.5	
Existing (USGS)													
Existing (USGS)	14403	10-Percent	7990	610.3	619.62		620	0.001191	5.74	2433.58	541.73	0.36	
Existing (USGS)	14403	2-Percent	11800	610.3	621.69		622.05	0.000915	5.87	3595.31	583.33	0.33	
Existing (USGS)	14403	1-Percent	13600	610.3	622.61		622.96	0.000824	5.91	4152.77	637.99	0.32	
Existing (USGS)	14403	0.2-Percent	18000	610.3	624.76		625.08	0.000625	5.8	5655.52	746.8	0.28	
Existing (USGS)													
Existing (USGS)	12986	10-Percent	7990	608.9	618.23		618.6	0.000826	5.21	2428.01	736.5	0.31	
Existing (USGS)	12986	2-Percent	11800	608.9	620.65		620.99	0.000619	5.29	4557.88	922.38	0.28	
Existing (USGS)	12986	1-Percent	13600	608.9	621.69		622.01	0.00055	5.29	5526.43	947.89	0.27	
Existing (USGS)	12986	0.2-Percent	18000	608.9	624.04		624.33	0.000438	5.31	7810.45	999.57	0.24	
Existing (USGS)													
Existing (USGS)	12162	10-Percent	7990	604.9	617.03		617.77	0.001141	6.98	1207.69	135.15	0.37	
Existing (USGS)	12162	2-Percent	11800	604.9	619.08		620.18	0.001369	8.56	1649.52	402.83	0.42	
Existing (USGS)	12162	1-Percent	13600	604.9	620.09		621.25	0.001345	8.91	2098.69	463.53	0.42	
Existing (USGS)	12162	0.2-Percent	18000	604.9	622.62		623.71	0.001118	9.06	3568.83	729.62	0.39	
Existing (USGS)													
Existing (USGS)	11955	10-Percent	7990	605.5	616.8	611.72	617.53	0.001175	6.85	1177.37	116.61	0.37	
Existing (USGS)	11955	2-Percent	11800	605.5	618.78	613.35	619.89	0.001432	8.48	1413.67	149.66	0.42	
Existing (USGS)	11955	1-Percent	13600	605.5	619.66	614.06	620.94	0.00151	9.11	1521.39	162.34	0.44	
Existing (USGS)	11955	0.2-Percent	18000	605.5	621.71	615.65	623.37	0.001626	10.4	1774.71	330.41	0.47	

Table 3: Existing Conditions with Ice Cover HEC-RAS Output (*continued*)

Alternative	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chn
<b>Existing (USGS)</b>													
Existing (USGS)	11860 Union Rd				Bridge								
Existing (USGS)													
Existing (USGS)	11789	10-Percent	7990	605.5	616.22	612.39	617.18	0.002925	7.85	1022.61	112.37	0.45	1
Existing (USGS)	11789	2-Percent	11800	605.5	617.95	614.02	619.43	0.003606	9.76	1223.01	119.72	0.52	1
Existing (USGS)	11789	1-Percent	13600	605.5	618.6	614.75	620.34	0.003946	10.61	1302.12	123.36	0.55	1
Existing (USGS)	11789	0.2-Percent	18000	605.5	619.92	616.38	622.34	0.004801	12.56	1464.05	152.39	0.61	1
Existing (USGS)													
Existing (USGS)	11675	10-Percent	7990	602.4	616.13		616.7	0.00209	6.08	1336.4	130.41	0.32	1
Existing (USGS)	11675	2-Percent	11800	602.4	617.87		618.79	0.002689	7.72	1568.75	139.63	0.38	1
Existing (USGS)	11675	1-Percent	13600	602.4	618.53		619.63	0.002983	8.46	1663.55	150.46	0.41	1
Existing (USGS)	11675	0.2-Percent	18000	602.4	619.87		621.43	0.00367	10.1	1939.26	305.89	0.46	1
Existing (USGS)													
Existing (USGS)	10302	10-Percent	7990	603.2	612.44		612.99	0.003619	6.22	1615.4	503.61	0.39	1
Existing (USGS)	10302	2-Percent	11800	603.2	613.64		614.32	0.00389	7.2	2290.98	591.22	0.42	1
Existing (USGS)	10302	1-Percent	13600	603.2	614.12		614.84	0.003933	7.54	2576.22	602.16	0.43	1
Existing (USGS)	10302	0.2-Percent	18000	603.2	615.17		615.96	0.003974	8.21	3219.06	623.64	0.44	1
Existing (USGS)													
Existing (USGS)	9372	10-Percent	7990	599.6	610.4		610.7	0.001695	4.73	2076.35	599.75	0.28	1
Existing (USGS)	9372	2-Percent	11800	599.6	611.63		611.96	0.001656	5.16	2828.95	618.25	0.28	1
Existing (USGS)	9372	1-Percent	13600	599.6	612.14		612.48	0.001632	5.32	3146.92	648.19	0.29	1
Existing (USGS)	9372	0.2-Percent	18000	599.6	613.36		613.71	0.001479	5.5	4087.26	990.94	0.28	1
Existing (USGS)													
Existing (USGS)	8312	10-Percent	7990	595.5	609.08		609.11	0.001203	1.43	5192.09	820.27	0.11	7.16
Existing (USGS)	8312	2-Percent	11800	595.5	609.68		609.76	0.00249	1.52	5270.84	822.62	0.13	9.33
Existing (USGS)	8312	1-Percent	13600	595.5	610.07		610.17	0.002832	1.6	5516.96	825.11	0.13	9.74
Existing (USGS)	8312	0.2-Percent	18000	595.5	611.43		611.55	0.00275	1.9	6627.03	841.13	0.14	9.86
Existing (USGS)													
Existing (USGS)	8145	10-Percent	7990	592.1	608.36	603.2	608.7	0.005775	4.73	1688.64	474.57	0.28	6.61
Existing (USGS)	8145	2-Percent	11800	592.1	608.93	601.35	609.32	0.002437	5	2358.85	487.24	0.25	3.34
Existing (USGS)	8145	1-Percent	13600	592.1	609.43	600.44	609.82	0.001396	5	2718.18	496.68	0.23	1.8
Existing (USGS)	8145	0.2-Percent	18000	592.1	610.72	600.82	611.24	0.001013	5.81	3098.54	517.14	0.25	1
Existing (USGS)													
Existing (USGS)	8049 Railroad Bridge		Bridge										
Existing (USGS)													
Existing (USGS)	7984	10-Percent	7990	592.1	608.09	602.72	608.45	0.003505	4.76	1668.88	565.98	0.27	3.41
Existing (USGS)	7984	2-Percent	11800	592.1	608.6	601.79	609.09	0.001524	5.67	2124.03	575.93	0.28	1
Existing (USGS)	7984	1-Percent	13600	592.1	608.97	602.36	609.58	0.001812	6.33	2193.91	587.73	0.31	1
Existing (USGS)	7984	0.2-Percent	18000	592.1	609.77	603.63	610.7	0.002532	7.84	2343.58	612.51	0.38	1
Existing (USGS)													
Existing (USGS)	7758	10-Percent	7990	595	607.29	604.56	607.4	0.001503	2.43	3151.86	1042.19	0.16	4.21
Existing (USGS)	7758	2-Percent	11800	595	608.11	606.02	608.25	0.001647	2.57	4080.68	1311.48	0.16	4.68
Existing (USGS)	7758	1-Percent	13600	595	608.45	606.47	608.61	0.001729	2.46	4449.71	1313.49	0.16	5.33
Existing (USGS)	7758	0.2-Percent	18000	595	609.25	606.94	609.45	0.001766	2.13	5304.77	1317.17	0.14	6.88

Table 3: Existing Conditions with Ice Cover HEC-RAS Output (*continued*)

Alternative	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.ChnL	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chn
<b>Existing (USGS)</b>													
Existing (USGS)	7564	10-Percent	7990	594.9	606.76		606.85	0.001143	2.4	3367.91	1168.24	0.15	3.31
Existing (USGS)	7564	2-Percent	11800	594.9	607.5		607.62	0.001353	2.73	4339.14	1547.68	0.16	3.49
Existing (USGS)	7564	1-Percent	13600	594.9	607.82		607.95	0.001408	2.78	4833.98	1647.91	0.16	3.68
Existing (USGS)	7564	0.2-Percent	18000	594.9	608.6		608.75	0.001548	2.93	6125.76	1771.17	0.17	4.08
<b>Existing (USGS)</b>													
Existing (USGS)	7340	10-Percent	7990	594.8	606.37		606.44	0.00084	2.18	3872.59	1378.63	0.13	2.81
Existing (USGS)	7340	2-Percent	11800	594.8	606.99		607.1	0.001165	2.46	4726.07	1658.94	0.15	3.37
Existing (USGS)	7340	1-Percent	13600	594.8	607.29		607.41	0.001209	2.55	5240.23	1779.13	0.15	3.45
Existing (USGS)	7340	0.2-Percent	18000	594.8	608.04		608.17	0.001253	2.72	6618.15	1923.75	0.16	3.57
<b>Existing (USGS)</b>													
Existing (USGS)	7151	10-Percent	7990	594.7	605.91		605.99	0.001248	2.58	4216.79	1990.49	0.16	2.63
Existing (USGS)	7151	2-Percent	11800	594.7	606.26		606.38	0.002331	3.01	4752	2084.89	0.2	3.64
Existing (USGS)	7151	1-Percent	13600	594.7	606.58		606.7	0.00215	2.99	5430.85	2165.23	0.19	3.67
Existing (USGS)	7151	0.2-Percent	18000	594.7	607.42		607.53	0.001579	2.84	7393.13	2447.29	0.17	3.57
<b>Existing (USGS)</b>													
Existing (USGS)	6890	10-Percent	7990	593	605.67	601.18	605.69	3e-04	1.37	9717.73	2352.62	0.08	2.48
Existing (USGS)	6890	2-Percent	11800	593	605.65	603.07	605.69	0.000798	1.76	9453.58	2351.76	0.11	3.74
Existing (USGS)	6890	1-Percent	13600	593	605.97	603.28	606.02	0.000833	1.86	10207.46	2360.12	0.12	3.74
Existing (USGS)	6890	0.2-Percent	18000	593	606.9	603.77	606.96	0.000775	2.01	12429.71	2396.93	0.12	3.65
<b>Existing (USGS)</b>													
Existing (USGS)	6631	10-Percent	7990	592	605.24	600.87	605.35	0.001491	2.69	3107.72	1027.15	0.17	3.3
Existing (USGS)	6631	2-Percent	11800	592	604.58	599.86	604.98	0.001996	5.28	2450.12	802.67	0.3	1
Existing (USGS)	6631	1-Percent	13600	592	605	600.35	605.33	0.001732	5.09	3291.69	970.71	0.29	1
Existing (USGS)	6631	0.2-Percent	18000	592	605.91	601.44	606.28	0.001805	5.57	4257.36	1130.67	0.3	1
<b>Existing (USGS)</b>													
Existing (USGS)	6324	10-Percent	7990	590.5	604.06	600.32	604.21	0.002372	2.79	2656.13	804.8	0.18	5.09
Existing (USGS)	6324	2-Percent	11800	590.5	603.45	597.78	603.85	0.001671	5.26	2374.01	711.82	0.29	1
Existing (USGS)	6324	1-Percent	13600	590.5	603.63	598.29	604.15	0.002077	5.94	2431.82	752.43	0.32	1
Existing (USGS)	6324	0.2-Percent	18000	590.5	604.87	599.63	605.25	0.001548	5.58	4084.81	1031.09	0.28	1
<b>Existing (USGS)</b>													
Existing (USGS)	6015	10-Percent	7990	588.7	601.96		602.24	0.003183	2.89	2103.56	515.83	0.2	5.12
Existing (USGS)	6015	2-Percent	11800	588.7	602.43		602.73	0.001406	4.91	2894.73	531.08	0.26	1
Existing (USGS)	6015	1-Percent	13600	588.7	602.2		602.63	0.002077	5.87	2776.6	523.59	0.32	1
Existing (USGS)	6015	0.2-Percent	18000	588.7	603.57		604.02	0.001903	6.18	3697.34	910.98	0.32	1
<b>Existing (USGS)</b>													
Existing (USGS)	5607	10-Percent	7990	587.3	600.96	595.62	601.1	0.000911	2.4	2971.39	496.47	0.14	3.41
Existing (USGS)	5607	2-Percent	11800	587.3	600.65	598.6	601.21	0.003502	2.81	2506.7	479.29	0.2	6.35
Existing (USGS)	5607	1-Percent	13600	587.3	601.15	595.56	601.47	0.001272	5.04	3322.28	503.26	0.26	1
Existing (USGS)	5607	0.2-Percent	18000	587.3	602.51	596.64	602.89	0.001323	5.6	4003.05	984.63	0.27	1
<b>Existing (USGS)</b>													
Existing (USGS)	5307	10-Percent	7990	585.8	600.49		600.6	0.000879	2.73	3186.18	520.41	0.15	3.08
Existing (USGS)	5307	2-Percent	11800	585.8	599.85		600.13	0.001081	4.74	3146.45	492.62	0.24	1
Existing (USGS)	5307	1-Percent	13600	585.8	600.49		600.8	0.001126	5.04	3469.36	520.42	0.25	1

Table 3: Existing Conditions with Ice Cover HEC-RAS Output (*continued*)

Alternative	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.ChnL	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chn
Existing (USGS)	5307	0.2-Percent	18000	585.8	601.81		602.19	0.001196	5.61	4440.32	1113.23	0.26	1
Existing (USGS)													
Existing (USGS)	5051	10-Percent	7990	584.3	599.87		599.99	0.001564	3.07	2941.04	875.7	0.17	4.04
Existing (USGS)	5051	2-Percent	11800	584.3	599.21		599.54	0.001187	4.87	2949.37	664.88	0.25	1
Existing (USGS)	5051	1-Percent	13600	584.3	599.85		600.2	0.001188	5.08	3421.11	871.99	0.25	1
Existing (USGS)	5051	0.2-Percent	18000	584.3	601.21		601.57	0.00116	5.44	4655.16	935.59	0.26	1
Existing (USGS)													
Existing (USGS)	4786	10-Percent	7990	582.8	599.09		599.21	0.001798	3.13	3054.96	862.71	0.18	4.95
Existing (USGS)	4786	2-Percent	11800	582.8	598.68		599.01	0.001074	5	3254.57	817.09	0.24	1
Existing (USGS)	4786	1-Percent	13600	582.8	599.33		599.67	0.001075	5.19	3806.42	913.65	0.25	1
Existing (USGS)	4786	0.2-Percent	18000	582.8	600.7		601.05	0.001048	5.52	5198.04	1042.57	0.25	1
Existing (USGS)													
Existing (USGS)	4582	10-Percent	7990	582.7	597.9		598.1	0.004116	4.02	2405.02	756.17	0.24	5.43
Existing (USGS)	4582	2-Percent	11800	582.7	598.14		598.51	0.001268	5.31	3182.46	816.12	0.26	1
Existing (USGS)	4582	1-Percent	13600	582.7	598.78		599.17	0.001283	5.55	3751.02	977.5	0.27	1
Existing (USGS)	4582	0.2-Percent	18000	582.7	600.15		600.56	0.001277	5.97	5198.41	1093.14	0.27	1
Existing (USGS)													
Existing (USGS)	4363	10-Percent	7990	582.5	596.49	590.49	596.83	0.002476	4.75	1789.66	743.49	0.26	2.35
Existing (USGS)	4363	2-Percent	11800	582.5	597.48	590.61	597.95	0.001487	5.72	2365.98	945.93	0.28	1
Existing (USGS)	4363	1-Percent	13600	582.5	598.28	591.23	598.66	0.001235	5.46	4086.34	1174.62	0.26	1
Existing (USGS)	4363	0.2-Percent	18000	582.5	599.68	592.56	600.06	0.001167	5.73	5786.89	1242.01	0.26	1
Existing (USGS)													
Existing (USGS)	4182	10-Percent	7990	582.4	596.04	590.03	596.39	0.002336	4.85	1726.04	461.85	0.27	1.93
Existing (USGS)	4182	2-Percent	11800	582.4	597.14	590.55	597.66	0.001656	5.93	2176.92	640.15	0.3	1
Existing (USGS)	4182	1-Percent	13600	582.4	597.78	591.12	598.37	0.001766	6.37	2369.17	894.76	0.31	1
Existing (USGS)	4182	0.2-Percent	18000	582.4	599.29	592.48	599.8	0.001504	6.4	4712.29	1187.29	0.3	1
Existing (USGS)													
Existing (USGS)	3997	10-Percent	7990	582.3	595.56	589.65	595.93	0.002589	4.95	1664.62	282.92	0.27	2.07
Existing (USGS)	3997	2-Percent	11800	582.3	596.82	590.02	597.36	0.001639	5.95	2153.86	525.73	0.3	1
Existing (USGS)	3997	1-Percent	13600	582.3	597.41	590.59	598.04	0.001816	6.49	2325.71	799.24	0.32	1
Existing (USGS)	3997	0.2-Percent	18000	582.3	598.75	591.89	599.47	0.001923	7.2	3967.34	1358.02	0.33	1
Existing (USGS)													
Existing (USGS)	3670	10-Percent	7990	582.1	595.26		595.31	0.001186	2.49	5655.58	1244.31	0.15	3.87
Existing (USGS)	3670	2-Percent	11800	582.1	596.76		596.82	0.001013	2.8	7649.98	1351.92	0.15	3.45
Existing (USGS)	3670	1-Percent	13600	582.1	597.39		597.46	0.001005	2.87	8504.31	1395.99	0.15	3.56
Existing (USGS)	3670	0.2-Percent	18000	582.1	598.79		598.86	0.000986	3	10644.42	1779.16	0.15	3.89
Existing (USGS)													
Existing (USGS)	2921	10-Percent	7990	576.6	593.85		594.11	0.002187	4.44	2559.96	955.18	0.23	3.09
Existing (USGS)	2921	2-Percent	11800	576.6	595.76		595.96	0.001287	4.2	5111.49	1428.92	0.2	2.55
Existing (USGS)	2921	1-Percent	13600	576.6	596.51		596.67	0.001055	4.08	6201.24	1444.71	0.19	2.39
Existing (USGS)	2921	0.2-Percent	18000	576.6	598.06		598.19	0.000785	3.94	8928.85	2136.62	0.17	2.19
Existing (USGS)													
Existing (USGS)	1922	10-Percent	7990	573.7	593.54		593.58	0.000197	2.08	8257.55	1344.43	0.09	1.46
Existing (USGS)	1922	2-Percent	11800	573.7	595.49		595.52	0.000184	2.27	10949.93	1463.03	0.1	1.38

Table 3: Existing Conditions with Ice Cover HEC-RAS Output (*continued*)

Alternative	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chn
Existing (USGS)	1922	1-Percent	13600	573.7	596.23		596.27	0.000186	2.36	12141.66	1693.19	0.1	1.39
Existing (USGS)	1922	0.2-Percent	18000	573.7	597.78		597.82	0.000192	2.53	14988.84	1884.17	0.1	1.42
Existing (USGS)													
Existing (USGS)	833	10-Percent	7990	571.5	593.39		593.42	0.000106	2.01	7051.55	1516.47	0.08	1
Existing (USGS)	833	2-Percent	11800	571.5	595.34		595.38	9.9e-05	2.1	10374.31	1805.97	0.08	1
Existing (USGS)	833	1-Percent	13600	571.5	596.09		596.12	9.8e-05	2.14	11779.88	2068.75	0.08	1
Existing (USGS)	833	0.2-Percent	18000	571.5	597.64		597.68	9.6e-05	2.24	15564.63	2543.58	0.08	1
Existing (USGS)													
Existing (USGS)	279	10-Percent	7990	571	593.27	581.03	593.33	0.00012	2.35	5948.74	1083.92	0.1	1
Existing (USGS)	279	2-Percent	11800	571	595.23	582.78	595.29	0.00012	2.53	8758.64	2173.18	0.1	1
Existing (USGS)	279	1-Percent	13600	571	595.98	583.49	596.04	0.00012	2.6	10421.48	2286.34	0.1	1
Existing (USGS)	279	0.2-Percent	18000	571	597.53	585.08	597.59	0.00012	2.73	14338.36	2771.69	0.11	1

Table 4: Existing Conditions with Ice Cover using FEMA FIS Discharges HEC-RAS Output

Alternative	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.ChnL	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chan
Existing (FIS)	20483	1-Percent	16000	621.4	634.49		635.94	0.002028	10	1901.93	297.38	0.51	
Existing (FIS)	19313	1-Percent	16000	620.4	631.58		633.1	0.002927	10.61	2198.46	494.92	0.59	
Existing (FIS)	18244	1-Percent	16000	617.6	629.9		630.66	0.001542	8.21	3428.18	571.71	0.44	
Existing (FIS)	17053	1-Percent	16000	615.5	627.52		628.57	0.001957	9.25	3256.19	541.6	0.49	
Existing (FIS)	15751	1-Percent	16000	612.8	624.79		625.9	0.002135	9.33	2433.06	372.55	0.51	
Existing (FIS)	14403	1-Percent	16000	610.3	623.8		624.13	0.000711	5.88	4953.69	705.18	0.3	
Existing (FIS)	12986	1-Percent	16000	608.9	623		623.3	0.000481	5.29	6779.51	970.77	0.25	
Existing (FIS)	12162	1-Percent	16000	604.9	621.46		622.61	0.001242	9.1	2782.93	571.07	0.41	
Existing (FIS)	11955	1-Percent	16000	605.5	620.8	614.93	622.29	0.001584	9.85	1661.09	215.55	0.46	
Existing (FIS)	11860 Union Rd	Bridge											
Existing (FIS)	11789	1-Percent	16000	605.5	619.37	615.64	621.47	0.004393	11.68	1396.84	140.42	0.58	1
Existing (FIS)	11675	1-Percent	16000	602.4	619.31		620.66	0.003364	9.38	1790.47	193.39	0.44	1
Existing (FIS)	10302	1-Percent	16000	603.2	614.71		615.48	0.003977	7.94	2935.99	618.47	0.44	1
Existing (FIS)	9372	1-Percent	16000	599.6	612.81		613.16	0.001559	5.45	3611.02	729.62	0.28	1
Existing (FIS)	8312	1-Percent	16000	595.5	610.78		610.9	0.002857	1.75	6085.13	833.8	0.14	9.88
Existing (FIS)	8145	1-Percent	16000	592.1	610.18	600.32	610.62	0.000901	5.34	2996.25	508.2	0.24	1
Existing (FIS)	8049 Railroad Bridge	Bridge											
Existing (FIS)	7984	1-Percent	16000	592.1	609.43	603.07	610.21	0.0022	7.16	2279.6	599.53	0.35	1
Existing (FIS)	7758	1-Percent	16000	595	608.9	606.94	609.08	0.001772	2.27	4921.24	1315.58	0.15	6.23
Existing (FIS)	7564	1-Percent	16000	594.9	608.24		608.38	0.001527	2.89	5511.41	1754.13	0.17	3.93
Existing (FIS)	7340	1-Percent	16000	594.8	607.69		607.81	0.001238	2.63	5946.11	1904.38	0.16	3.54
Existing (FIS)	7151	1-Percent	16000	594.7	607.01		607.13	0.001874	2.93	6404.58	2339.23	0.18	3.66
Existing (FIS)	6890	1-Percent	16000	593	606.43	603.58	606.48	0.000836	1.95	11291.79	2372.51	0.12	3.76
Existing (FIS)	6631	1-Percent	16000	592	605.38	600.95	605.76	0.00191	5.51	3685.66	1041.18	0.3	1
Existing (FIS)	6324	1-Percent	16000	590.5	604.27	598.98	604.67	0.001659	5.55	3549.54	814.74	0.29	1
Existing (FIS)	6015	1-Percent	16000	588.7	602.85		603.32	0.002111	6.2	3138.67	643.99	0.33	1
Existing (FIS)	5607	1-Percent	16000	587.3	601.71	596.17	602.09	0.001405	5.5	3604.36	666.59	0.28	1
Existing (FIS)	5307	1-Percent	16000	585.8	600.95		601.34	0.001308	5.58	3719.89	575.5	0.27	1
Existing (FIS)	5051	1-Percent	16000	584.3	600.21		600.63	0.001402	5.64	3742.07	906.61	0.28	1
Existing (FIS)	4786	1-Percent	16000	582.8	599.55		599.98	0.001351	5.9	4016.13	956.11	0.28	1
Existing (FIS)	4582	1-Percent	16000	582.7	598.78		599.32	0.001772	6.52	3756.82	980.07	0.31	1
Existing (FIS)	4363	1-Percent	16000	582.5	597.59	591.98	598.43	0.002622	7.64	2423.28	1009.84	0.38	1
Existing (FIS)	4182	1-Percent	16000	582.4	596.85	591.89	597.88	0.003377	8.31	2089.51	608.76	0.42	1
Existing (FIS)	3997	1-Percent	16000	582.3	596.04	591.32	597.2	0.003876	8.7	1939.89	349.9	0.45	1
Existing (FIS)	3670	1-Percent	16000	582.1	596.02		596.28	0.001307	5.23	6997.67	1293.39	0.26	1
Existing (FIS)	2921	1-Percent	16000	576.6	593.88		594.83	0.002794	8.14	2854.84	965.01	0.39	1
Existing (FIS)	1922	1-Percent	16000	573.7	592.99		593.2	0.00085	5	7555.7	1340.37	0.23	1
Existing (FIS)	833	1-Percent	16000	571.5	592.03		592.3	0.000788	5.16	5192.24	1103.55	0.22	1
Existing (FIS)	279	1-Percent	16000	571	590.96	584.37	591.52	0.001201	6.71	3604.61	814.2	0.31	1

## FEMA Effective versus Existing Conditions Models with Ice Cover

### FEMA FIS Peak Discharge for the 1-Percent AEP (100-Year Recurrence) Event




Figure 27: Effective FEMA versus Existing Conditions Profile Plot with Ice Cover (FEMA 1-Percent AEP/100-Year Recurrence Event Peak Discharges)

**USGS StreamStats Peak Discharges for the 10-, 2-, 1-, & 0.2-Percent AEP (10-, 50-, 100-, & 500-Year Recurrence) Events**




Figure 28: Effective FEMA versus Existing Conditions Profile Plot (USGS StreamStats 10-, 2-, 1-, & 0.2-Percent AEP Event Peak Discharges)

## **Flood Scenario #1 with Ice Cover**

### **Flood Bench Configuration: 1a**

Plan: UPDATE-FB-1A-SCHOOL-FULL-ICE

Geometry: UPDATE-FB-1A-SCHOOL-FULL-ICE

Steady Flow Data: USGS BF,10,2,1,0.2-PERCENT-UPDATE-BC

Date: December 2022




Figure 29: Flood Scenario #1 (1a) with Ice Cover Profile Plot

Table 5: Flood Scenario 1 with Ice Cover HEC-RAS Output

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.ChnL	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chan
1 (1a)	20483	10-Percent	7990	621.4	631.44		632.23	0.00152	7.14	1149.93	159.75	0.42	
1 (1a)	20483	2-Percent	11800	621.4	633.13		634.27	0.001801	8.71	1502.7	283.71	0.47	
1 (1a)	20483	1-Percent	13600	621.4	633.75		635.03	0.001907	9.3	1683.2	292.19	0.49	
1 (1a)	20483	0.2-Percent	18000	621.4	635.05		636.62	0.002117	10.53	2068.75	300.59	0.52	
1 (1a)	19313	10-Percent	7990	620.4	628.71		629.8	0.002908	8.44	1044.14	306.61	0.56	
1 (1a)	19313	2-Percent	11800	620.4	630.2		631.56	0.003003	9.73	1584.78	383.6	0.58	
1 (1a)	19313	1-Percent	13600	620.4	630.82		632.26	0.00298	10.15	1839.24	441.9	0.59	
1 (1a)	19313	0.2-Percent	18000	620.4	632.19	630.62	633.75	0.002869	10.92	2526.91	588.68	0.59	
1 (1a)	18244	10-Percent	7990	617.6	626.65		627.29	0.001757	6.95	1777.22	467.86	0.44	
1 (1a)	18244	2-Percent	11800	617.6	628.34		629.05	0.001639	7.65	2591.04	496.46	0.44	
1 (1a)	18244	1-Percent	13600	617.6	629.04		629.77	0.001595	7.91	2943.68	525.83	0.44	
1 (1a)	18244	0.2-Percent	18000	617.6	630.58		631.36	0.001502	8.43	3818.19	582.92	0.43	
1 (1a)	17053	10-Percent	7990	615.5	624.35		625.09	0.001916	7.31	1642.13	449.92	0.46	
1 (1a)	17053	2-Percent	11800	615.5	625.99		626.9	0.001962	8.38	2446.6	516.1	0.48	
1 (1a)	17053	1-Percent	13600	615.5	626.66		627.64	0.001967	8.79	2801.03	526.03	0.49	
1 (1a)	17053	0.2-Percent	18000	615.5	628.2		629.3	0.001934	9.57	3631.51	561.19	0.49	
1 (1a)	15751	10-Percent	7990	612.8	621.5		622.32	0.002353	7.63	1281.07	298.43	0.5	
1 (1a)	15751	2-Percent	11800	612.8	623.1		624.11	0.002331	8.68	1817.77	352.78	0.52	
1 (1a)	15751	1-Percent	13600	612.8	623.84		624.9	0.002251	9	2081.97	364.33	0.51	
1 (1a)	15751	0.2-Percent	18000	612.8	625.57		626.72	0.00203	9.55	2727.68	378.08	0.5	
1 (1a)	14403	10-Percent	7990	610.3	619.62		620	0.001191	5.74	2433.54	541.73	0.36	
1 (1a)	14403	2-Percent	11800	610.3	621.69		622.05	0.000915	5.87	3595.27	583.33	0.33	
1 (1a)	14403	1-Percent	13600	610.3	622.61		622.96	0.000824	5.91	4152.77	637.99	0.32	
1 (1a)	14403	0.2-Percent	18000	610.3	624.76		625.08	0.000625	5.8	5655.52	746.8	0.28	
1 (1a)	12986	10-Percent	7990	608.9	618.23		618.6	0.000827	5.21	2427.97	736.48	0.31	
1 (1a)	12986	2-Percent	11800	608.9	620.65		620.99	0.000619	5.29	4557.71	922.38	0.28	
1 (1a)	12986	1-Percent	13600	608.9	621.69		622.01	0.00055	5.29	5526.43	947.89	0.27	
1 (1a)	12986	0.2-Percent	18000	608.9	624.04		624.33	0.000438	5.31	7810.39	999.57	0.24	
1 (1a)	12162	10-Percent	7990	604.9	617.03		617.77	0.001141	6.98	1207.69	135.15	0.37	
1 (1a)	12162	2-Percent	11800	604.9	619.08		620.18	0.001369	8.56	1649.42	402.74	0.42	
1 (1a)	12162	1-Percent	13600	604.9	620.09		621.25	0.001345	8.91	2098.69	463.53	0.42	
1 (1a)	12162	0.2-Percent	18000	604.9	622.62		623.71	0.001118	9.06	3568.74	729.59	0.39	
1 (1a)	11955	10-Percent	7990	605.5	616.8	611.72	617.53	0.001175	6.85	1177.36	116.61	0.37	
1 (1a)	11955	2-Percent	11800	605.5	618.78	613.35	619.89	0.001432	8.48	1413.64	149.66	0.42	
1 (1a)	11955	1-Percent	13600	605.5	619.66	614.06	620.94	0.00151	9.11	1521.39	162.34	0.44	
1 (1a)	11955	0.2-Percent	18000	605.5	621.71	615.65	623.37	0.001626	10.4	1774.68	330.37	0.47	
1 (1a)	11860 Union Rd	Bridge											
1 (1a)	11789	10-Percent	7990	605.5	616.22	612.39	617.18	0.002925	7.85	1022.6	112.37	0.45	1
1 (1a)	11789	2-Percent	11800	605.5	617.95	614.02	619.43	0.003606	9.76	1223	119.72	0.52	1
1 (1a)	11789	1-Percent	13600	605.5	618.6	614.75	620.34	0.003946	10.61	1302.12	123.36	0.55	1
1 (1a)	11789	0.2-Percent	18000	605.5	619.92	616.38	622.34	0.004801	12.56	1464.02	152.38	0.61	1
1 (1a)	11675	10-Percent	7990	602.4	616.13		616.7	0.00209	6.08	1336.39	130.41	0.32	1
1 (1a)	11675	2-Percent	11800	602.4	617.87		618.79	0.002689	7.72	1568.74	139.63	0.38	1
1 (1a)	11675	1-Percent	13600	602.4	618.53		619.63	0.002983	8.46	1663.55	150.46	0.41	1

Table 5: Flood Scenario 1 with Ice Cover HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.ChnL	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chn
1 (1a)	11675	0.2-Percent	18000	602.4	619.87		621.43	0.003671	10.1	1939.18	305.88	0.46	1
1 (1a)	10302	10-Percent	7990	603.2	612.44		612.99	0.003619	6.22	1615.4	503.61	0.39	1
1 (1a)	10302	2-Percent	11800	603.2	613.64		614.32	0.00389	7.2	2290.98	591.22	0.42	1
1 (1a)	10302	1-Percent	13600	603.2	614.12		614.84	0.003933	7.54	2576.29	602.16	0.43	1
1 (1a)	10302	0.2-Percent	18000	603.2	615.17		615.96	0.003973	8.21	3219.4	623.65	0.44	1
1 (1a)	9372	10-Percent	7990	599.6	610.4		610.7	0.001695	4.73	2076.24	599.75	0.28	1
1 (1a)	9372	2-Percent	11800	599.6	611.63		611.96	0.001657	5.17	2827.97	618.23	0.28	1
1 (1a)	9372	1-Percent	13600	599.6	612.14		612.48	0.001631	5.32	3148.03	648.35	0.28	1
1 (1a)	9372	0.2-Percent	18000	599.6	613.36		613.71	0.001475	5.5	4091.56	991.09	0.28	1
1 (1a)	8312	10-Percent	7990	595.5	609.08		609.11	0.001203	1.43	5191.98	820.26	0.11	7.16
1 (1a)	8312	2-Percent	11800	595.5	609.67		609.76	0.002491	1.52	5270.62	822.67	0.13	9.32
1 (1a)	8312	1-Percent	13600	595.5	610.07		610.17	0.002836	1.59	5513.58	824.93	0.13	9.77
1 (1a)	8312	0.2-Percent	18000	595.5	611.43		611.55	0.002761	1.88	6617.42	841.15	0.14	9.92
1 (1a)	8145	10-Percent	7990	592.1	608.36	603.21	608.7	0.005806	4.74	1686.64	474.53	0.28	6.62
1 (1a)	8145	2-Percent	11800	592.1	608.92	601.34	609.31	0.002435	5	2359.04	487.19	0.25	3.33
1 (1a)	8145	1-Percent	13600	592.1	609.43	600.44	609.82	0.001396	5	2718.14	496.7	0.23	1.8
1 (1a)	8145	0.2-Percent	18000	592.1	610.72	600.82	611.25	0.001012	5.81	3099.17	517.2	0.25	1
1 (1a)	8049 Railroad Bridge	Bridge											
1 (1a)	7984	10-Percent	7990	592.1	608.09	602.72	608.45	0.003491	4.76	1670.04	565.97	0.27	3.4
1 (1a)	7984	2-Percent	11800	592.1	608.6	601.79	609.09	0.001526	5.67	2123.44	575.77	0.29	1
1 (1a)	7984	1-Percent	13600	592.1	608.97	602.36	609.58	0.001812	6.33	2194.2	587.78	0.31	1
1 (1a)	7984	0.2-Percent	18000	592.1	609.77	603.63	610.7	0.002529	7.84	2344.22	612.62	0.38	1
1 (1a)	7758	10-Percent	7990	595	607.3	604.76	607.41	0.001484	2.43	3164.24	1045.37	0.15	4.18
1 (1a)	7758	2-Percent	11800	595	608.1	606.03	608.24	0.001654	2.57	4074.85	1311.43	0.16	4.67
1 (1a)	7758	1-Percent	13600	595	608.46	606.5	608.61	0.001729	2.45	4450.16	1313.5	0.16	5.34
1 (1a)	7758	0.2-Percent	18000	595	609.25	606.94	609.45	0.001769	2.12	5300.93	1317.18	0.14	6.93
1 (1a)	7564	10-Percent	7990	594.9	606.78		606.87	0.00112	2.39	3391.44	1179.02	0.15	3.29
1 (1a)	7564	2-Percent	11800	594.9	607.49		607.61	0.001365	2.74	4324.89	1541.53	0.16	3.49
1 (1a)	7564	1-Percent	13600	594.9	607.82		607.95	0.00141	2.77	4833.56	1648.18	0.16	3.7
1 (1a)	7564	0.2-Percent	18000	594.9	608.6		608.75	0.001563	2.91	6113.78	1771.15	0.17	4.16
1 (1a)	7340	10-Percent	7990	594.8	606.39		606.47	0.000831	2.15	3899.34	1384.33	0.13	2.86
1 (1a)	7340	2-Percent	11800	594.8	606.97		607.08	0.00119	2.46	4692.18	1637.05	0.15	3.42
1 (1a)	7340	1-Percent	13600	594.8	607.29		607.41	0.001216	2.54	5231.83	1778.56	0.15	3.47
1 (1a)	7340	0.2-Percent	18000	594.8	608.03		608.16	0.001268	2.71	6596.35	1923.58	0.16	3.62
1 (1a)	7151	10-Percent	7990	594.7	605.93		606.01	0.001282	2.53	4231.03	1996.18	0.16	2.81
1 (1a)	7151	2-Percent	11800	594.7	606.2		606.32	0.002588	3.08	4597.3	2064.92	0.2	3.75
1 (1a)	7151	1-Percent	13600	594.7	606.57		606.68	0.002207	2.99	5390.48	2161.04	0.19	3.72
1 (1a)	7151	0.2-Percent	18000	594.7	607.4		607.51	0.001621	2.85	7335.18	2443.98	0.17	3.62
1 (1a)	6890	10-Percent	7990	593	605.68	601.94	605.7	0.000318	1.31	9670.79	2352.79	0.08	2.86
1 (1a)	6890	2-Percent	11800	593	605.49	603.12	605.53	0.000935	1.79	9037.37	2344.41	0.12	3.97
1 (1a)	6890	1-Percent	13600	593	605.93	603.3	605.98	0.000864	1.86	10108.82	2359.18	0.12	3.82
1 (1a)	6890	0.2-Percent	18000	593	606.86	603.79	606.92	0.000799	2	12329.98	2395.32	0.12	3.73
1 (1a)	6631	10-Percent	7990	592	604.94	602.01	605.22	0.004577	3.73	1975.18	946.65	0.25	4.38
1 (1a)	6631	2-Percent	11800	592	604.25	599.87	604.7	0.002343	5.57	2312.78	657.67	0.33	1

Table 5: Flood Scenario 1 with Ice Cover HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.ChnL	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chn
1 (1a)	6631	1-Percent	13600	592	604.92	600.36	605.27	0.001812	5.18	3219.05	938.7	0.29	1
1 (1a)	6631	0.2-Percent	18000	592	605.83	601.44	606.22	0.001889	5.67	4171.85	1116.12	0.31	1
1 (1a)	6324	10-Percent	7990	590.5	602.42	598.12	602.73	0.003587	4.46	1796.58	492	0.28	2.63
1 (1a)	6324	2-Percent	11800	590.5	602.88	597.78	603.35	0.002062	5.59	2213.36	532.06	0.31	1
1 (1a)	6324	1-Percent	13600	590.5	603.5	598.29	604.03	0.002177	6.02	2389.41	723.31	0.33	1
1 (1a)	6324	0.2-Percent	18000	590.5	604.72	599.64	605.13	0.001662	5.73	3934.37	979.56	0.29	1
1 (1a)	6015	10-Percent	7990	588.7	601.01		601.24	0.00132	4.26	2171.65	467.9	0.25	1
1 (1a)	6015	2-Percent	11800	588.7	601.22		601.7	0.002573	6.05	2275.25	491.95	0.35	1
1 (1a)	6015	1-Percent	13600	588.7	601.89		602.37	0.002421	6.19	2612.47	513.95	0.34	1
1 (1a)	6015	0.2-Percent	18000	588.7	603.22		603.74	0.002248	6.57	3402.81	795.29	0.34	1
1 (1a)	5607	10-Percent	7990	587.3	598.66	597.83	599.49	0.005615	2.29	1548.16	441.17	0.2	6.87
1 (1a)	5607	2-Percent	11800	587.3	599.88	595.1	600.25	0.001608	5.19	2720.13	460.14	0.28	1
1 (1a)	5607	1-Percent	13600	587.3	600.58	595.55	600.96	0.001601	5.45	3046.11	476.72	0.29	1
1 (1a)	5607	0.2-Percent	18000	587.3	601.92	596.63	602.37	0.00164	6.02	3709.47	774.75	0.3	1
1 (1a)	5307	10-Percent	7990	585.8	597.72		597.89	0.001422	2.51	2522.48	401.34	0.16	3.52
1 (1a)	5307	2-Percent	11800	585.8	598.63		599.07	0.00285	2.58	2566.03	409.54	0.18	5.93
1 (1a)	5307	1-Percent	13600	585.8	599.28		599.76	0.003054	2.73	2798.15	477.99	0.19	6.3
1 (1a)	5307	0.2-Percent	18000	585.8	600.6		601.17	0.002928	2.91	3396.95	524.24	0.19	6.75
1 (1a)	5051	10-Percent	7990	584.3	597.54		597.58	0.000273	1.37	4987.22	795.07	0.08	2.43
1 (1a)	5051	2-Percent	11800	584.3	598.42		598.5	0.000431	1.64	5641.29	949.13	0.1	3.16
1 (1a)	5051	1-Percent	13600	584.3	599.08		599.16	0.000429	1.69	6286.04	1058.39	0.1	3.3
1 (1a)	5051	0.2-Percent	18000	584.3	600.47		600.56	0.00042	1.83	7956.9	1336.32	0.1	3.45
1 (1a)	4786	10-Percent	7990	582.8	597.39		597.44	0.000292	1.82	4582.67	908.59	0.1	1.85
1 (1a)	4786	2-Percent	11800	582.8	598.19		598.28	0.000477	2.27	5317.83	1056.07	0.12	2.29
1 (1a)	4786	1-Percent	13600	582.8	598.85		598.95	0.000475	2.35	6034.06	1127.44	0.12	2.35
1 (1a)	4786	0.2-Percent	18000	582.8	600.24		600.35	0.000474	2.51	7764.63	1342.16	0.12	2.47
1 (1a)	4582	10-Percent	7990	582.7	597.24		597.31	0.000369	2.06	4326.1	908.6	0.11	1.83
1 (1a)	4582	2-Percent	11800	582.7	597.93		598.05	0.000655	2.58	4911.52	1009.02	0.14	2.41
1 (1a)	4582	1-Percent	13600	582.7	598.59		598.71	0.000645	2.68	5626.67	1169.49	0.14	2.43
1 (1a)	4582	0.2-Percent	18000	582.7	599.98		600.12	0.000634	2.85	7387.22	1327.85	0.14	2.54
1 (1a)	4363	10-Percent	7990	582.5	597.05	590.38	597.14	0.000477	2.18	3473.07	976.02	0.12	2.35
1 (1a)	4363	2-Percent	11800	582.5	597.55	591.27	597.73	0.000957	2.91	3675.13	1102.28	0.16	2.89
1 (1a)	4363	1-Percent	13600	582.5	598.26	591.59	598.42	0.000829	2.86	5430.26	1289.11	0.15	2.87
1 (1a)	4363	0.2-Percent	18000	582.5	599.66	592.37	599.83	0.000798	3.05	7284.34	1360.15	0.15	2.95
1 (1a)	4182	10-Percent	7990	582.4	596.7	591.19	596.96	0.002139	3.69	2052.17	578.38	0.21	3.51
1 (1a)	4182	2-Percent	11800	582.4	597.14	590.7	597.51	0.001231	5.11	2531.34	640.03	0.26	1
1 (1a)	4182	1-Percent	13600	582.4	597.78	591.21	598.2	0.001323	5.51	2723.25	892.79	0.27	1
1 (1a)	4182	0.2-Percent	18000	582.4	599.22	592.34	599.63	0.001222	5.75	4982.25	1185.14	0.27	1
1 (1a)	3997	10-Percent	7990	582.3	595.86	591.92	596.33	0.00564	4.63	1564.92	296.35	0.29	4.89
1 (1a)	3997	2-Percent	11800	582.3	596.86	590.18	597.27	0.001315	5.34	2383.62	532.71	0.27	1
1 (1a)	3997	1-Percent	13600	582.3	597.46	590.73	597.94	0.001442	5.8	2561.25	820.39	0.28	1
1 (1a)	3997	0.2-Percent	18000	582.3	598.81	591.92	599.37	0.001524	6.43	4259.37	1365.06	0.3	1
1 (1a)	3670	10-Percent	7990	582.1	595.4		595.44	0.001359	2.24	5675.78	1248.96	0.14	5.03
1 (1a)	3670	2-Percent	11800	582.1	596.75		596.81	0.00098	2.84	7666.43	1351.62	0.15	3.25

Table 5: Flood Scenario 1 with Ice Cover HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chn
1 (1a)	3670	1-Percent	13600	582.1	597.39		597.45	0.000975	2.92	8524.13	1395.21	0.15	3.36
1 (1a)	3670	0.2-Percent	18000	582.1	598.78		598.85	0.00095	3.07	10670.6	1774.67	0.15	3.58
1 (1a)	2921	10-Percent	7990	576.6	593.86		594.12	0.002287	4.45	2554.79	958.12	0.23	3.22
1 (1a)	2921	2-Percent	11800	576.6	595.77		595.96	0.001317	4.2	5103.35	1428.94	0.2	2.64
1 (1a)	2921	1-Percent	13600	576.6	596.51		596.67	0.001081	4.07	6192.14	1444.75	0.19	2.48
1 (1a)	2921	0.2-Percent	18000	576.6	598.06		598.19	0.000802	3.92	8918.56	2137.19	0.17	2.3
1 (1a)	1922	10-Percent	7990	573.7	593.55		593.58	0.0002	2.07	8255.7	1344.44	0.09	1.5
1 (1a)	1922	2-Percent	11800	573.7	595.49		595.52	0.000183	2.28	10950.95	1462.94	0.1	1.36
1 (1a)	1922	1-Percent	13600	573.7	596.23		596.27	0.000185	2.37	12142.89	1692.99	0.1	1.37
1 (1a)	1922	0.2-Percent	18000	573.7	597.78		597.82	0.00019	2.55	14991.2	1884.16	0.1	1.38
1 (1a)	833	10-Percent	7990	571.5	593.39		593.42	0.000106	2.01	7051.55	1516.47	0.08	1
1 (1a)	833	2-Percent	11800	571.5	595.34		595.38	0.000099	2.1	10374.31	1805.97	0.08	1
1 (1a)	833	1-Percent	13600	571.5	596.09		596.12	0.000098	2.14	11779.88	2068.75	0.08	1
1 (1a)	833	0.2-Percent	18000	571.5	597.64		597.68	0.000096	2.24	15564.63	2543.58	0.08	1
1 (1a)	279	10-Percent	7990	571	593.27	581.03	593.33	0.00012	2.35	5948.74	1083.92	0.1	1
1 (1a)	279	2-Percent	11800	571	595.23	582.78	595.29	0.00012	2.53	8758.64	2173.18	0.1	1
1 (1a)	279	1-Percent	13600	571	595.98	583.49	596.04	0.00012	2.6	10421.48	2286.34	0.1	1
1 (1a)	279	0.2-Percent	18000	571	597.53	585.08	597.59	0.00012	2.73	14338.36	2771.69	0.11	1

## **Flood Scenario #2 with Ice Cover**

### **Flood Bench Configuration: 1b**

Plan: UPDATE-FB-1B-SCHOOL-OPEN-ICE

Geometry: UPDATE-FB-1B-SCHOOL-OPEN-ICE

Steady Flow Data: USGS BF,10,2,1,0.2-PERCENT-UPDATE-BC

Date: December 2022




Figure 30: Flood Scenario #2 (1b) with Ice Cover Profile Plot

Table 6: Flood Scenario 2 with Ice Cover HEC-RAS Output

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.ChnL	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chn
2 (1b)	20483	10-Percent	7990	621.4	631.44		632.23	0.00152	7.14	1149.93	159.75	0.42	
2 (1b)	20483	2-Percent	11800	621.4	633.13		634.27	0.001801	8.71	1502.7	283.71	0.47	
2 (1b)	20483	1-Percent	13600	621.4	633.75		635.03	0.001907	9.3	1683.2	292.19	0.49	
2 (1b)	20483	0.2-Percent	18000	621.4	635.05		636.62	0.002117	10.53	2068.75	300.59	0.52	
2 (1b)	19313	10-Percent	7990	620.4	628.71		629.8	0.002908	8.44	1044.14	306.61	0.56	
2 (1b)	19313	2-Percent	11800	620.4	630.2		631.56	0.003003	9.73	1584.78	383.6	0.58	
2 (1b)	19313	1-Percent	13600	620.4	630.82		632.26	0.00298	10.15	1839.24	441.9	0.59	
2 (1b)	19313	0.2-Percent	18000	620.4	632.19	630.62	633.75	0.002869	10.92	2526.91	588.68	0.59	
2 (1b)	18244	10-Percent	7990	617.6	626.65		627.29	0.001757	6.95	1777.22	467.86	0.44	
2 (1b)	18244	2-Percent	11800	617.6	628.34		629.05	0.001639	7.65	2591.04	496.46	0.44	
2 (1b)	18244	1-Percent	13600	617.6	629.04		629.77	0.001595	7.91	2943.68	525.83	0.44	
2 (1b)	18244	0.2-Percent	18000	617.6	630.58		631.36	0.001502	8.43	3818.19	582.92	0.43	
2 (1b)	17053	10-Percent	7990	615.5	624.35		625.09	0.001916	7.31	1642.13	449.92	0.46	
2 (1b)	17053	2-Percent	11800	615.5	625.99		626.9	0.001962	8.38	2446.6	516.1	0.48	
2 (1b)	17053	1-Percent	13600	615.5	626.66		627.64	0.001967	8.79	2801.03	526.03	0.49	
2 (1b)	17053	0.2-Percent	18000	615.5	628.2		629.3	0.001934	9.57	3631.51	561.19	0.49	
2 (1b)	15751	10-Percent	7990	612.8	621.5		622.32	0.002353	7.63	1281.07	298.43	0.5	
2 (1b)	15751	2-Percent	11800	612.8	623.1		624.11	0.002331	8.68	1817.77	352.78	0.52	
2 (1b)	15751	1-Percent	13600	612.8	623.84		624.9	0.002251	9	2081.97	364.33	0.51	
2 (1b)	15751	0.2-Percent	18000	612.8	625.57		626.72	0.00203	9.55	2727.68	378.08	0.5	
2 (1b)	14403	10-Percent	7990	610.3	619.62		620	0.001191	5.74	2433.58	541.73	0.36	
2 (1b)	14403	2-Percent	11800	610.3	621.69		622.05	0.000915	5.87	3595.27	583.33	0.33	
2 (1b)	14403	1-Percent	13600	610.3	622.61		622.96	0.000824	5.91	4152.74	637.99	0.32	
2 (1b)	14403	0.2-Percent	18000	610.3	624.76		625.08	0.000625	5.8	5655.52	746.8	0.28	
2 (1b)	12986	10-Percent	7990	608.9	618.23		618.6	0.000826	5.21	2428.01	736.5	0.31	
2 (1b)	12986	2-Percent	11800	608.9	620.65		620.99	0.000619	5.29	4557.71	922.38	0.28	
2 (1b)	12986	1-Percent	13600	608.9	621.69		622.01	0.00055	5.29	5526.38	947.89	0.27	
2 (1b)	12986	0.2-Percent	18000	608.9	624.04		624.33	0.000438	5.31	7810.45	999.57	0.24	
2 (1b)	12162	10-Percent	7990	604.9	617.03		617.77	0.001141	6.98	1207.69	135.15	0.37	
2 (1b)	12162	2-Percent	11800	604.9	619.08		620.18	0.001369	8.56	1649.42	402.74	0.42	
2 (1b)	12162	1-Percent	13600	604.9	620.09		621.25	0.001345	8.91	2098.66	463.53	0.42	
2 (1b)	12162	0.2-Percent	18000	604.9	622.62		623.71	0.001118	9.06	3568.83	729.62	0.39	
2 (1b)	11955	10-Percent	7990	605.5	616.8	611.72	617.53	0.001175	6.85	1177.37	116.61	0.37	
2 (1b)	11955	2-Percent	11800	605.5	618.78	613.35	619.89	0.001432	8.48	1413.64	149.66	0.42	
2 (1b)	11955	1-Percent	13600	605.5	619.66	614.06	620.94	0.00151	9.11	1521.38	162.34	0.44	
2 (1b)	11955	0.2-Percent	18000	605.5	621.71	615.65	623.37	0.001626	10.4	1774.71	330.41	0.47	
2 (1b)	11860 Union Rd	Bridge											
2 (1b)	11789	10-Percent	7990	605.5	616.22	612.39	617.18	0.002925	7.85	1022.61	112.37	0.45	1
2 (1b)	11789	2-Percent	11800	605.5	617.95	614.02	619.43	0.003606	9.76	1223	119.72	0.52	1
2 (1b)	11789	1-Percent	13600	605.5	618.6	614.75	620.34	0.003946	10.61	1302.11	123.36	0.55	1
2 (1b)	11789	0.2-Percent	18000	605.5	619.92	616.38	622.34	0.004801	12.56	1464.05	152.39	0.61	1
2 (1b)	11675	10-Percent	7990	602.4	616.13		616.7	0.00209	6.08	1336.4	130.41	0.32	1
2 (1b)	11675	2-Percent	11800	602.4	617.87		618.79	0.002689	7.72	1568.74	139.63	0.38	1
2 (1b)	11675	1-Percent	13600	602.4	618.53		619.63	0.002983	8.46	1663.54	150.46	0.41	1

Table 6: Flood Scenario 2 with Ice Cover HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.ChnL	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chn
2 (1b)	11675	0.2-Percent	18000	602.4	619.87		621.43	0.00367	10.1	1939.26	305.89	0.46	1
2 (1b)	10302	10-Percent	7990	603.2	612.44		612.99	0.003619	6.22	1615.37	503.61	0.39	1
2 (1b)	10302	2-Percent	11800	603.2	613.64		614.32	0.003889	7.2	2291.05	591.22	0.42	1
2 (1b)	10302	1-Percent	13600	603.2	614.12		614.84	0.003933	7.54	2576.36	602.17	0.43	1
2 (1b)	10302	0.2-Percent	18000	603.2	615.17		615.96	0.003974	8.21	3219.06	623.64	0.44	1
2 (1b)	9372	10-Percent	7990	599.6	610.4		610.7	0.001692	4.73	2077.85	599.78	0.28	1
2 (1b)	9372	2-Percent	11800	599.6	611.64		611.96	0.001654	5.16	2829.82	618.27	0.28	1
2 (1b)	9372	1-Percent	13600	599.6	612.14		612.49	0.001628	5.32	3149.77	648.6	0.28	1
2 (1b)	9372	0.2-Percent	18000	599.6	613.36		613.71	0.001479	5.5	4087.39	990.94	0.28	1
2 (1b)	8312	10-Percent	7990	595.5	609.07		609.11	0.001215	1.42	5178.1	820.18	0.11	7.21
2 (1b)	8312	2-Percent	11800	595.5	609.68		609.76	0.002489	1.51	5270.66	822.56	0.13	9.34
2 (1b)	8312	1-Percent	13600	595.5	610.07		610.17	0.002852	1.58	5500.91	824.41	0.13	9.83
2 (1b)	8312	0.2-Percent	18000	595.5	611.43		611.55	0.002749	1.9	6627.81	841.13	0.14	9.86
2 (1b)	8145	10-Percent	7990	592.1	608.35	603.21	608.7	0.00583	4.74	1684.85	474.34	0.28	6.62
2 (1b)	8145	2-Percent	11800	592.1	608.93	601.34	609.32	0.002438	5	2358.81	487.28	0.25	3.34
2 (1b)	8145	1-Percent	13600	592.1	609.43	600.44	609.82	0.001402	5.01	2716.43	496.66	0.23	1.81
2 (1b)	8145	0.2-Percent	18000	592.1	610.72	600.82	611.24	0.001013	5.81	3098.65	517.15	0.25	1
2 (1b)	8049 Railroad Bridge	Bridge											
2 (1b)	7984	10-Percent	7990	592.1	608.08	602.69	608.44	0.003459	4.75	1672.48	565.92	0.27	3.37
2 (1b)	7984	2-Percent	11800	592.1	608.6	601.79	609.09	0.001523	5.67	2124.48	576.05	0.28	1
2 (1b)	7984	1-Percent	13600	592.1	608.97	602.36	609.58	0.001813	6.33	2193.74	587.7	0.31	1
2 (1b)	7984	0.2-Percent	18000	592.1	609.77	603.63	610.7	0.002531	7.84	2343.68	612.52	0.38	1
2 (1b)	7758	10-Percent	7990	595	607.3	604.56	607.4	0.001482	2.44	3163.7	1044.17	0.15	4.15
2 (1b)	7758	2-Percent	11800	595	608.11	606.04	608.25	0.001646	2.56	4082.39	1311.5	0.16	4.69
2 (1b)	7758	1-Percent	13600	595	608.45	606.49	608.61	0.001733	2.46	4446.68	1313.48	0.16	5.33
2 (1b)	7758	0.2-Percent	18000	595	609.25	606.94	609.45	0.001764	2.13	5306.93	1317.17	0.14	6.88
2 (1b)	7564	10-Percent	7990	594.9	606.77		606.86	0.001121	2.4	3388.76	1176.9	0.15	3.28
2 (1b)	7564	2-Percent	11800	594.9	607.5		607.62	0.001352	2.72	4342.56	1549.9	0.16	3.5
2 (1b)	7564	1-Percent	13600	594.9	607.82		607.95	0.001419	2.78	4821.49	1646.64	0.16	3.7
2 (1b)	7564	0.2-Percent	18000	594.9	608.6		608.75	0.001544	2.93	6131.25	1771.21	0.17	4.08
2 (1b)	7340	10-Percent	7990	594.8	606.39		606.46	0.000825	2.16	3902.93	1384	0.13	2.81
2 (1b)	7340	2-Percent	11800	594.8	607		607.1	0.001162	2.45	4731.71	1660.54	0.15	3.38
2 (1b)	7340	1-Percent	13600	594.8	607.28		607.4	0.001216	2.56	5225.42	1777.19	0.15	3.43
2 (1b)	7340	0.2-Percent	18000	594.8	608.04		608.17	0.001246	2.72	6629.21	1923.87	0.16	3.56
2 (1b)	7151	10-Percent	7990	594.7	605.93		606.01	0.001278	2.53	4233.73	1996.34	0.16	2.8
2 (1b)	7151	2-Percent	11800	594.7	606.27		606.38	0.002312	3	4768.01	2087.24	0.2	3.64
2 (1b)	7151	1-Percent	13600	594.7	606.57		606.69	0.002154	3.02	5413.4	2161.5	0.19	3.61
2 (1b)	7151	0.2-Percent	18000	594.7	607.43		607.54	0.001561	2.84	7421.84	2449.08	0.17	3.56
2 (1b)	6890	10-Percent	7990	593	605.68	601.95	605.7	0.000317	1.31	9674.69	2352.82	0.08	2.85
2 (1b)	6890	2-Percent	11800	593	605.66	603.06	605.7	0.000791	1.75	9483.44	2352.42	0.11	3.75
2 (1b)	6890	1-Percent	13600	593	605.96	603.28	606.01	0.00083	1.89	10195.33	2359.82	0.12	3.65
2 (1b)	6890	0.2-Percent	18000	593	606.92	603.77	606.97	0.000766	2	12473.89	2397.7	0.12	3.63
2 (1b)	6631	10-Percent	7990	592	604.95	601.99	605.22	0.004505	3.72	1983.09	949.47	0.25	4.35
2 (1b)	6631	2-Percent	11800	592	604.6	599.87	604.99	0.001989	5.28	2458.16	807.82	0.3	1

Table 6: Flood Scenario 2 with Ice Cover HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.ChnL	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chn
2 (1b)	6631	1-Percent	13600	592	604.98	600.36	605.32	0.001736	5.11	3279.64	964.92	0.29	1
2 (1b)	6631	0.2-Percent	18000	592	605.94	601.44	606.31	0.001768	5.53	4298.06	1148.95	0.3	1
2 (1b)	6324	10-Percent	7990	590.5	602.44	598.15	602.75	0.003595	4.46	1797.87	493.64	0.28	2.65
2 (1b)	6324	2-Percent	11800	590.5	603.48	597.78	603.88	0.001651	5.24	2383.19	719.39	0.28	1
2 (1b)	6324	1-Percent	13600	590.5	604.07	598.29	604.38	0.001336	4.92	3381.59	804.93	0.26	1
2 (1b)	6324	0.2-Percent	18000	590.5	604.95	599.64	605.32	0.001487	5.5	4162.55	1046.76	0.28	1
2 (1b)	6015	10-Percent	7990	588.7	601.05		601.28	0.001292	4.23	2190.44	470.36	0.24	1
2 (1b)	6015	2-Percent	11800	588.7	602.48		602.77	0.001372	4.87	2922.28	535.55	0.26	1
2 (1b)	6015	1-Percent	13600	588.7	603.1		603.41	0.001361	5.07	3309.32	718.52	0.26	1
2 (1b)	6015	0.2-Percent	18000	588.7	603.73		604.15	0.00176	6.01	3850.02	973.96	0.31	1
2 (1b)	5607	10-Percent	7990	587.3	599.85	596.55	600.15	0.001998	2.49	2292.29	457.67	0.17	4.86
2 (1b)	5607	2-Percent	11800	587.3	600.93	598.47	601.39	0.002903	2.83	2683.27	494.64	0.19	5.96
2 (1b)	5607	1-Percent	13600	587.3	601.59	598.86	602.06	0.002785	2.95	3000.24	583.32	0.19	6.06
2 (1b)	5607	0.2-Percent	18000	587.3	602.75	596.63	603.11	0.001215	5.44	4128.34	1018.68	0.26	1
2 (1b)	5307	10-Percent	7990	585.8	599.42		599.52	0.000625	2.26	3232.65	481.71	0.13	2.69
2 (1b)	5307	2-Percent	11800	585.8	600.09		600.29	0.00127	2.82	3402.04	499.43	0.16	3.85
2 (1b)	5307	1-Percent	13600	585.8	600.74		600.96	0.001302	2.94	3717.96	537.1	0.16	4.01
2 (1b)	5307	0.2-Percent	18000	585.8	602.09		602.33	0.001461	2.96	4735.49	1254.09	0.16	5.14
2 (1b)	5051	10-Percent	7990	584.3	599.05		599.16	0.00074	2.36	3199.87	656.87	0.13	2.93
2 (1b)	5051	2-Percent	11800	584.3	599.12		599.43	0.002139	3.27	3042.16	669.38	0.19	4.21
2 (1b)	5051	1-Percent	13600	584.3	599.8		600.12	0.002037	3.34	3520.07	867.29	0.19	4.32
2 (1b)	5051	0.2-Percent	18000	584.3	601.17		601.49	0.001789	3.51	4794.61	955.02	0.19	4.3
2 (1b)	4786	10-Percent	7990	582.8	598.59		598.73	0.001179	2.96	3091.62	806.87	0.16	3.6
2 (1b)	4786	2-Percent	11800	582.8	598.5		598.78	0.000951	4.66	3374.68	798.11	0.23	1
2 (1b)	4786	1-Percent	13600	582.8	599.19		599.48	0.000946	4.83	3947.05	880.79	0.23	1
2 (1b)	4786	0.2-Percent	18000	582.8	600.58		600.89	0.000942	5.2	5334.49	1041.25	0.24	1
2 (1b)	4582	10-Percent	7990	582.7	597.88		598.06	0.002178	3.36	2744.95	766.99	0.19	4.49
2 (1b)	4582	2-Percent	11800	582.7	598.02		598.34	0.001133	4.98	3318.42	790.55	0.25	1
2 (1b)	4582	1-Percent	13600	582.7	598.71		599.04	0.001131	5.19	3915.43	951.61	0.25	1
2 (1b)	4582	0.2-Percent	18000	582.7	600.09		600.45	0.001137	5.61	5367.14	1091.7	0.26	1
2 (1b)	4363	10-Percent	7990	582.5	596.54	592.68	596.93	0.003662	3.5	1834.26	752.87	0.22	5.4
2 (1b)	4363	2-Percent	11800	582.5	597.61	590.78	597.91	0.000987	4.69	2879	1019.82	0.23	1
2 (1b)	4363	1-Percent	13600	582.5	598.36	591.3	598.63	0.000867	4.6	4631.81	1189.86	0.22	1
2 (1b)	4363	0.2-Percent	18000	582.5	599.75	592.38	600.03	0.000869	4.96	6316.99	1244.97	0.23	1
2 (1b)	4182	10-Percent	7990	582.4	596.03	590.08	596.38	0.002423	4.88	1715.52	461.01	0.27	1.99
2 (1b)	4182	2-Percent	11800	582.4	597.15	590.55	597.66	0.001656	5.93	2177.21	640.26	0.3	1
2 (1b)	4182	1-Percent	13600	582.4	597.79	591.12	598.38	0.001764	6.37	2370.28	896.17	0.31	1
2 (1b)	4182	0.2-Percent	18000	582.4	599.29	592.48	599.8	0.001504	6.4	4712.29	1187.29	0.3	1
2 (1b)	3997	10-Percent	7990	582.3	595.55	589.62	595.92	0.002555	4.95	1666.69	282.71	0.27	2.05
2 (1b)	3997	2-Percent	11800	582.3	596.83	590.02	597.36	0.001639	5.95	2154.17	525.9	0.3	1
2 (1b)	3997	1-Percent	13600	582.3	597.41	590.59	598.04	0.001814	6.48	2326.93	803.2	0.32	1
2 (1b)	3997	0.2-Percent	18000	582.3	598.75	591.89	599.47	0.001923	7.2	3967.34	1358.02	0.33	1
2 (1b)	3670	10-Percent	7990	582.1	595.25		595.31	0.001179	2.5	5654.99	1244.06	0.15	3.83
2 (1b)	3670	2-Percent	11800	582.1	596.76		596.82	0.001014	2.8	7649.63	1351.95	0.15	3.46

Table 6: Flood Scenario 2 with Ice Cover HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chn
2 (1b)	3670	1-Percent	13600	582.1	597.4		597.46	0.001011	2.86	8502.22	1396.39	0.15	3.61
2 (1b)	3670	0.2-Percent	18000	582.1	598.79		598.86	0.000986	3	10644.42	1779.16	0.15	3.89
2 (1b)	2921	10-Percent	7990	576.6	593.85		594.11	0.002189	4.44	2558.9	954.88	0.23	3.09
2 (1b)	2921	2-Percent	11800	576.6	595.76		595.96	0.001287	4.2	5111.49	1428.92	0.2	2.55
2 (1b)	2921	1-Percent	13600	576.6	596.51		596.67	0.001055	4.08	6201.24	1444.71	0.19	2.39
2 (1b)	2921	0.2-Percent	18000	576.6	598.06		598.19	0.000785	3.94	8928.85	2136.62	0.17	2.19
2 (1b)	1922	10-Percent	7990	573.7	593.54		593.58	0.000196	2.09	8257.98	1344.43	0.09	1.45
2 (1b)	1922	2-Percent	11800	573.7	595.49		595.52	0.000184	2.27	10949.93	1463.03	0.1	1.38
2 (1b)	1922	1-Percent	13600	573.7	596.23		596.27	0.000186	2.36	12141.66	1693.19	0.1	1.39
2 (1b)	1922	0.2-Percent	18000	573.7	597.78		597.82	0.000192	2.53	14988.84	1884.17	0.1	1.42
2 (1b)	833	10-Percent	7990	571.5	593.39		593.42	0.000106	2.01	7051.55	1516.47	0.08	1
2 (1b)	833	2-Percent	11800	571.5	595.34		595.38	0.000099	2.1	10374.31	1805.97	0.08	1
2 (1b)	833	1-Percent	13600	571.5	596.09		596.12	0.000098	2.14	11779.88	2068.75	0.08	1
2 (1b)	833	0.2-Percent	18000	571.5	597.64		597.68	0.000096	2.24	15564.63	2543.58	0.08	1
2 (1b)	279	10-Percent	7990	571	593.27	581.03	593.33	0.00012	2.35	5948.74	1083.92	0.1	1
2 (1b)	279	2-Percent	11800	571	595.23	582.78	595.29	0.00012	2.53	8758.64	2173.18	0.1	1
2 (1b)	279	1-Percent	13600	571	595.98	583.49	596.04	0.00012	2.6	10421.48	2286.34	0.1	1
2 (1b)	279	0.2-Percent	18000	571	597.53	585.08	597.59	0.00012	2.73	14338.36	2771.69	0.11	1

## **Flood Scenario #3 with Ice Cover**

### **Flood Bench Configuration: 1b + 2**

Plan: UPDATE-FB-1B+2-SCHOOL+UNION-ICE

Geometry: UPDATE-FB-1B+2-SCHOOL+UNION-ICE

Steady Flow Data: USGS BF,10,2,1,0.2-PERCENT-UPDATE-BC

Date: December 2022




Figure 31: Flood Scenario #3 (1b+2) with Ice Cover Profile Plot

Table 7: Flood Scenario 3 with Ice Cover HEC-RAS Output

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.ChnL	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chn
3 (1b+2)	20483	10-Percent	7990	621.4	631.44		632.23	0.00152	7.14	1149.93	159.75	0.42	
3 (1b+2)	20483	2-Percent	11800	621.4	633.13		634.27	0.001801	8.71	1502.7	283.71	0.47	
3 (1b+2)	20483	1-Percent	13600	621.4	633.75		635.03	0.001907	9.3	1683.2	292.19	0.49	
3 (1b+2)	20483	0.2-Percent	18000	621.4	635.05		636.62	0.002117	10.53	2068.75	300.59	0.52	
3 (1b+2)	19313	10-Percent	7990	620.4	628.71		629.8	0.002908	8.44	1044.14	306.61	0.56	
3 (1b+2)	19313	2-Percent	11800	620.4	630.2		631.56	0.003003	9.73	1584.78	383.6	0.58	
3 (1b+2)	19313	1-Percent	13600	620.4	630.82		632.26	0.00298	10.15	1839.24	441.9	0.59	
3 (1b+2)	19313	0.2-Percent	18000	620.4	632.19	630.62	633.75	0.002869	10.92	2526.91	588.68	0.59	
3 (1b+2)	18244	10-Percent	7990	617.6	626.65		627.29	0.001757	6.95	1777.22	467.86	0.44	
3 (1b+2)	18244	2-Percent	11800	617.6	628.34		629.05	0.001639	7.65	2591.04	496.46	0.44	
3 (1b+2)	18244	1-Percent	13600	617.6	629.04		629.77	0.001595	7.91	2943.68	525.83	0.44	
3 (1b+2)	18244	0.2-Percent	18000	617.6	630.58		631.36	0.001502	8.43	3818.19	582.92	0.43	
3 (1b+2)	17053	10-Percent	7990	615.5	624.35		625.09	0.001916	7.31	1642.13	449.92	0.46	
3 (1b+2)	17053	2-Percent	11800	615.5	625.99		626.9	0.001962	8.38	2446.6	516.1	0.48	
3 (1b+2)	17053	1-Percent	13600	615.5	626.66		627.64	0.001967	8.79	2801.03	526.03	0.49	
3 (1b+2)	17053	0.2-Percent	18000	615.5	628.2		629.3	0.001934	9.57	3631.51	561.19	0.49	
3 (1b+2)	15751	10-Percent	7990	612.8	621.5		622.32	0.002353	7.63	1281.07	298.43	0.5	
3 (1b+2)	15751	2-Percent	11800	612.8	623.1		624.11	0.002331	8.68	1817.77	352.78	0.52	
3 (1b+2)	15751	1-Percent	13600	612.8	623.84		624.9	0.002251	9	2081.97	364.33	0.51	
3 (1b+2)	15751	0.2-Percent	18000	612.8	625.57		626.72	0.00203	9.55	2727.68	378.08	0.5	
3 (1b+2)	14403	10-Percent	7990	610.3	619.62		620	0.001191	5.74	2433.58	541.73	0.36	
3 (1b+2)	14403	2-Percent	11800	610.3	621.69		622.05	0.000915	5.87	3595.27	583.33	0.33	
3 (1b+2)	14403	1-Percent	13600	610.3	622.61		622.96	0.000824	5.91	4152.77	637.99	0.32	
3 (1b+2)	14403	0.2-Percent	18000	610.3	624.76		625.08	0.000625	5.8	5655.52	746.8	0.28	
3 (1b+2)	12986	10-Percent	7990	608.9	618.23		618.6	0.000826	5.21	2428.01	736.5	0.31	
3 (1b+2)	12986	2-Percent	11800	608.9	620.65		620.99	0.000619	5.29	4557.71	922.38	0.28	
3 (1b+2)	12986	1-Percent	13600	608.9	621.69		622.01	0.00055	5.29	5526.43	947.89	0.27	
3 (1b+2)	12986	0.2-Percent	18000	608.9	624.04		624.33	0.000438	5.31	7810.45	999.57	0.24	
3 (1b+2)	12162	10-Percent	7990	604.9	617.03		617.77	0.001141	6.98	1207.69	135.15	0.37	
3 (1b+2)	12162	2-Percent	11800	604.9	619.08		620.18	0.001369	8.56	1649.42	402.74	0.42	
3 (1b+2)	12162	1-Percent	13600	604.9	620.09		621.25	0.001345	8.91	2098.69	463.53	0.42	
3 (1b+2)	12162	0.2-Percent	18000	604.9	622.62		623.71	0.001118	9.06	3568.83	729.62	0.39	
3 (1b+2)	11955	10-Percent	7990	605.5	616.8	611.72	617.53	0.001175	6.85	1177.37	116.61	0.37	
3 (1b+2)	11955	2-Percent	11800	605.5	618.78	613.35	619.89	0.001432	8.48	1413.64	149.66	0.42	
3 (1b+2)	11955	1-Percent	13600	605.5	619.66	614.06	620.94	0.00151	9.11	1521.39	162.34	0.44	
3 (1b+2)	11955	0.2-Percent	18000	605.5	621.71	615.65	623.37	0.001626	10.4	1774.71	330.41	0.47	
3 (1b+2)	11860 Union Rd	Bridge											
3 (1b+2)	11789	10-Percent	7990	605.5	616.22	612.39	617.18	0.002925	7.85	1022.61	112.37	0.45	1
3 (1b+2)	11789	2-Percent	11800	605.5	617.95	614.02	619.43	0.003606	9.76	1223	119.72	0.52	1
3 (1b+2)	11789	1-Percent	13600	605.5	618.6	614.75	620.34	0.003946	10.61	1302.12	123.36	0.55	1
3 (1b+2)	11789	0.2-Percent	18000	605.5	619.92	616.38	622.34	0.004801	12.56	1464.05	152.39	0.61	1
3 (1b+2)	11675	10-Percent	7990	602.4	616.13		616.7	0.00209	6.08	1336.4	130.41	0.32	1
3 (1b+2)	11675	2-Percent	11800	602.4	617.87		618.79	0.002689	7.72	1568.74	139.63	0.38	1
3 (1b+2)	11675	1-Percent	13600	602.4	618.53		619.63	0.002983	8.46	1663.55	150.46	0.41	1

Table 7: Flood Scenario 3 with Ice Cover HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chn
3 (1b+2)	11675	0.2-Percent	18000	602.4	619.87		621.43	0.00367	10.1	1939.27	305.89	0.46	1
3 (1b+2)	10302	10-Percent	7990	603.2	612.44		612.99	0.003619	6.22	1615.34	503.6	0.39	1
3 (1b+2)	10302	2-Percent	11800	603.2	613.64		614.32	0.00389	7.2	2290.94	591.22	0.42	1
3 (1b+2)	10302	1-Percent	13600	603.2	614.12		614.84	0.003933	7.54	2576.25	602.16	0.43	1
3 (1b+2)	10302	0.2-Percent	18000	603.2	615.17		615.96	0.003975	8.21	3218.83	623.64	0.44	1
3 (1b+2)	9372	10-Percent	7990	599.6	610.4		610.7	0.001693	4.73	2077.38	599.77	0.28	1
3 (1b+2)	9372	2-Percent	11800	599.6	611.63		611.96	0.001658	5.17	2827.52	618.22	0.28	1
3 (1b+2)	9372	1-Percent	13600	599.6	612.14		612.48	0.001632	5.32	3147.16	648.22	0.28	1
3 (1b+2)	9372	0.2-Percent	18000	599.6	613.36		613.71	0.001481	5.51	4084.79	990.85	0.28	1
3 (1b+2)	8312	10-Percent	7990	595.5	609.08		609.12	0.001198	1.43	5198.05	820.37	0.11	7.15
3 (1b+2)	8312	2-Percent	11800	595.5	609.67		609.76	0.002483	1.52	5276.43	822.88	0.13	9.3
3 (1b+2)	8312	1-Percent	13600	595.5	610.07		610.17	0.00284	1.59	5511.27	824.91	0.13	9.76
3 (1b+2)	8312	0.2-Percent	18000	595.5	611.42		611.54	0.002753	1.9	6625.37	841.09	0.14	9.85
3 (1b+2)	8145	10-Percent	7990	592.1	608.36	603.21	608.71	0.005869	4.75	1682.9	474.62	0.28	6.64
3 (1b+2)	8145	2-Percent	11800	592.1	608.93	601.33	609.32	0.002437	5	2358.88	487.22	0.25	3.34
3 (1b+2)	8145	1-Percent	13600	592.1	609.43	600.43	609.82	0.001395	5	2718.26	496.66	0.23	1.8
3 (1b+2)	8145	0.2-Percent	18000	592.1	610.71	600.82	611.24	0.001014	5.81	3097.55	517.06	0.25	1
3 (1b+2)	8049 Railroad Bridge	Bridge											
3 (1b+2)	7984	10-Percent	7990	592.1	608.09	602.72	608.45	0.003498	4.76	1669.72	566.01	0.27	3.41
3 (1b+2)	7984	2-Percent	11800	592.1	608.6	601.79	609.09	0.001525	5.67	2123.87	575.89	0.29	1
3 (1b+2)	7984	1-Percent	13600	592.1	608.97	602.36	609.58	0.001814	6.33	2193.45	587.66	0.31	1
3 (1b+2)	7984	0.2-Percent	18000	592.1	609.76	603.63	610.7	0.002535	7.84	2342.55	612.33	0.38	1
3 (1b+2)	7758	10-Percent	7990	595	607.31	604.72	607.41	0.001471	2.43	3173.57	1048.4	0.15	4.17
3 (1b+2)	7758	2-Percent	11800	595	608.11	606.03	608.24	0.001659	2.57	4072.41	1311.44	0.16	4.71
3 (1b+2)	7758	1-Percent	13600	595	608.45	606.48	608.61	0.001729	2.47	4449.64	1313.48	0.16	5.3
3 (1b+2)	7758	0.2-Percent	18000	595	609.24	606.94	609.44	0.001785	2.13	5286.27	1317.12	0.14	6.9
3 (1b+2)	7564	10-Percent	7990	594.9	606.78		606.87	0.001135	2.37	3386.28	1183.22	0.15	3.39
3 (1b+2)	7564	2-Percent	11800	594.9	607.49		607.61	0.001368	2.73	4322.26	1541.15	0.16	3.5
3 (1b+2)	7564	1-Percent	13600	594.9	607.82		607.95	0.001413	2.78	4827.35	1647.04	0.16	3.68
3 (1b+2)	7564	0.2-Percent	18000	594.9	608.57		608.72	0.001588	2.95	6077.96	1770.87	0.17	4.11
3 (1b+2)	7340	10-Percent	7990	594.8	606.4		606.47	0.000839	2.13	3893.68	1384.6	0.13	2.93
3 (1b+2)	7340	2-Percent	11800	594.8	606.97		607.08	0.001197	2.46	4683.99	1635.94	0.15	3.44
3 (1b+2)	7340	1-Percent	13600	594.8	607.28		607.4	0.001226	2.54	5216.67	1776.88	0.15	3.48
3 (1b+2)	7340	0.2-Percent	18000	594.8	607.99		608.13	0.001316	2.74	6515.37	1922.68	0.16	3.66
3 (1b+2)	7151	10-Percent	7990	594.7	605.93		606	0.00129	2.53	4224.14	1995.6	0.16	2.83
3 (1b+2)	7151	2-Percent	11800	594.7	606.15		606.28	0.002832	3.11	4482.14	2048.48	0.21	3.92
3 (1b+2)	7151	1-Percent	13600	594.7	606.55		606.67	0.002264	3.02	5343.88	2155.68	0.2	3.73
3 (1b+2)	7151	0.2-Percent	18000	594.7	607.32		607.43	0.00179	2.9	7101.14	2417.8	0.18	3.76
3 (1b+2)	6890	10-Percent	7990	593	605.68	601.86	605.7	0.000312	1.33	9691.83	2352.8	0.08	2.75
3 (1b+2)	6890	2-Percent	11800	593	605.34	603.19	605.39	0.001107	1.8	8623.6	2336.91	0.12	4.28
3 (1b+2)	6890	1-Percent	13600	593	605.88	603.35	605.93	0.000915	1.85	9958.42	2357.81	0.12	3.98
3 (1b+2)	6890	0.2-Percent	18000	593	606.71	603.83	606.78	0.000896	2.02	11936.4	2388.55	0.12	3.94
3 (1b+2)	6631	10-Percent	7990	592	605.2	601.74	605.33	0.001905	2.69	2942.79	1025.36	0.18	3.95
3 (1b+2)	6631	2-Percent	11800	592	603.88	599.88	604.39	0.002834	5.93	2161.15	598.27	0.35	1

Table 7: Flood Scenario 3 with Ice Cover HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chn
3 (1b+2)	6631	1-Percent	13600	592	604.51	600.36	605.05	0.002747	6.16	2418.13	777.37	0.36	1
3 (1b+2)	6631	0.2-Percent	18000	592	605.5	601.44	605.97	0.002304	6.11	3808.91	1070.69	0.34	1
3 (1b+2)	6324	10-Percent	7990	590.5	602.65	600.75	603.28	0.00668	3	1610.03	561.72	0.24	6.43
3 (1b+2)	6324	2-Percent	11800	590.5	602.73	598.1	603.06	0.001588	4.85	2595.65	568.49	0.27	1
3 (1b+2)	6324	1-Percent	13600	590.5	603.32	598.51	603.71	0.001659	5.19	2788.96	709.03	0.28	1
3 (1b+2)	6324	0.2-Percent	18000	590.5	604.51	599.38	604.84	0.0014	5.18	4197.95	827.61	0.27	1
3 (1b+2)	6015	10-Percent	7990	588.7	600.02		600.3	0.002684	1.68	2146.41	495.66	0.15	5.74
3 (1b+2)	6015	2-Percent	11800	588.7	600.97		601.43	0.003435	1.72	2458.91	503.92	0.16	6.96
3 (1b+2)	6015	1-Percent	13600	588.7	601.61		602.1	0.003146	1.8	2760.44	511.7	0.15	7.15
3 (1b+2)	6015	0.2-Percent	18000	588.7	602.97		603.47	0.002653	2.28	3568.27	691.97	0.16	6.7
3 (1b+2)	5607	10-Percent	7990	587.3	599.5	594.56	599.58	0.00047	1.72	3662.96	527.85	0.1	2.67
3 (1b+2)	5607	2-Percent	11800	587.3	600.19	595.16	600.33	0.000768	2.28	4019.41	547.11	0.13	2.83
3 (1b+2)	5607	1-Percent	13600	587.3	600.86	595.43	601.02	0.000773	2.41	4389.48	571.59	0.14	2.86
3 (1b+2)	5607	0.2-Percent	18000	587.3	602.24	596.05	602.44	0.000801	2.7	5177.09	963.37	0.14	2.94
3 (1b+2)	5307	10-Percent	7990	585.8	599.3		599.36	0.000321	1.91	4083.65	560.39	0.1	1.79
3 (1b+2)	5307	2-Percent	11800	585.8	599.81		599.93	0.000664	2.43	4258.1	572.27	0.13	2.64
3 (1b+2)	5307	1-Percent	13600	585.8	600.47		600.61	0.000677	2.55	4636.25	587.02	0.13	2.7
3 (1b+2)	5307	0.2-Percent	18000	585.8	601.84		602.01	0.000714	2.8	5650.87	1135.86	0.14	2.87
3 (1b+2)	5051	10-Percent	7990	584.3	599.01		599.12	0.000667	2.41	3244.61	652.53	0.13	2.5
3 (1b+2)	5051	2-Percent	11800	584.3	599.11		599.38	0.001796	3.38	3157.61	668.58	0.19	3.46
3 (1b+2)	5051	1-Percent	13600	584.3	599.79		600.07	0.001722	3.47	3642.41	860.33	0.19	3.52
3 (1b+2)	5051	0.2-Percent	18000	584.3	601.16		601.46	0.001601	3.64	4895.97	954.55	0.19	3.67
3 (1b+2)	4786	10-Percent	7990	582.8	598.58		598.71	0.00114	2.98	3101.18	805.87	0.16	3.45
3 (1b+2)	4786	2-Percent	11800	582.8	598.5		598.78	0.000951	4.66	3373.7	797.97	0.23	1
3 (1b+2)	4786	1-Percent	13600	582.8	599.19		599.48	0.000946	4.84	3945.22	880.42	0.23	1
3 (1b+2)	4786	0.2-Percent	18000	582.8	600.58		600.89	0.000942	5.2	5334.11	1041.25	0.24	1
3 (1b+2)	4582	10-Percent	7990	582.7	597.89		598.06	0.002151	3.36	2752.36	767.19	0.19	4.45
3 (1b+2)	4582	2-Percent	11800	582.7	598.02		598.34	0.001134	4.98	3317.16	790.06	0.25	1
3 (1b+2)	4582	1-Percent	13600	582.7	598.7		599.04	0.001133	5.19	3912.82	951.01	0.25	1
3 (1b+2)	4582	0.2-Percent	18000	582.7	600.09		600.45	0.001137	5.61	5366.67	1091.69	0.26	1
3 (1b+2)	4363	10-Percent	7990	582.5	596.56	592.68	596.94	0.003614	3.49	1842.22	757	0.22	5.39
3 (1b+2)	4363	2-Percent	11800	582.5	597.61	590.8	597.91	0.000987	4.69	2878	1018.71	0.23	1
3 (1b+2)	4363	1-Percent	13600	582.5	598.36	591.3	598.62	0.000868	4.6	4627.97	1189.75	0.22	1
3 (1b+2)	4363	0.2-Percent	18000	582.5	599.75	592.38	600.03	0.000869	4.96	6316.38	1244.95	0.23	1
3 (1b+2)	4182	10-Percent	7990	582.4	596.04	590.14	596.4	0.00246	4.88	1714.46	462.58	0.27	2.03
3 (1b+2)	4182	2-Percent	11800	582.4	597.14	590.55	597.66	0.001657	5.93	2176.59	640.03	0.3	1
3 (1b+2)	4182	1-Percent	13600	582.4	597.78	591.12	598.37	0.001766	6.37	2369.17	894.76	0.31	1
3 (1b+2)	4182	0.2-Percent	18000	582.4	599.29	592.48	599.8	0.001505	6.4	4711.58	1187.27	0.3	1
3 (1b+2)	3997	10-Percent	7990	582.3	595.56	589.65	595.93	0.002583	4.95	1665.36	282.94	0.27	2.07
3 (1b+2)	3997	2-Percent	11800	582.3	596.82	590.02	597.36	0.00164	5.95	2153.49	525.53	0.3	1
3 (1b+2)	3997	1-Percent	13600	582.3	597.41	590.59	598.04	0.001816	6.49	2325.71	799.24	0.32	1
3 (1b+2)	3997	0.2-Percent	18000	582.3	598.75	591.89	599.47	0.001924	7.2	3966.32	1357.9	0.33	1
3 (1b+2)	3670	10-Percent	7990	582.1	595.26		595.31	0.001188	2.49	5655.1	1244.35	0.15	3.88
3 (1b+2)	3670	2-Percent	11800	582.1	596.76		596.82	0.001011	2.8	7650.44	1351.88	0.15	3.43

Table 7: Flood Scenario 3 with Ice Cover HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chn
3 (1b+2)	3670	1-Percent	13600	582.1	597.39		597.46	0.001005	2.87	8504.31	1395.99	0.15	3.56
3 (1b+2)	3670	0.2-Percent	18000	582.1	598.79		598.86	0.000985	3	10644.95	1778.9	0.15	3.87
3 (1b+2)	2921	10-Percent	7990	576.6	593.85		594.11	0.002189	4.44	2558.9	954.88	0.23	3.09
3 (1b+2)	2921	2-Percent	11800	576.6	595.76		595.96	0.001287	4.2	5111.49	1428.92	0.2	2.55
3 (1b+2)	2921	1-Percent	13600	576.6	596.51		596.67	0.001055	4.08	6201.24	1444.71	0.19	2.39
3 (1b+2)	2921	0.2-Percent	18000	576.6	598.06		598.19	0.000785	3.94	8928.85	2136.62	0.17	2.19
3 (1b+2)	1922	10-Percent	7990	573.7	593.54		593.58	0.000196	2.09	8257.98	1344.43	0.09	1.45
3 (1b+2)	1922	2-Percent	11800	573.7	595.49		595.52	0.000184	2.27	10949.93	1463.03	0.1	1.38
3 (1b+2)	1922	1-Percent	13600	573.7	596.23		596.27	0.000186	2.36	12141.66	1693.19	0.1	1.39
3 (1b+2)	1922	0.2-Percent	18000	573.7	597.78		597.82	0.000192	2.53	14988.84	1884.17	0.1	1.42
3 (1b+2)	833	10-Percent	7990	571.5	593.39		593.42	0.000106	2.01	7051.55	1516.47	0.08	1
3 (1b+2)	833	2-Percent	11800	571.5	595.34		595.38	0.000099	2.1	10374.31	1805.97	0.08	1
3 (1b+2)	833	1-Percent	13600	571.5	596.09		596.12	0.000098	2.14	11779.88	2068.75	0.08	1
3 (1b+2)	833	0.2-Percent	18000	571.5	597.64		597.68	0.000096	2.24	15564.63	2543.58	0.08	1
3 (1b+2)	279	10-Percent	7990	571	593.27	581.03	593.33	0.00012	2.35	5948.74	1083.92	0.1	1
3 (1b+2)	279	2-Percent	11800	571	595.23	582.78	595.29	0.00012	2.53	8758.64	2173.18	0.1	1
3 (1b+2)	279	1-Percent	13600	571	595.98	583.49	596.04	0.00012	2.6	10421.48	2286.34	0.1	1
3 (1b+2)	279	0.2-Percent	18000	571	597.53	585.08	597.59	0.00012	2.73	14338.36	2771.69	0.11	1

## **Flood Scenario #4 with Ice Cover**

### **Flood Bench Configuration: 2 + 3**

Plan: UPDATE-FB-2+3-UNION+CLINTON-ICE

Geometry: UPDATE-FB-2+3-UNION+CLINTON-ICE

Steady Flow Data: USGS BF,10,2,1,0.2-PERCENT-UPDATE-BC

Date: December 2022




Figure 32: Flood Scenario #4 (2+3) with Ice Cover Profile Plot

Table 8: Flood Scenario 4 with Ice Cover HEC-RAS Output

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.ChnL	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chn
4 (2+3)	20483	10-Percent	7990	621.4	631.44		632.23	0.00152	7.14	1149.93	159.75	0.42	
4 (2+3)	20483	2-Percent	11800	621.4	633.13		634.27	0.001801	8.71	1502.7	283.71	0.47	
4 (2+3)	20483	1-Percent	13600	621.4	633.75		635.03	0.001907	9.3	1683.2	292.19	0.49	
4 (2+3)	20483	0.2-Percent	18000	621.4	635.05		636.62	0.002117	10.53	2068.77	300.59	0.52	
4 (2+3)	19313	10-Percent	7990	620.4	628.71		629.8	0.002908	8.44	1044.14	306.61	0.56	
4 (2+3)	19313	2-Percent	11800	620.4	630.2		631.56	0.003003	9.73	1584.78	383.6	0.58	
4 (2+3)	19313	1-Percent	13600	620.4	630.82		632.26	0.00298	10.15	1839.24	441.9	0.59	
4 (2+3)	19313	0.2-Percent	18000	620.4	632.19	630.62	633.75	0.002869	10.92	2526.99	588.7	0.59	
4 (2+3)	18244	10-Percent	7990	617.6	626.65		627.29	0.001757	6.95	1777.22	467.86	0.44	
4 (2+3)	18244	2-Percent	11800	617.6	628.34		629.05	0.001639	7.65	2591.04	496.46	0.44	
4 (2+3)	18244	1-Percent	13600	617.6	629.04		629.77	0.001595	7.91	2943.68	525.83	0.44	
4 (2+3)	18244	0.2-Percent	18000	617.6	630.58		631.36	0.001502	8.43	3818.3	582.92	0.43	
4 (2+3)	17053	10-Percent	7990	615.5	624.35		625.09	0.001916	7.31	1642.13	449.92	0.46	
4 (2+3)	17053	2-Percent	11800	615.5	625.99		626.9	0.001962	8.38	2446.6	516.1	0.48	
4 (2+3)	17053	1-Percent	13600	615.5	626.66		627.64	0.001967	8.79	2801.06	526.03	0.49	
4 (2+3)	17053	0.2-Percent	18000	615.5	628.2		629.3	0.001933	9.57	3631.81	561.22	0.49	
4 (2+3)	15751	10-Percent	7990	612.8	621.5		622.32	0.002353	7.63	1281.07	298.43	0.5	
4 (2+3)	15751	2-Percent	11800	612.8	623.1		624.11	0.002331	8.68	1817.84	352.78	0.52	
4 (2+3)	15751	1-Percent	13600	612.8	623.84		624.9	0.00225	8.99	2082.15	364.34	0.51	
4 (2+3)	15751	0.2-Percent	18000	612.8	625.58		626.72	0.002028	9.55	2728.69	378.1	0.5	
4 (2+3)	14403	10-Percent	7990	610.3	619.62		620	0.001191	5.74	2433.51	541.73	0.36	
4 (2+3)	14403	2-Percent	11800	610.3	621.69		622.05	0.000914	5.87	3595.56	583.34	0.33	
4 (2+3)	14403	1-Percent	13600	610.3	622.61		622.96	0.000824	5.91	4153.44	638.03	0.32	
4 (2+3)	14403	0.2-Percent	18000	610.3	624.77		625.08	0.000624	5.8	5658.76	747.05	0.28	
4 (2+3)	12986	10-Percent	7990	608.9	618.23		618.6	0.000827	5.21	2427.88	736.44	0.31	
4 (2+3)	12986	2-Percent	11800	608.9	620.65		620.99	0.000619	5.29	4558.45	922.4	0.28	
4 (2+3)	12986	1-Percent	13600	608.9	621.69		622.01	0.00055	5.29	5527.88	947.91	0.27	
4 (2+3)	12986	0.2-Percent	18000	608.9	624.05		624.34	0.000438	5.3	7815.94	999.73	0.24	
4 (2+3)	12162	10-Percent	7990	604.9	617.03		617.77	0.001141	6.98	1207.66	135.14	0.37	
4 (2+3)	12162	2-Percent	11800	604.9	619.08		620.18	0.001369	8.55	1649.94	403.2	0.42	
4 (2+3)	12162	1-Percent	13600	604.9	620.09		621.25	0.001344	8.9	2099.93	463.56	0.42	
4 (2+3)	12162	0.2-Percent	18000	604.9	622.63		623.71	0.001115	9.05	3575.48	731.22	0.39	
4 (2+3)	11955	10-Percent	7990	605.5	616.8	611.72	617.53	0.001175	6.85	1177.34	116.61	0.37	
4 (2+3)	11955	2-Percent	11800	605.5	618.78	613.35	619.89	0.001432	8.48	1413.81	149.68	0.42	
4 (2+3)	11955	1-Percent	13600	605.5	619.66	614.06	620.94	0.001509	9.11	1521.73	162.38	0.44	
4 (2+3)	11955	0.2-Percent	18000	605.5	621.72	615.65	623.38	0.001623	10.39	1775.84	332.06	0.47	
4 (2+3)	11860 Union Rd	Bridge											
4 (2+3)	11789	10-Percent	7990	605.5	616.22	612.39	617.18	0.002925	7.85	1022.58	112.37	0.45	1
4 (2+3)	11789	2-Percent	11800	605.5	617.95	614.02	619.43	0.003604	9.76	1223.19	119.72	0.52	1
4 (2+3)	11789	1-Percent	13600	605.5	618.61	614.75	620.34	0.003942	10.61	1302.55	123.38	0.55	1
4 (2+3)	11789	0.2-Percent	18000	605.5	619.93	616.38	622.35	0.004784	12.55	1465.69	153.18	0.61	1
4 (2+3)	11675	10-Percent	7990	602.4	616.13		616.7	0.00209	6.08	1336.36	130.41	0.32	1
4 (2+3)	11675	2-Percent	11800	602.4	617.88		618.8	0.002688	7.72	1568.97	139.64	0.38	1
4 (2+3)	11675	1-Percent	13600	602.4	618.53		619.63	0.00298	8.46	1664.11	150.55	0.41	1

Table 8: Flood Scenario 4 with Ice Cover HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.ChnL	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chn
4 (2+3)	11675	0.2-Percent	18000	602.4	619.89		621.44	0.003656	10.09	1943.67	306.48	0.46	1
4 (2+3)	10302	10-Percent	7990	603.2	612.45		613	0.003606	6.21	1618.54	503.83	0.39	1
4 (2+3)	10302	2-Percent	11800	603.2	613.64		614.32	0.003899	7.21	2288.49	591.17	0.42	1
4 (2+3)	10302	1-Percent	13600	603.2	614.11		614.83	0.003958	7.55	2569.57	601.71	0.43	1
4 (2+3)	10302	0.2-Percent	18000	603.2	615.13		615.94	0.004056	8.27	3193.87	623.24	0.45	1
4 (2+3)	9372	10-Percent	7990	599.6	610.25		610.58	0.001872	4.91	1990.24	596.56	0.29	1
4 (2+3)	9372	2-Percent	11800	599.6	611.44		611.8	0.001868	5.4	2706.38	613.84	0.3	1
4 (2+3)	9372	1-Percent	13600	599.6	611.93		612.3	0.001848	5.58	3010.19	631.31	0.3	1
4 (2+3)	9372	0.2-Percent	18000	599.6	613.06		613.46	0.00173	5.84	3804.73	871.61	0.3	1
4 (2+3)	8312	10-Percent	7990	595.5	607.93		608.01	0.003056	1.12	3824.79	778.69	0.12	9.62
4 (2+3)	8312	2-Percent	11800	595.5	608.29		608.45	0.006115	0.87	3771.02	761.98	0.12	11.67
4 (2+3)	8312	1-Percent	13600	595.5	608.73		608.92	0.006483	0.9	4041.9	769.14	0.13	12.1
4 (2+3)	8312	0.2-Percent	18000	595.5	610.15		610.36	0.005649	1.22	5096.6	801.78	0.14	12.51
4 (2+3)	8145	10-Percent	7990	592.1	606.88	602.21	607.26	0.006332	5	1597.19	430.2	0.3	5.52
4 (2+3)	8145	2-Percent	11800	592.1	607.54	599.97	607.93	0.001774	5	2357.7	457.15	0.25	1.83
4 (2+3)	8145	1-Percent	13600	592.1	608.11	599.7	608.53	0.001065	5.21	2608.35	469.33	0.25	1
4 (2+3)	8145	0.2-Percent	18000	592.1	609.27	600.82	609.9	0.001403	6.37	2826.43	494.42	0.29	1
4 (2+3)	8049 Railroad Bridge	Bridge											
4 (2+3)	7984	10-Percent	7990	592.1	606.6	601.23	606.98	0.002758	4.96	1623.74	502.26	0.28	1.86
4 (2+3)	7984	2-Percent	11800	592.1	607	601.79	607.66	0.002549	6.58	1824.86	524.05	0.35	1
4 (2+3)	7984	1-Percent	13600	592.1	607.41	602.37	608.22	0.002951	7.29	1900.63	535.1	0.39	1
4 (2+3)	7984	0.2-Percent	18000	592.1	608.23	603.64	609.45	0.003971	8.94	2054.82	567.15	0.46	1
4 (2+3)	7758	10-Percent	7990	595	606.3	602.53	606.37	0.000579	1.73	3949.08	888.53	0.11	2.87
4 (2+3)	7758	2-Percent	11800	595	606.43	603.51	606.61	0.001519	1.83	3749.34	894.3	0.13	5.19
4 (2+3)	7758	1-Percent	13600	595	606.88	603.79	607.06	0.001461	1.76	4297.22	937.67	0.13	5.65
4 (2+3)	7758	0.2-Percent	18000	595	607.68	604.51	607.92	0.001694	1.58	4937.03	1206.71	0.12	7.24
4 (2+3)	7564	10-Percent	7990	594.9	606.12		606.16	0.000398	1.76	4545.41	962.1	0.1	1.92
4 (2+3)	7564	2-Percent	11800	594.9	605.9		606.03	0.001207	2.27	4177.14	926.65	0.15	3.27
4 (2+3)	7564	1-Percent	13600	594.9	606.35		606.49	0.001211	2.35	4599.1	1006.82	0.15	3.36
4 (2+3)	7564	0.2-Percent	18000	594.9	607.06		607.25	0.001433	2.49	5341.97	1291.58	0.16	3.93
4 (2+3)	7340	10-Percent	7990	594.8	606		606.03	0.00025	1.57	5575.2	1172.09	0.09	1.42
4 (2+3)	7340	2-Percent	11800	594.8	605.5		605.59	0.000907	2.13	4869.56	1089.68	0.14	2.64
4 (2+3)	7340	1-Percent	13600	594.8	605.95		606.05	0.000887	2.2	5372.19	1150.56	0.14	2.67
4 (2+3)	7340	0.2-Percent	18000	594.8	606.59		606.73	0.001074	2.4	6160.26	1428.34	0.15	3.06
4 (2+3)	7151	10-Percent	7990	594.7	605.92		605.94	0.000152	1.37	7047.19	1992.33	0.08	1.11
4 (2+3)	7151	2-Percent	11800	594.7	605.14		605.22	0.000731	1.92	5418.71	1468.93	0.13	2.36
4 (2+3)	7151	1-Percent	13600	594.7	605.62		605.7	0.000685	2	6261.41	1920.16	0.13	2.28
4 (2+3)	7151	0.2-Percent	18000	594.7	606.19		606.28	0.000852	2.19	7324.17	2062.22	0.14	2.66
4 (2+3)	6890	10-Percent	7990	593	605.88	599.92	605.89	0.000064	0.94	12527.93	2357.76	0.05	1.12
4 (2+3)	6890	2-Percent	11800	593	604.87	600.38	604.93	0.000416	1.48	6447.69	2310.61	0.09	2.51
4 (2+3)	6890	1-Percent	13600	593	605.44	600.53	605.46	0.00028	1.36	11301.99	2342.06	0.08	2.24
4 (2+3)	6890	0.2-Percent	18000	593	605.95	600.96	605.98	0.000373	1.58	12458.11	2359.63	0.09	2.48
4 (2+3)	6631	10-Percent	7990	592	605.58	601.3	605.76	0.002201	3.17	2419.19	1082.85	0.2	3.67
4 (2+3)	6631	2-Percent	11800	592	603.88	599.88	604.39	0.002832	5.92	2161.64	733.84	0.35	1

Table 8: Flood Scenario 4 with Ice Cover HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.ChnL	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chn
4 (2+3)	6631	1-Percent	13600	592	604.51	600.37	605.05	0.002744	6.16	2419.08	784.27	0.36	1
4 (2+3)	6631	0.2-Percent	18000	592	605.41	601.44	605.62	0.001143	4.27	4979.63	1045.05	0.24	1
4 (2+3)	6324	10-Percent	7990	590.5	602.53	601.1	603.33	0.008292	2.93	1481.12	547.41	0.25	6.95
4 (2+3)	6324	2-Percent	11800	590.5	602.73	598.1	603.06	0.001587	4.85	2596.36	568.62	0.27	1
4 (2+3)	6324	1-Percent	13600	590.5	603.33	598.51	603.71	0.001656	5.19	2790.22	710.54	0.28	1
4 (2+3)	6324	0.2-Percent	18000	590.5	604.51	599.38	604.84	0.0014	5.18	4198.31	827.73	0.27	1
4 (2+3)	6015	10-Percent	7990	588.7	600.51		600.73	0.001833	1.63	2427.41	499.98	0.13	5.49
4 (2+3)	6015	2-Percent	11800	588.7	601		601.45	0.003353	1.74	2482.71	504.18	0.16	6.89
4 (2+3)	6015	1-Percent	13600	588.7	601.63		602.12	0.00309	1.82	2780.05	511.9	0.15	7.1
4 (2+3)	6015	0.2-Percent	18000	588.7	603		603.49	0.0026	2.31	3599.85	695.75	0.16	6.59
4 (2+3)	5607	10-Percent	7990	587.3	600.16	594.34	600.22	0.000333	1.67	4059.63	546.31	0.09	2.26
4 (2+3)	5607	2-Percent	11800	587.3	600.24	595.16	600.38	0.000747	2.28	4053.08	548.25	0.13	2.78
4 (2+3)	5607	1-Percent	13600	587.3	600.9	595.41	601.06	0.000757	2.41	4416.75	573.94	0.13	2.82
4 (2+3)	5607	0.2-Percent	18000	587.3	602.27	596	602.47	0.000789	2.7	5200.24	973.07	0.14	2.91
4 (2+3)	5307	10-Percent	7990	585.8	600.01		600.06	0.000233	1.75	4506.07	575.82	0.09	1.67
4 (2+3)	5307	2-Percent	11800	585.8	599.88		600	0.000627	2.44	4319.75	573.49	0.13	2.48
4 (2+3)	5307	1-Percent	13600	585.8	600.53		600.66	0.000648	2.57	4687.13	587.54	0.13	2.56
4 (2+3)	5307	0.2-Percent	18000	585.8	601.89		602.05	0.000688	2.82	5722.75	1168.9	0.14	2.73
4 (2+3)	5051	10-Percent	7990	584.3	599.68		599.82	0.001249	3.15	2947.62	766.64	0.17	3.06
4 (2+3)	5051	2-Percent	11800	584.3	599.21		599.54	0.001187	4.87	2949.37	664.88	0.25	1
4 (2+3)	5051	1-Percent	13600	584.3	599.85		600.2	0.001188	5.08	3421.59	872.11	0.25	1
4 (2+3)	5051	0.2-Percent	18000	584.3	601.21		601.57	0.00116	5.44	4655.16	935.59	0.26	1
4 (2+3)	4786	10-Percent	7990	582.8	599.01		599.13	0.001702	3.2	3042.02	845.12	0.18	4.56
4 (2+3)	4786	2-Percent	11800	582.8	598.68		599.01	0.001074	5	3254.57	817.09	0.24	1
4 (2+3)	4786	1-Percent	13600	582.8	599.33		599.67	0.001074	5.19	3806.97	913.8	0.25	1
4 (2+3)	4786	0.2-Percent	18000	582.8	600.7		601.05	0.001048	5.52	5198.04	1042.57	0.25	1
4 (2+3)	4582	10-Percent	7990	582.7	597.88		598.08	0.00399	4.04	2406.55	751.33	0.24	5.27
4 (2+3)	4582	2-Percent	11800	582.7	598.14		598.51	0.001268	5.31	3182.46	816.12	0.26	1
4 (2+3)	4582	1-Percent	13600	582.7	598.78		599.17	0.001283	5.55	3751.86	977.87	0.27	1
4 (2+3)	4582	0.2-Percent	18000	582.7	600.15		600.56	0.001277	5.97	5198.41	1093.14	0.27	1
4 (2+3)	4363	10-Percent	7990	582.5	596.49	590.48	596.82	0.002462	4.75	1790.51	742.9	0.26	2.34
4 (2+3)	4363	2-Percent	11800	582.5	597.48	590.61	597.95	0.001487	5.72	2365.98	945.93	0.28	1
4 (2+3)	4363	1-Percent	13600	582.5	598.28	591.23	598.66	0.001234	5.46	4087.63	1174.9	0.26	1
4 (2+3)	4363	0.2-Percent	18000	582.5	599.68	592.56	600.06	0.001167	5.73	5786.89	1242.01	0.26	1
4 (2+3)	4182	10-Percent	7990	582.4	596.03	590.04	596.39	0.002329	4.85	1726.56	461.73	0.27	1.93
4 (2+3)	4182	2-Percent	11800	582.4	597.14	590.55	597.66	0.001656	5.93	2176.92	640.15	0.3	1
4 (2+3)	4182	1-Percent	13600	582.4	597.78	591.12	598.37	0.001766	6.37	2369.5	895.16	0.31	1
4 (2+3)	4182	0.2-Percent	18000	582.4	599.29	592.48	599.8	0.001504	6.4	4712.29	1187.29	0.3	1
4 (2+3)	3997	10-Percent	7990	582.3	595.56	589.65	595.93	0.002585	4.95	1664.97	282.91	0.27	2.07
4 (2+3)	3997	2-Percent	11800	582.3	596.82	590.02	597.36	0.001639	5.95	2153.86	525.73	0.3	1
4 (2+3)	3997	1-Percent	13600	582.3	597.41	590.59	598.04	0.001815	6.49	2326.06	800.37	0.32	1
4 (2+3)	3997	0.2-Percent	18000	582.3	598.75	591.89	599.47	0.001923	7.2	3967.34	1358.02	0.33	1
4 (2+3)	3670	10-Percent	7990	582.1	595.26		595.31	0.001186	2.49	5655.55	1244.31	0.15	3.87
4 (2+3)	3670	2-Percent	11800	582.1	596.76		596.82	0.001013	2.8	7649.98	1351.92	0.15	3.45

Table 8: Flood Scenario 4 with Ice Cover HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chn
4 (2+3)	3670	1-Percent	13600	582.1	597.4		597.46	0.001007	2.87	8503.65	1396.1	0.15	3.58
4 (2+3)	3670	0.2-Percent	18000	582.1	598.79		598.86	0.000986	3	10644.42	1779.16	0.15	3.89
4 (2+3)	2921	10-Percent	7990	576.6	593.85		594.11	0.002187	4.44	2559.96	955.18	0.23	3.09
4 (2+3)	2921	2-Percent	11800	576.6	595.76		595.96	0.001287	4.2	5111.49	1428.92	0.2	2.55
4 (2+3)	2921	1-Percent	13600	576.6	596.51		596.67	0.001055	4.08	6201.24	1444.71	0.19	2.39
4 (2+3)	2921	0.2-Percent	18000	576.6	598.06		598.19	0.000785	3.94	8928.85	2136.62	0.17	2.19
4 (2+3)	1922	10-Percent	7990	573.7	593.54		593.58	0.000197	2.08	8257.55	1344.43	0.09	1.46
4 (2+3)	1922	2-Percent	11800	573.7	595.49		595.52	0.000184	2.27	10949.93	1463.03	0.1	1.38
4 (2+3)	1922	1-Percent	13600	573.7	596.23		596.27	0.000186	2.36	12141.66	1693.19	0.1	1.39
4 (2+3)	1922	0.2-Percent	18000	573.7	597.78		597.82	0.000192	2.53	14988.84	1884.17	0.1	1.42
4 (2+3)	833	10-Percent	7990	571.5	593.39		593.42	0.000106	2.01	7051.55	1516.47	0.08	1
4 (2+3)	833	2-Percent	11800	571.5	595.34		595.38	0.000099	2.1	10374.31	1805.97	0.08	1
4 (2+3)	833	1-Percent	13600	571.5	596.09		596.12	0.000098	2.14	11779.88	2068.75	0.08	1
4 (2+3)	833	0.2-Percent	18000	571.5	597.64		597.68	0.000096	2.24	15564.63	2543.58	0.08	1
4 (2+3)	279	10-Percent	7990	571	593.27	581.03	593.33	0.00012	2.35	5948.74	1083.92	0.1	1
4 (2+3)	279	2-Percent	11800	571	595.23	582.78	595.29	0.00012	2.53	8758.64	2173.18	0.1	1
4 (2+3)	279	1-Percent	13600	571	595.98	583.49	596.04	0.00012	2.6	10421.48	2286.34	0.1	1
4 (2+3)	279	0.2-Percent	18000	571	597.53	585.08	597.59	0.00012	2.73	14338.36	2771.69	0.11	1

## **Flood Scenario #5 with Ice Cover**

### **Flood Bench Configuration: 1b + 2 + 3**

Plan: UPDATE-FB-1b+2+3-SCHOOL+UNION+CLINTON-ICE

Geometry: UPDATE-FB-1b+2+3-SCHOOL+UNION+CLINTON-ICE

Steady Flow Data: USGS BF,10,2,1,0.2-PERCENT-UPDATE-BC

Date: December 2022




Figure 33: Flood Scenario #5 (1b+2+3) with Ice Cover Profile Plot

Table 9: Flood Scenario 5 with Ice Cover HEC-RAS Output

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chan
5 (1b+2+3)	20483	10-Percent	7990	621.4	631.44		632.23	0.00152	7.14	1149.93	159.75	0.42	
5 (1b+2+3)	20483	2-Percent	11800	621.4	633.13		634.27	0.001801	8.71	1502.7	283.71	0.47	
5 (1b+2+3)	20483	1-Percent	13600	621.4	633.75		635.03	0.001907	9.3	1683.2	292.19	0.49	
5 (1b+2+3)	20483	0.2-Percent	18000	621.4	635.05		636.62	0.002117	10.53	2068.77	300.59	0.52	
5 (1b+2+3)	19313	10-Percent	7990	620.4	628.71		629.8	0.002908	8.44	1044.14	306.61	0.56	
5 (1b+2+3)	19313	2-Percent	11800	620.4	630.2		631.56	0.003003	9.73	1584.78	383.6	0.58	
5 (1b+2+3)	19313	1-Percent	13600	620.4	630.82		632.26	0.00298	10.15	1839.24	441.9	0.59	
5 (1b+2+3)	19313	0.2-Percent	18000	620.4	632.19	630.62	633.75	0.002869	10.92	2526.99	588.7	0.59	
5 (1b+2+3)	18244	10-Percent	7990	617.6	626.65		627.29	0.001757	6.95	1777.22	467.86	0.44	
5 (1b+2+3)	18244	2-Percent	11800	617.6	628.34		629.05	0.001639	7.65	2591.04	496.46	0.44	
5 (1b+2+3)	18244	1-Percent	13600	617.6	629.04		629.77	0.001595	7.91	2943.68	525.83	0.44	
5 (1b+2+3)	18244	0.2-Percent	18000	617.6	630.58		631.36	0.001502	8.43	3818.3	582.92	0.43	
5 (1b+2+3)	17053	10-Percent	7990	615.5	624.35		625.09	0.001916	7.31	1642.13	449.92	0.46	
5 (1b+2+3)	17053	2-Percent	11800	615.5	625.99		626.9	0.001962	8.38	2446.6	516.1	0.48	
5 (1b+2+3)	17053	1-Percent	13600	615.5	626.66		627.64	0.001967	8.79	2801.06	526.03	0.49	
5 (1b+2+3)	17053	0.2-Percent	18000	615.5	628.2		629.3	0.001933	9.57	3631.81	561.22	0.49	
5 (1b+2+3)	15751	10-Percent	7990	612.8	621.5		622.32	0.002353	7.63	1281.07	298.43	0.5	
5 (1b+2+3)	15751	2-Percent	11800	612.8	623.1		624.11	0.002331	8.68	1817.84	352.78	0.52	
5 (1b+2+3)	15751	1-Percent	13600	612.8	623.84		624.9	0.00225	8.99	2082.15	364.34	0.51	
5 (1b+2+3)	15751	0.2-Percent	18000	612.8	625.58		626.72	0.002028	9.55	2728.69	378.1	0.5	
5 (1b+2+3)	14403	10-Percent	7990	610.3	619.62		620	0.001191	5.74	2433.54	541.73	0.36	
5 (1b+2+3)	14403	2-Percent	11800	610.3	621.69		622.05	0.000914	5.87	3595.56	583.34	0.33	
5 (1b+2+3)	14403	1-Percent	13600	610.3	622.61		622.96	0.000824	5.91	4153.44	638.03	0.32	
5 (1b+2+3)	14403	0.2-Percent	18000	610.3	624.77		625.08	0.000624	5.8	5658.71	747.05	0.28	
5 (1b+2+3)	12986	10-Percent	7990	608.9	618.23		618.6	0.000827	5.21	2427.97	736.48	0.31	
5 (1b+2+3)	12986	2-Percent	11800	608.9	620.65		620.99	0.000619	5.29	4558.45	922.4	0.28	
5 (1b+2+3)	12986	1-Percent	13600	608.9	621.69		622.01	0.00055	5.29	5527.88	947.91	0.27	
5 (1b+2+3)	12986	0.2-Percent	18000	608.9	624.05		624.34	0.000438	5.3	7815.88	999.73	0.24	
5 (1b+2+3)	12162	10-Percent	7990	604.9	617.03		617.77	0.001141	6.98	1207.69	135.15	0.37	
5 (1b+2+3)	12162	2-Percent	11800	604.9	619.08		620.18	0.001369	8.55	1649.94	403.2	0.42	
5 (1b+2+3)	12162	1-Percent	13600	604.9	620.09		621.25	0.001344	8.9	2099.93	463.56	0.42	
5 (1b+2+3)	12162	0.2-Percent	18000	604.9	622.63		623.71	0.001115	9.05	3575.43	731.22	0.39	
5 (1b+2+3)	11955	10-Percent	7990	605.5	616.8	611.72	617.53	0.001175	6.85	1177.36	116.61	0.37	
5 (1b+2+3)	11955	2-Percent	11800	605.5	618.78	613.35	619.89	0.001432	8.48	1413.81	149.68	0.42	
5 (1b+2+3)	11955	1-Percent	13600	605.5	619.66	614.06	620.94	0.001509	9.11	1521.73	162.38	0.44	
5 (1b+2+3)	11955	0.2-Percent	18000	605.5	621.72	615.65	623.38	0.001623	10.39	1775.83	332.05	0.47	
5 (1b+2+3)	11860 Union Rd	Bridge											
5 (1b+2+3)	11789	10-Percent	7990	605.5	616.22	612.39	617.18	0.002925	7.85	1022.59	112.37	0.45	1
5 (1b+2+3)	11789	2-Percent	11800	605.5	617.95	614.02	619.43	0.003604	9.76	1223.19	119.72	0.52	1
5 (1b+2+3)	11789	1-Percent	13600	605.5	618.61	614.75	620.34	0.003942	10.61	1302.55	123.38	0.55	1
5 (1b+2+3)	11789	0.2-Percent	18000	605.5	619.93	616.38	622.35	0.004784	12.55	1465.68	153.16	0.61	1
5 (1b+2+3)	11675	10-Percent	7990	602.4	616.13		616.7	0.00209	6.08	1336.37	130.41	0.32	1
5 (1b+2+3)	11675	2-Percent	11800	602.4	617.88		618.8	0.002688	7.72	1568.97	139.64	0.38	1
5 (1b+2+3)	11675	1-Percent	13600	602.4	618.53		619.63	0.00298	8.46	1664.11	150.55	0.41	1

Table 9: Flood Scenario 5 with Ice Cover HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.ChnL	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chan
5 (1b+2+3)	11675	0.2-Percent	18000	602.4	619.89		621.44	0.003656	10.09	1943.65	306.48	0.46	1
5 (1b+2+3)	10302	10-Percent	7990	603.2	612.45		613	0.003606	6.21	1618.45	503.82	0.39	1
5 (1b+2+3)	10302	2-Percent	11800	603.2	613.64		614.32	0.003899	7.21	2288.49	591.17	0.42	1
5 (1b+2+3)	10302	1-Percent	13600	603.2	614.11		614.83	0.003958	7.55	2569.57	601.71	0.43	1
5 (1b+2+3)	10302	0.2-Percent	18000	603.2	615.13		615.94	0.004056	8.27	3193.91	623.24	0.45	1
5 (1b+2+3)	9372	10-Percent	7990	599.6	610.26		610.58	0.001868	4.9	1991.95	596.63	0.29	1
5 (1b+2+3)	9372	2-Percent	11800	599.6	611.44		611.8	0.001868	5.4	2706.38	613.84	0.3	1
5 (1b+2+3)	9372	1-Percent	13600	599.6	611.93		612.3	0.001848	5.58	3010.19	631.31	0.3	1
5 (1b+2+3)	9372	0.2-Percent	18000	599.6	613.06		613.46	0.00173	5.84	3804.63	871.39	0.3	1
5 (1b+2+3)	8312	10-Percent	7990	595.5	607.92		607.99	0.00311	1.09	3797.4	777.89	0.12	9.71
5 (1b+2+3)	8312	2-Percent	11800	595.5	608.29		608.45	0.006115	0.87	3771.04	761.98	0.12	11.67
5 (1b+2+3)	8312	1-Percent	13600	595.5	608.73		608.92	0.006483	0.9	4041.86	769.14	0.13	12.1
5 (1b+2+3)	8312	0.2-Percent	18000	595.5	610.15		610.36	0.005649	1.22	5096.33	801.77	0.14	12.51
5 (1b+2+3)	8145	10-Percent	7990	592.1	606.86	602.19	607.25	0.006306	5	1597.83	428.55	0.3	5.5
5 (1b+2+3)	8145	2-Percent	11800	592.1	607.54	599.97	607.93	0.001775	5	2357.67	457.15	0.25	1.83
5 (1b+2+3)	8145	1-Percent	13600	592.1	608.11	599.7	608.53	0.001065	5.21	2608.34	469.33	0.25	1
5 (1b+2+3)	8145	0.2-Percent	18000	592.1	609.27	600.82	609.9	0.001403	6.37	2826.36	494.41	0.29	1
5 (1b+2+3)	8049 Railroad Bridge	Bridge											
5 (1b+2+3)	7984	10-Percent	7990	592.1	606.59	601.15	606.96	0.002681	4.95	1629.35	501.55	0.28	1.8
5 (1b+2+3)	7984	2-Percent	11800	592.1	607	601.79	607.66	0.002549	6.58	1824.85	524.05	0.35	1
5 (1b+2+3)	7984	1-Percent	13600	592.1	607.41	602.37	608.22	0.002952	7.29	1900.62	535.1	0.39	1
5 (1b+2+3)	7984	0.2-Percent	18000	592.1	608.23	603.64	609.45	0.003972	8.94	2054.73	567.15	0.46	1
5 (1b+2+3)	7758	10-Percent	7990	595	606.28	602.54	606.35	0.000592	1.73	3926.16	888.14	0.11	2.94
5 (1b+2+3)	7758	2-Percent	11800	595	606.43	603.5	606.61	0.001519	1.83	3749.23	894.29	0.13	5.2
5 (1b+2+3)	7758	1-Percent	13600	595	606.88	603.8	607.06	0.001462	1.76	4297.05	937.67	0.13	5.65
5 (1b+2+3)	7758	0.2-Percent	18000	595	607.68	604.51	607.92	0.001695	1.58	4937.05	1206.32	0.12	7.24
5 (1b+2+3)	7564	10-Percent	7990	594.9	606.09		606.14	0.00041	1.74	4511.15	958.97	0.1	2
5 (1b+2+3)	7564	2-Percent	11800	594.9	605.9		606.03	0.001208	2.27	4176.89	926.64	0.15	3.27
5 (1b+2+3)	7564	1-Percent	13600	594.9	606.35		606.49	0.001212	2.35	4598.73	1006.78	0.15	3.36
5 (1b+2+3)	7564	0.2-Percent	18000	594.9	607.06		607.25	0.001434	2.49	5340.83	1291.22	0.16	3.93
5 (1b+2+3)	7340	10-Percent	7990	594.8	605.97		606	0.00026	1.54	5530.36	1156.67	0.09	1.5
5 (1b+2+3)	7340	2-Percent	11800	594.8	605.5		605.59	0.000907	2.13	4869.04	1089.66	0.14	2.64
5 (1b+2+3)	7340	1-Percent	13600	594.8	605.95		606.05	0.000888	2.2	5371.68	1150.43	0.14	2.67
5 (1b+2+3)	7340	0.2-Percent	18000	594.8	606.59		606.72	0.001075	2.4	6158.43	1428.06	0.15	3.06
5 (1b+2+3)	7151	10-Percent	7990	594.7	605.89		605.91	0.000159	1.35	6966.51	1984.21	0.08	1.19
5 (1b+2+3)	7151	2-Percent	11800	594.7	605.14		605.22	0.000731	1.93	5419.84	1468.82	0.13	2.36
5 (1b+2+3)	7151	1-Percent	13600	594.7	605.62		605.7	0.000686	2	6259.99	1919.94	0.13	2.28
5 (1b+2+3)	7151	0.2-Percent	18000	594.7	606.19		606.28	0.000853	2.19	7321.21	2061.64	0.14	2.66
5 (1b+2+3)	6890	10-Percent	7990	593	605.84	599.92	605.85	0.000066	0.92	12427.56	2356.84	0.05	1.22
5 (1b+2+3)	6890	2-Percent	11800	593	604.87	600.38	604.93	0.000416	1.48	6447.47	2310.6	0.09	2.51
5 (1b+2+3)	6890	1-Percent	13600	593	605.44	600.53	605.46	0.00028	1.36	11299.96	2342.02	0.08	2.24
5 (1b+2+3)	6890	0.2-Percent	18000	593	605.95	600.96	605.98	0.000374	1.58	12453.3	2359.59	0.09	2.48
5 (1b+2+3)	6631	10-Percent	7990	592	605.55	601.18	605.73	0.002191	3.2	2415.01	1075.41	0.2	3.59
5 (1b+2+3)	6631	2-Percent	11800	592	603.88	599.88	604.39	0.002832	5.92	2161.54	733.83	0.35	1

Table 9: Flood Scenario 5 with Ice Cover HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chan
5 (1b+2+3)	6631	1-Percent	13600	592	604.51	600.36	605.05	0.002745	6.16	2418.58	783.96	0.36	1
5 (1b+2+3)	6631	0.2-Percent	18000	592	605.4	601.44	605.62	0.001144	4.27	4977.01	1044.61	0.24	1
5 (1b+2+3)	6324	10-Percent	7990	590.5	602.71	601.04	603.43	0.007181	2.87	1553.77	565.17	0.24	6.87
5 (1b+2+3)	6324	2-Percent	11800	590.5	602.73	598.1	603.06	0.001587	4.85	2596.2	568.59	0.27	1
5 (1b+2+3)	6324	1-Percent	13600	590.5	603.33	598.51	603.71	0.001657	5.19	2789.57	709.76	0.28	1
5 (1b+2+3)	6324	0.2-Percent	18000	590.5	604.5	599.38	604.83	0.001402	5.19	4195.02	826.68	0.27	1
5 (1b+2+3)	6015	10-Percent	7990	588.7	600.02		600.3	0.002737	1.62	2123.58	495.67	0.15	5.92
5 (1b+2+3)	6015	2-Percent	11800	588.7	600.97		601.43	0.003437	1.71	2457.24	503.93	0.16	6.98
5 (1b+2+3)	6015	1-Percent	13600	588.7	601.61		602.1	0.003148	1.79	2758.78	511.71	0.15	7.17
5 (1b+2+3)	6015	0.2-Percent	18000	588.7	602.97		603.47	0.002641	2.29	3575.84	692.15	0.16	6.65
5 (1b+2+3)	5607	10-Percent	7990	587.3	599.5	594.51	599.58	0.000472	1.72	3659.34	527.85	0.1	2.7
5 (1b+2+3)	5607	2-Percent	11800	587.3	600.19	595.17	600.34	0.000767	2.28	4020.58	547.16	0.13	2.83
5 (1b+2+3)	5607	1-Percent	13600	587.3	600.87	595.43	601.02	0.000772	2.41	4390.76	571.72	0.14	2.86
5 (1b+2+3)	5607	0.2-Percent	18000	587.3	602.24	596.05	602.44	0.000801	2.7	5177.87	963.67	0.14	2.94
5 (1b+2+3)	5307	10-Percent	7990	585.8	599.3		599.36	0.000321	1.91	4083.58	560.39	0.1	1.79
5 (1b+2+3)	5307	2-Percent	11800	585.8	599.81		599.93	0.000664	2.42	4258.08	572.31	0.13	2.65
5 (1b+2+3)	5307	1-Percent	13600	585.8	600.48		600.62	0.000678	2.55	4636.22	587.04	0.13	2.71
5 (1b+2+3)	5307	0.2-Percent	18000	585.8	601.85		602.01	0.000713	2.8	5652.3	1136.63	0.14	2.87
5 (1b+2+3)	5051	10-Percent	7990	584.3	599.01		599.12	0.000667	2.41	3244.59	652.53	0.13	2.5
5 (1b+2+3)	5051	2-Percent	11800	584.3	599.11		599.38	0.001802	3.37	3155.8	668.63	0.19	3.47
5 (1b+2+3)	5051	1-Percent	13600	584.3	599.79		600.07	0.001728	3.47	3640.33	860.74	0.19	3.53
5 (1b+2+3)	5051	0.2-Percent	18000	584.3	601.16		601.46	0.001605	3.63	4893.97	954.61	0.19	3.68
5 (1b+2+3)	4786	10-Percent	7990	582.8	598.58		598.71	0.00114	2.98	3101.18	805.87	0.16	3.45
5 (1b+2+3)	4786	2-Percent	11800	582.8	598.5		598.78	0.000951	4.66	3374.24	798.05	0.23	1
5 (1b+2+3)	4786	1-Percent	13600	582.8	599.19		599.48	0.000946	4.84	3945.76	880.52	0.23	1
5 (1b+2+3)	4786	0.2-Percent	18000	582.8	600.58		600.89	0.000942	5.2	5334.49	1041.25	0.24	1
5 (1b+2+3)	4582	10-Percent	7990	582.7	597.89		598.06	0.002151	3.36	2752.36	767.19	0.19	4.45
5 (1b+2+3)	4582	2-Percent	11800	582.7	598.02		598.34	0.001133	4.98	3317.88	790.35	0.25	1
5 (1b+2+3)	4582	1-Percent	13600	582.7	598.71		599.04	0.001132	5.19	3913.63	951.19	0.25	1
5 (1b+2+3)	4582	0.2-Percent	18000	582.7	600.09		600.45	0.001137	5.61	5367.14	1091.7	0.26	1
5 (1b+2+3)	4363	10-Percent	7990	582.5	596.56	592.68	596.94	0.003614	3.49	1842.22	757	0.22	5.39
5 (1b+2+3)	4363	2-Percent	11800	582.5	597.61	590.78	597.91	0.000987	4.69	2878.57	1019.34	0.23	1
5 (1b+2+3)	4363	1-Percent	13600	582.5	598.36	591.3	598.62	0.000868	4.6	4629.13	1189.78	0.22	1
5 (1b+2+3)	4363	0.2-Percent	18000	582.5	599.75	592.38	600.03	0.000869	4.96	6316.99	1244.97	0.23	1
5 (1b+2+3)	4182	10-Percent	7990	582.4	596.04	590.14	596.4	0.00246	4.88	1714.46	462.58	0.27	2.03
5 (1b+2+3)	4182	2-Percent	11800	582.4	597.14	590.55	597.66	0.001656	5.93	2176.92	640.15	0.3	1
5 (1b+2+3)	4182	1-Percent	13600	582.4	597.78	591.12	598.37	0.001766	6.37	2369.5	895.16	0.31	1
5 (1b+2+3)	4182	0.2-Percent	18000	582.4	599.29	592.48	599.8	0.001504	6.4	4712.29	1187.29	0.3	1
5 (1b+2+3)	3997	10-Percent	7990	582.3	595.56	589.65	595.93	0.002583	4.95	1665.36	282.94	0.27	2.07
5 (1b+2+3)	3997	2-Percent	11800	582.3	596.82	590.02	597.36	0.001639	5.95	2153.86	525.73	0.3	1
5 (1b+2+3)	3997	1-Percent	13600	582.3	597.41	590.59	598.04	0.001815	6.49	2326.06	800.37	0.32	1
5 (1b+2+3)	3997	0.2-Percent	18000	582.3	598.75	591.89	599.47	0.001923	7.2	3967.34	1358.02	0.33	1
5 (1b+2+3)	3670	10-Percent	7990	582.1	595.26		595.31	0.001188	2.49	5655.1	1244.35	0.15	3.88
5 (1b+2+3)	3670	2-Percent	11800	582.1	596.76		596.82	0.001013	2.8	7649.98	1351.92	0.15	3.45

Table 9: Flood Scenario 5 with Ice Cover HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chan
5 (1b+2+3)	3670	1-Percent	13600	582.1	597.4		597.46	0.001007	2.87	8503.65	1396.1	0.15	3.58
5 (1b+2+3)	3670	0.2-Percent	18000	582.1	598.79		598.86	0.000986	3	10644.42	1779.16	0.15	3.89
5 (1b+2+3)	2921	10-Percent	7990	576.6	593.85		594.11	0.002189	4.44	2558.9	954.88	0.23	3.09
5 (1b+2+3)	2921	2-Percent	11800	576.6	595.76		595.96	0.001287	4.2	5111.49	1428.92	0.2	2.55
5 (1b+2+3)	2921	1-Percent	13600	576.6	596.51		596.67	0.001055	4.08	6201.24	1444.71	0.19	2.39
5 (1b+2+3)	2921	0.2-Percent	18000	576.6	598.06		598.19	0.000785	3.94	8928.85	2136.62	0.17	2.19
5 (1b+2+3)	1922	10-Percent	7990	573.7	593.54		593.58	0.000196	2.09	8257.98	1344.43	0.09	1.45
5 (1b+2+3)	1922	2-Percent	11800	573.7	595.49		595.52	0.000184	2.27	10949.93	1463.03	0.1	1.38
5 (1b+2+3)	1922	1-Percent	13600	573.7	596.23		596.27	0.000186	2.36	12141.66	1693.19	0.1	1.39
5 (1b+2+3)	1922	0.2-Percent	18000	573.7	597.78		597.82	0.000192	2.53	14988.84	1884.17	0.1	1.42
5 (1b+2+3)	833	10-Percent	7990	571.5	593.39		593.42	0.000106	2.01	7051.55	1516.47	0.08	1
5 (1b+2+3)	833	2-Percent	11800	571.5	595.34		595.38	0.000099	2.1	10374.31	1805.97	0.08	1
5 (1b+2+3)	833	1-Percent	13600	571.5	596.09		596.12	0.000098	2.14	11779.88	2068.75	0.08	1
5 (1b+2+3)	833	0.2-Percent	18000	571.5	597.64		597.68	0.000096	2.24	15564.63	2543.58	0.08	1
5 (1b+2+3)	279	10-Percent	7990	571	593.27	581.03	593.33	0.00012	2.35	5948.74	1083.92	0.1	1
5 (1b+2+3)	279	2-Percent	11800	571	595.23	582.78	595.29	0.00012	2.53	8758.64	2173.18	0.1	1
5 (1b+2+3)	279	1-Percent	13600	571	595.98	583.49	596.04	0.00012	2.6	10421.48	2286.34	0.1	1
5 (1b+2+3)	279	0.2-Percent	18000	571	597.53	585.08	597.59	0.00012	2.73	14338.36	2771.69	0.11	1

## Flood Scenario #6 with Ice Cover

**Flood Bench Configuration: 2 + 3 + 4**

Plan: UPDATE-FB-2+3+4-UNION+CLINT+UTILI-ICE

Geometry: UPDATE-FB-2+3+4-UNION+CLINT+UTILI-ICE

Steady Flow Data: USGS BF,10,2,1,0.2-PERCENT-UPDATE-BC

Date: December 2022




Figure 34: Flood Scenario #6 (2+3+4) with Ice Cover Profile Plot

Table 10: Flood Scenario 6 with Ice Cover HEC-RAS Output

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.ChnL	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chan
6 (2+3+4)	20483	10-Percent	7990	621.4	631.44		632.23	0.00152	7.14	1149.93	159.75	0.42	
6 (2+3+4)	20483	2-Percent	11800	621.4	633.13		634.27	0.001801	8.71	1502.7	283.71	0.47	
6 (2+3+4)	20483	1-Percent	13600	621.4	633.75		635.03	0.001907	9.3	1683.2	292.19	0.49	
6 (2+3+4)	20483	0.2-Percent	18000	621.4	635.05		636.62	0.002117	10.53	2068.77	300.59	0.52	
6 (2+3+4)	19313	10-Percent	7990	620.4	628.71		629.8	0.002908	8.44	1044.14	306.61	0.56	
6 (2+3+4)	19313	2-Percent	11800	620.4	630.2		631.56	0.003003	9.73	1584.78	383.6	0.58	
6 (2+3+4)	19313	1-Percent	13600	620.4	630.82		632.26	0.00298	10.15	1839.24	441.9	0.59	
6 (2+3+4)	19313	0.2-Percent	18000	620.4	632.19	630.62	633.75	0.002869	10.92	2526.99	588.7	0.59	
6 (2+3+4)	18244	10-Percent	7990	617.6	626.65		627.29	0.001757	6.95	1777.22	467.86	0.44	
6 (2+3+4)	18244	2-Percent	11800	617.6	628.34		629.05	0.001639	7.65	2591.04	496.46	0.44	
6 (2+3+4)	18244	1-Percent	13600	617.6	629.04		629.77	0.001595	7.91	2943.68	525.83	0.44	
6 (2+3+4)	18244	0.2-Percent	18000	617.6	630.58		631.36	0.001502	8.43	3818.3	582.92	0.43	
6 (2+3+4)	17053	10-Percent	7990	615.5	624.35		625.09	0.001916	7.31	1642.13	449.92	0.46	
6 (2+3+4)	17053	2-Percent	11800	615.5	625.99		626.9	0.001962	8.38	2446.6	516.1	0.48	
6 (2+3+4)	17053	1-Percent	13600	615.5	626.66		627.64	0.001967	8.79	2801.06	526.03	0.49	
6 (2+3+4)	17053	0.2-Percent	18000	615.5	628.2		629.3	0.001933	9.57	3631.81	561.22	0.49	
6 (2+3+4)	15751	10-Percent	7990	612.8	621.5		622.32	0.002353	7.63	1281.07	298.43	0.5	
6 (2+3+4)	15751	2-Percent	11800	612.8	623.1		624.11	0.002331	8.68	1817.84	352.78	0.52	
6 (2+3+4)	15751	1-Percent	13600	612.8	623.84		624.9	0.00225	8.99	2082.15	364.34	0.51	
6 (2+3+4)	15751	0.2-Percent	18000	612.8	625.58		626.72	0.002028	9.55	2728.72	378.1	0.5	
6 (2+3+4)	14403	10-Percent	7990	610.3	619.62		620	0.001192	5.74	2433.48	541.73	0.36	
6 (2+3+4)	14403	2-Percent	11800	610.3	621.69		622.05	0.000914	5.87	3595.56	583.34	0.33	
6 (2+3+4)	14403	1-Percent	13600	610.3	622.61		622.96	0.000824	5.91	4153.44	638.03	0.32	
6 (2+3+4)	14403	0.2-Percent	18000	610.3	624.77		625.08	0.000624	5.8	5658.8	747.06	0.28	
6 (2+3+4)	12986	10-Percent	7990	608.9	618.23		618.6	0.000827	5.21	2427.79	736.39	0.31	
6 (2+3+4)	12986	2-Percent	11800	608.9	620.65		620.99	0.000619	5.29	4558.45	922.4	0.28	
6 (2+3+4)	12986	1-Percent	13600	608.9	621.69		622.01	0.00055	5.29	5527.88	947.91	0.27	
6 (2+3+4)	12986	0.2-Percent	18000	608.9	624.05		624.34	0.000438	5.3	7816	999.73	0.24	
6 (2+3+4)	12162	10-Percent	7990	604.9	617.03		617.77	0.001141	6.98	1207.64	135.14	0.37	
6 (2+3+4)	12162	2-Percent	11800	604.9	619.08		620.18	0.001369	8.55	1649.94	403.2	0.42	
6 (2+3+4)	12162	1-Percent	13600	604.9	620.09		621.25	0.001344	8.9	2099.93	463.56	0.42	
6 (2+3+4)	12162	0.2-Percent	18000	604.9	622.63		623.71	0.001115	9.05	3575.52	731.23	0.39	
6 (2+3+4)	11955	10-Percent	7990	605.5	616.8	611.72	617.53	0.001175	6.85	1177.32	116.61	0.37	
6 (2+3+4)	11955	2-Percent	11800	605.5	618.78	613.35	619.89	0.001432	8.48	1413.81	149.68	0.42	
6 (2+3+4)	11955	1-Percent	13600	605.5	619.66	614.06	620.94	0.001509	9.11	1521.73	162.38	0.44	
6 (2+3+4)	11955	0.2-Percent	18000	605.5	621.72	615.65	623.38	0.001623	10.39	1775.85	332.07	0.47	
6 (2+3+4)	11860 Union Rd	Bridge											
6 (2+3+4)	11789	10-Percent	7990	605.5	616.22	612.39	617.18	0.002926	7.85	1022.56	112.37	0.45	1
6 (2+3+4)	11789	2-Percent	11800	605.5	617.95	614.02	619.43	0.003604	9.76	1223.19	119.72	0.52	1
6 (2+3+4)	11789	1-Percent	13600	605.5	618.61	614.75	620.34	0.003942	10.61	1302.55	123.38	0.55	1
6 (2+3+4)	11789	0.2-Percent	18000	605.5	619.93	616.38	622.35	0.004784	12.55	1465.7	153.18	0.61	1
6 (2+3+4)	11675	10-Percent	7990	602.4	616.13		616.7	0.00209	6.08	1336.33	130.41	0.32	1
6 (2+3+4)	11675	2-Percent	11800	602.4	617.88		618.8	0.002688	7.72	1568.97	139.64	0.38	1
6 (2+3+4)	11675	1-Percent	13600	602.4	618.53		619.63	0.00298	8.46	1664.11	150.55	0.41	1

Table 10: Flood Scenario 6 with Ice Cover HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.ChnL	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chan
6 (2+3+4)	11675	0.2-Percent	18000	602.4	619.89		621.44	0.003656	10.09	1943.7	306.49	0.46	1
6 (2+3+4)	10302	10-Percent	7990	603.2	612.45		613	0.0036	6.21	1619.77	503.92	0.39	1
6 (2+3+4)	10302	2-Percent	11800	603.2	613.64		614.32	0.003899	7.21	2288.52	591.17	0.42	1
6 (2+3+4)	10302	1-Percent	13600	603.2	614.11		614.83	0.003958	7.55	2569.57	601.71	0.43	1
6 (2+3+4)	10302	0.2-Percent	18000	603.2	615.12		615.93	0.004057	8.27	3193.56	623.23	0.45	1
6 (2+3+4)	9372	10-Percent	7990	599.6	610.22		610.55	0.00192	4.96	1968.41	595.77	0.29	1
6 (2+3+4)	9372	2-Percent	11800	599.6	611.43		611.79	0.001875	5.41	2702.89	613.78	0.3	1
6 (2+3+4)	9372	1-Percent	13600	599.6	611.92		612.3	0.00185	5.58	3008.73	631.18	0.3	1
6 (2+3+4)	9372	0.2-Percent	18000	599.6	613.05		613.45	0.001735	5.84	3799.82	862.08	0.3	1
6 (2+3+4)	8312	10-Percent	7990	595.5	607.26		607.37	0.005054	0.81	3156.52	751.86	0.12	10.57
6 (2+3+4)	8312	2-Percent	11800	595.5	608.22		608.39	0.006419	0.78	3693.43	760.17	0.12	11.82
6 (2+3+4)	8312	1-Percent	13600	595.5	608.7		608.9	0.006578	0.87	4016.16	768.49	0.13	12.15
6 (2+3+4)	8312	0.2-Percent	18000	595.5	610.12		610.34	0.00573	1.21	5068.75	801	0.14	12.54
6 (2+3+4)	8145	10-Percent	7990	592.1	606.06	601.39	606.45	0.005684	5	1596.51	347.92	0.3	4.63
6 (2+3+4)	8145	2-Percent	11800	592.1	607.47	599.89	607.86	0.001739	5.01	2357.63	455.44	0.25	1.76
6 (2+3+4)	8145	1-Percent	13600	592.1	608.09	599.7	608.51	0.001072	5.22	2603.44	468.87	0.25	1
6 (2+3+4)	8145	0.2-Percent	18000	592.1	609.24	600.82	609.87	0.001414	6.38	2820.33	493.79	0.29	1
6 (2+3+4)	8049 Railroad Bridge	Bridge											
6 (2+3+4)	7984	10-Percent	7990	592.1	605.77	600.46	606.17	0.00183	5.07	1600.17	385.35	0.29	1
6 (2+3+4)	7984	2-Percent	11800	592.1	606.91	601.79	607.59	0.002627	6.63	1808.83	521.53	0.36	1
6 (2+3+4)	7984	1-Percent	13600	592.1	607.38	602.36	608.19	0.002986	7.31	1894.16	534.03	0.39	1
6 (2+3+4)	7984	0.2-Percent	18000	592.1	608.19	603.64	609.41	0.004025	8.97	2046.77	566.8	0.46	1
6 (2+3+4)	7758	10-Percent	7990	595	605.21	602.8	605.34	0.001489	1.89	3005.59	782.96	0.14	4.12
6 (2+3+4)	7758	2-Percent	11800	595	606.26	603.59	606.46	0.001755	1.78	3576.24	887.7	0.14	5.58
6 (2+3+4)	7758	1-Percent	13600	595	606.69	603.92	606.92	0.001867	1.7	3799.77	918.48	0.13	6.29
6 (2+3+4)	7758	0.2-Percent	18000	595	607.57	604.55	607.83	0.00184	1.51	4772.88	1153.52	0.12	7.55
6 (2+3+4)	7564	10-Percent	7990	594.9	604.62		604.73	0.001413	2.14	3101.63	771.08	0.15	3.17
6 (2+3+4)	7564	2-Percent	11800	594.9	605.6		605.76	0.001548	2.31	3861.29	902.63	0.16	3.63
6 (2+3+4)	7564	1-Percent	13600	594.9	606.02		606.19	0.00158	2.36	4216.54	949.83	0.16	3.83
6 (2+3+4)	7564	0.2-Percent	18000	594.9	606.88		607.09	0.001641	2.5	5080.98	1220.47	0.16	4.18
6 (2+3+4)	7340	10-Percent	7990	594.8	604.05		604.15	0.001386	2.03	3296.18	998.24	0.15	3
6 (2+3+4)	7340	2-Percent	11800	594.8	605.03		605.15	0.001369	2.21	4295.66	1071.75	0.15	3.19
6 (2+3+4)	7340	1-Percent	13600	594.8	605.44		605.58	0.001334	2.28	4741.93	1087.49	0.15	3.24
6 (2+3+4)	7340	0.2-Percent	18000	594.8	606.31		606.47	0.00132	2.43	5730.26	1361.64	0.16	3.38
6 (2+3+4)	7151	10-Percent	7990	594.7	603.39		603.49	0.001538	1.84	3309.61	990.7	0.15	3.1
6 (2+3+4)	7151	2-Percent	11800	594.7	604.39		604.51	0.001447	2.04	4338.09	1124.58	0.15	3.19
6 (2+3+4)	7151	1-Percent	13600	594.7	604.84		604.97	0.001355	2.12	4875.72	1253.54	0.15	3.17
6 (2+3+4)	7151	0.2-Percent	18000	594.7	605.76		605.89	0.001201	2.28	6400.81	1963.41	0.15	3.07
6 (2+3+4)	6890	10-Percent	7990	593	602.77	600.02	602.85	0.000988	1.46	3913.8	2109.53	0.12	3.22
6 (2+3+4)	6890	2-Percent	11800	593	603.83	600.44	603.92	0.000885	1.62	5154.88	2175.21	0.12	3.23
6 (2+3+4)	6890	1-Percent	13600	593	604.32	600.62	604.42	0.00082	1.69	5747.41	2226.76	0.12	3.19
6 (2+3+4)	6890	0.2-Percent	18000	593	605.44	600.97	605.48	0.000503	1.62	11265.95	2341.95	0.1	2.83
6 (2+3+4)	6631	10-Percent	7990	592	602.09	599.33	602.19	0.001339	1.66	3305.29	858.83	0.13	3.32
6 (2+3+4)	6631	2-Percent	11800	592	603.18	599.83	603.31	0.00129	1.91	4233.21	866.43	0.14	3.38

Table 10: Flood Scenario 6 with Ice Cover HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.ChnL	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chan
6 (2+3+4)	6631	1-Percent	13600	592	603.71	600.02	603.85	0.001208	2.01	4700.21	868.64	0.14	3.34
6 (2+3+4)	6631	0.2-Percent	18000	592	604.91	600.41	605.07	0.001045	2.26	5812.83	986.82	0.14	3.09
6 (2+3+4)	6324	10-Percent	7990	590.5	601.3	598.08	601.4	0.001236	1.92	3215.23	670.63	0.14	3.5
6 (2+3+4)	6324	2-Percent	11800	590.5	602.28	598.68	602.45	0.00152	2.21	3798.61	673.88	0.15	3.94
6 (2+3+4)	6324	1-Percent	13600	590.5	602.86	598.88	603.04	0.001442	2.32	4189.84	676.23	0.15	3.92
6 (2+3+4)	6324	0.2-Percent	18000	590.5	604.14	599.4	604.35	0.001301	2.53	5175.72	835.42	0.15	3.91
6 (2+3+4)	6015	10-Percent	7990	588.7	600.47		600.59	0.001039	2.13	2985.25	536.42	0.14	2.84
6 (2+3+4)	6015	2-Percent	11800	588.7	600.96		601.21	0.001967	2.59	3126.08	539.72	0.18	3.75
6 (2+3+4)	6015	1-Percent	13600	588.7	601.6		601.87	0.001828	2.7	3477.05	544.1	0.17	3.74
6 (2+3+4)	6015	0.2-Percent	18000	588.7	602.97		603.28	0.001689	2.95	4258.62	715.22	0.18	3.83
6 (2+3+4)	5607	10-Percent	7990	587.3	600.15	594.17	600.21	0.000303	1.8	4128.8	546.2	0.1	1.67
6 (2+3+4)	5607	2-Percent	11800	587.3	600.24	595.12	600.38	0.000729	2.32	4075.45	548.18	0.13	2.63
6 (2+3+4)	5607	1-Percent	13600	587.3	600.9	595.38	601.05	0.00074	2.45	4439.49	573.77	0.14	2.67
6 (2+3+4)	5607	0.2-Percent	18000	587.3	602.27	596	602.46	0.000778	2.72	5217.2	972.57	0.14	2.81
6 (2+3+4)	5307	10-Percent	7990	585.8	600.01		600.06	0.000232	1.76	4507.28	575.81	0.09	1.66
6 (2+3+4)	5307	2-Percent	11800	585.8	599.88		600	0.000626	2.44	4320.93	573.49	0.13	2.47
6 (2+3+4)	5307	1-Percent	13600	585.8	600.53		600.66	0.000648	2.57	4687.92	587.54	0.13	2.56
6 (2+3+4)	5307	0.2-Percent	18000	585.8	601.89		602.05	0.000688	2.83	5723.75	1168.93	0.14	2.72
6 (2+3+4)	5051	10-Percent	7990	584.3	599.68		599.81	0.001248	3.15	2947.68	766.44	0.17	3.06
6 (2+3+4)	5051	2-Percent	11800	584.3	599.21		599.54	0.001187	4.87	2949.37	664.88	0.25	1
6 (2+3+4)	5051	1-Percent	13600	584.3	599.85		600.2	0.001188	5.08	3421.59	872.11	0.25	1
6 (2+3+4)	5051	0.2-Percent	18000	584.3	601.21		601.57	0.001159	5.44	4655.39	935.59	0.26	1
6 (2+3+4)	4786	10-Percent	7990	582.8	599.01		599.13	0.001702	3.2	3041.99	845.08	0.18	4.56
6 (2+3+4)	4786	2-Percent	11800	582.8	598.68		599.01	0.001074	5	3254.57	817.09	0.24	1
6 (2+3+4)	4786	1-Percent	13600	582.8	599.33		599.67	0.001074	5.19	3806.97	913.8	0.25	1
6 (2+3+4)	4786	0.2-Percent	18000	582.8	600.7		601.05	0.001047	5.52	5198.36	1042.57	0.25	1
6 (2+3+4)	4582	10-Percent	7990	582.7	597.88		598.08	0.00399	4.04	2406.54	751.32	0.24	5.27
6 (2+3+4)	4582	2-Percent	11800	582.7	598.14		598.51	0.001268	5.31	3182.46	816.12	0.26	1
6 (2+3+4)	4582	1-Percent	13600	582.7	598.78		599.17	0.001283	5.55	3751.86	977.87	0.27	1
6 (2+3+4)	4582	0.2-Percent	18000	582.7	600.15		600.56	0.001276	5.97	5198.81	1093.15	0.27	1
6 (2+3+4)	4363	10-Percent	7990	582.5	596.49	590.48	596.82	0.002462	4.75	1790.51	742.9	0.26	2.34
6 (2+3+4)	4363	2-Percent	11800	582.5	597.48	590.61	597.95	0.001487	5.72	2365.98	945.93	0.28	1
6 (2+3+4)	4363	1-Percent	13600	582.5	598.28	591.23	598.66	0.001234	5.46	4087.63	1174.9	0.26	1
6 (2+3+4)	4363	0.2-Percent	18000	582.5	599.68	592.56	600.06	0.001166	5.73	5787.43	1242.03	0.26	1
6 (2+3+4)	4182	10-Percent	7990	582.4	596.03	590.04	596.39	0.002329	4.85	1726.56	461.73	0.27	1.93
6 (2+3+4)	4182	2-Percent	11800	582.4	597.14	590.55	597.66	0.001656	5.93	2176.92	640.15	0.3	1
6 (2+3+4)	4182	1-Percent	13600	582.4	597.78	591.12	598.37	0.001766	6.37	2369.5	895.16	0.31	1
6 (2+3+4)	4182	0.2-Percent	18000	582.4	599.29	592.48	599.8	0.001504	6.4	4713	1187.31	0.3	1
6 (2+3+4)	3997	10-Percent	7990	582.3	595.56	589.65	595.93	0.002585	4.95	1664.97	282.91	0.27	2.07
6 (2+3+4)	3997	2-Percent	11800	582.3	596.82	590.02	597.36	0.001639	5.95	2153.86	525.73	0.3	1
6 (2+3+4)	3997	1-Percent	13600	582.3	597.41	590.59	598.04	0.001815	6.49	2326.06	800.37	0.32	1
6 (2+3+4)	3997	0.2-Percent	18000	582.3	598.75	591.89	599.47	0.001923	7.2	3968.22	1358.12	0.33	1
6 (2+3+4)	3670	10-Percent	7990	582.1	595.26		595.31	0.001186	2.49	5655.56	1244.31	0.15	3.87
6 (2+3+4)	3670	2-Percent	11800	582.1	596.76		596.82	0.001013	2.8	7649.98	1351.92	0.15	3.45

Table 10: Flood Scenario 6 with Ice Cover HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chan
6 (2+3+4)	3670	1-Percent	13600	582.1	597.4		597.46	0.001007	2.87	8503.65	1396.1	0.15	3.58
6 (2+3+4)	3670	0.2-Percent	18000	582.1	598.79		598.86	0.000987	3	10643.85	1779.37	0.15	3.9
6 (2+3+4)	2921	10-Percent	7990	576.6	593.85		594.11	0.002187	4.44	2559.96	955.18	0.23	3.09
6 (2+3+4)	2921	2-Percent	11800	576.6	595.76		595.96	0.001287	4.2	5111.49	1428.92	0.2	2.55
6 (2+3+4)	2921	1-Percent	13600	576.6	596.51		596.67	0.001055	4.08	6201.24	1444.71	0.19	2.39
6 (2+3+4)	2921	0.2-Percent	18000	576.6	598.06		598.19	0.000785	3.94	8928.85	2136.62	0.17	2.19
6 (2+3+4)	1922	10-Percent	7990	573.7	593.54		593.58	0.000197	2.08	8257.55	1344.43	0.09	1.46
6 (2+3+4)	1922	2-Percent	11800	573.7	595.49		595.52	0.000184	2.27	10949.93	1463.03	0.1	1.38
6 (2+3+4)	1922	1-Percent	13600	573.7	596.23		596.27	0.000186	2.36	12141.66	1693.19	0.1	1.39
6 (2+3+4)	1922	0.2-Percent	18000	573.7	597.78		597.82	0.000192	2.53	14988.84	1884.17	0.1	1.42
6 (2+3+4)	833	10-Percent	7990	571.5	593.39		593.42	0.000106	2.01	7051.55	1516.47	0.08	1
6 (2+3+4)	833	2-Percent	11800	571.5	595.34		595.38	0.000099	2.1	10374.31	1805.97	0.08	1
6 (2+3+4)	833	1-Percent	13600	571.5	596.09		596.12	0.000098	2.14	11779.88	2068.75	0.08	1
6 (2+3+4)	833	0.2-Percent	18000	571.5	597.64		597.68	0.000096	2.24	15564.63	2543.58	0.08	1
6 (2+3+4)	279	10-Percent	7990	571	593.27	581.03	593.33	0.00012	2.35	5948.74	1083.92	0.1	1
6 (2+3+4)	279	2-Percent	11800	571	595.23	582.78	595.29	0.00012	2.53	8758.64	2173.18	0.1	1
6 (2+3+4)	279	1-Percent	13600	571	595.98	583.49	596.04	0.00012	2.6	10421.48	2286.34	0.1	1
6 (2+3+4)	279	0.2-Percent	18000	571	597.53	585.08	597.59	0.00012	2.73	14338.36	2771.69	0.11	1

## Flood Scenario #7 with Ice Cover

**Flood Bench Configuration:** 1b + 2 + 3 + 4

Plan: UPDATE-FB-1b+2+3+4-SCH+UNION+CLINT+UTILI-ICE

Geometry: UPDATE-FB-1b+2+3+4-SCH+UNION+CLINT+UTILI-ICE

Steady Flow Data: USGS BF,10,2,1,0.2-PERCENT-UPDATE-BC

Date: December 2022




Figure 35: Flood Scenario #7 (1b+2+3+4) with Ice Cover Profile Plot

Table 11: Flood Scenario 7 with Ice Cover HEC-RAS Output

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.ChnL	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chan
7 (1b+2+3+4)	20483	10-Percent	7990	621.4	631.44		632.23	0.00152	7.14	1149.93	159.75	0.42	
7 (1b+2+3+4)	20483	2-Percent	11800	621.4	633.13		634.27	0.001801	8.71	1502.7	283.71	0.47	
7 (1b+2+3+4)	20483	1-Percent	13600	621.4	633.75		635.03	0.001907	9.3	1683.2	292.19	0.49	
7 (1b+2+3+4)	20483	0.2-Percent	18000	621.4	635.05		636.62	0.002117	10.53	2068.77	300.59	0.52	
7 (1b+2+3+4)	19313	10-Percent	7990	620.4	628.71		629.8	0.002908	8.44	1044.14	306.61	0.56	
7 (1b+2+3+4)	19313	2-Percent	11800	620.4	630.2		631.56	0.003003	9.73	1584.78	383.6	0.58	
7 (1b+2+3+4)	19313	1-Percent	13600	620.4	630.82		632.26	0.00298	10.15	1839.24	441.9	0.59	
7 (1b+2+3+4)	19313	0.2-Percent	18000	620.4	632.19	630.62	633.75	0.002869	10.92	2526.99	588.7	0.59	
7 (1b+2+3+4)	18244	10-Percent	7990	617.6	626.65		627.29	0.001757	6.95	1777.22	467.86	0.44	
7 (1b+2+3+4)	18244	2-Percent	11800	617.6	628.34		629.05	0.001639	7.65	2591.04	496.46	0.44	
7 (1b+2+3+4)	18244	1-Percent	13600	617.6	629.04		629.77	0.001595	7.91	2943.68	525.83	0.44	
7 (1b+2+3+4)	18244	0.2-Percent	18000	617.6	630.58		631.36	0.001502	8.43	3818.3	582.92	0.43	
7 (1b+2+3+4)	17053	10-Percent	7990	615.5	624.35		625.09	0.001916	7.31	1642.13	449.92	0.46	
7 (1b+2+3+4)	17053	2-Percent	11800	615.5	625.99		626.9	0.001962	8.38	2446.6	516.1	0.48	
7 (1b+2+3+4)	17053	1-Percent	13600	615.5	626.66		627.64	0.001967	8.79	2801.06	526.03	0.49	
7 (1b+2+3+4)	17053	0.2-Percent	18000	615.5	628.2		629.3	0.001933	9.57	3631.81	561.22	0.49	
7 (1b+2+3+4)	15751	10-Percent	7990	612.8	621.5		622.32	0.002353	7.63	1281.07	298.43	0.5	
7 (1b+2+3+4)	15751	2-Percent	11800	612.8	623.1		624.11	0.002331	8.68	1817.84	352.78	0.52	
7 (1b+2+3+4)	15751	1-Percent	13600	612.8	623.84		624.9	0.00225	8.99	2082.15	364.34	0.51	
7 (1b+2+3+4)	15751	0.2-Percent	18000	612.8	625.58		626.72	0.002028	9.55	2728.72	378.1	0.5	
7 (1b+2+3+4)	14403	10-Percent	7990	610.3	619.62		620	0.001192	5.74	2433.48	541.73	0.36	
7 (1b+2+3+4)	14403	2-Percent	11800	610.3	621.69		622.05	0.000914	5.87	3595.56	583.34	0.33	
7 (1b+2+3+4)	14403	1-Percent	13600	610.3	622.61		622.96	0.000824	5.91	4153.44	638.03	0.32	
7 (1b+2+3+4)	14403	0.2-Percent	18000	610.3	624.77		625.08	0.000624	5.8	5658.8	747.06	0.28	
7 (1b+2+3+4)	12986	10-Percent	7990	608.9	618.23		618.6	0.000827	5.21	2427.79	736.39	0.31	
7 (1b+2+3+4)	12986	2-Percent	11800	608.9	620.65		620.99	0.000619	5.29	4558.45	922.4	0.28	
7 (1b+2+3+4)	12986	1-Percent	13600	608.9	621.69		622.01	0.00055	5.29	5527.88	947.91	0.27	
7 (1b+2+3+4)	12986	0.2-Percent	18000	608.9	624.05		624.34	0.000438	5.3	7816	999.73	0.24	
7 (1b+2+3+4)	12162	10-Percent	7990	604.9	617.03		617.77	0.001141	6.98	1207.64	135.14	0.37	
7 (1b+2+3+4)	12162	2-Percent	11800	604.9	619.08		620.18	0.001369	8.55	1649.94	403.2	0.42	
7 (1b+2+3+4)	12162	1-Percent	13600	604.9	620.09		621.25	0.001344	8.9	2099.93	463.56	0.42	
7 (1b+2+3+4)	12162	0.2-Percent	18000	604.9	622.63		623.71	0.001115	9.05	3575.52	731.23	0.39	
7 (1b+2+3+4)	11955	10-Percent	7990	605.5	616.8	611.72	617.53	0.001175	6.85	1177.32	116.61	0.37	
7 (1b+2+3+4)	11955	2-Percent	11800	605.5	618.78	613.35	619.89	0.001432	8.48	1413.81	149.68	0.42	
7 (1b+2+3+4)	11955	1-Percent	13600	605.5	619.66	614.06	620.94	0.001509	9.11	1521.73	162.38	0.44	
7 (1b+2+3+4)	11955	0.2-Percent	18000	605.5	621.72	615.65	623.38	0.001623	10.39	1775.85	332.07	0.47	
7 (1b+2+3+4)	11860 Union Rd	Bridge											
7 (1b+2+3+4)	11789	10-Percent	7990	605.5	616.22	612.39	617.18	0.002926	7.85	1022.56	112.37	0.45	1
7 (1b+2+3+4)	11789	2-Percent	11800	605.5	617.95	614.02	619.43	0.003604	9.76	1223.19	119.72	0.52	1
7 (1b+2+3+4)	11789	1-Percent	13600	605.5	618.61	614.75	620.34	0.003942	10.61	1302.55	123.38	0.55	1
7 (1b+2+3+4)	11789	0.2-Percent	18000	605.5	619.93	616.38	622.35	0.004784	12.55	1465.7	153.18	0.61	1
7 (1b+2+3+4)	11675	10-Percent	7990	602.4	616.13		616.7	0.00209	6.08	1336.33	130.41	0.32	1
7 (1b+2+3+4)	11675	2-Percent	11800	602.4	617.88		618.8	0.002688	7.72	1568.97	139.64	0.38	1
7 (1b+2+3+4)	11675	1-Percent	13600	602.4	618.53		619.63	0.00298	8.46	1664.11	150.55	0.41	1

Table 11: Flood Scenario 7 with Ice Cover HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chan
7 (1b+2+3+4)	11675	0.2-Percent	18000	602.4	619.89		621.44	0.003656	10.09	1943.7	306.49	0.46	1
7 (1b+2+3+4)	10302	10-Percent	7990	603.2	612.45		613	0.0036	6.21	1619.77	503.92	0.39	1
7 (1b+2+3+4)	10302	2-Percent	11800	603.2	613.64		614.32	0.003899	7.21	2288.52	591.17	0.42	1
7 (1b+2+3+4)	10302	1-Percent	13600	603.2	614.11		614.83	0.003958	7.55	2569.53	601.71	0.43	1
7 (1b+2+3+4)	10302	0.2-Percent	18000	603.2	615.12		615.93	0.004057	8.27	3193.56	623.23	0.45	1
7 (1b+2+3+4)	9372	10-Percent	7990	599.6	610.22		610.55	0.00192	4.96	1968.37	595.77	0.29	1
7 (1b+2+3+4)	9372	2-Percent	11800	599.6	611.43		611.79	0.001875	5.41	2702.93	613.78	0.3	1
7 (1b+2+3+4)	9372	1-Percent	13600	599.6	611.92		612.3	0.00185	5.58	3008.69	631.17	0.3	1
7 (1b+2+3+4)	9372	0.2-Percent	18000	599.6	613.05		613.45	0.001735	5.84	3799.87	862.17	0.3	1
7 (1b+2+3+4)	8312	10-Percent	7990	595.5	607.26		607.37	0.005055	0.81	3156.19	751.86	0.12	10.57
7 (1b+2+3+4)	8312	2-Percent	11800	595.5	608.22		608.39	0.006419	0.78	3693.34	760.17	0.12	11.82
7 (1b+2+3+4)	8312	1-Percent	13600	595.5	608.7		608.9	0.006578	0.87	4016.07	768.49	0.13	12.15
7 (1b+2+3+4)	8312	0.2-Percent	18000	595.5	610.12		610.34	0.00573	1.21	5068.85	801.01	0.14	12.54
7 (1b+2+3+4)	8145	10-Percent	7990	592.1	606.06	601.39	606.45	0.005683	5	1596.52	347.91	0.3	4.63
7 (1b+2+3+4)	8145	2-Percent	11800	592.1	607.47	599.89	607.86	0.001738	5	2357.67	455.43	0.25	1.76
7 (1b+2+3+4)	8145	1-Percent	13600	592.1	608.09	599.7	608.51	0.001072	5.22	2603.42	468.87	0.25	1
7 (1b+2+3+4)	8145	0.2-Percent	18000	592.1	609.24	600.82	609.87	0.001414	6.38	2820.32	493.79	0.29	1
7 (1b+2+3+4)	8049 Railroad Bridge	Bridge											
7 (1b+2+3+4)	7984	10-Percent	7990	592.1	605.77	600.46	606.16	0.00183	5.07	1600.08	385.29	0.29	1
7 (1b+2+3+4)	7984	2-Percent	11800	592.1	606.91	601.79	607.59	0.002627	6.63	1808.82	521.53	0.36	1
7 (1b+2+3+4)	7984	1-Percent	13600	592.1	607.37	602.36	608.19	0.002986	7.31	1894.14	534.03	0.39	1
7 (1b+2+3+4)	7984	0.2-Percent	18000	592.1	608.19	603.64	609.41	0.004025	8.97	2046.75	566.8	0.46	1
7 (1b+2+3+4)	7758	10-Percent	7990	595	605.21	602.81	605.34	0.00149	1.89	3004.72	782.81	0.14	4.12
7 (1b+2+3+4)	7758	2-Percent	11800	595	606.26	603.59	606.46	0.001756	1.78	3576.05	887.7	0.14	5.58
7 (1b+2+3+4)	7758	1-Percent	13600	595	606.69	603.91	606.92	0.001867	1.7	3799.64	918.47	0.13	6.29
7 (1b+2+3+4)	7758	0.2-Percent	18000	595	607.57	604.55	607.83	0.00184	1.51	4772.3	1153.37	0.12	7.56
7 (1b+2+3+4)	7564	10-Percent	7990	594.9	604.62		604.72	0.001419	2.14	3098.17	770.84	0.15	3.17
7 (1b+2+3+4)	7564	2-Percent	11800	594.9	605.6		605.76	0.001548	2.31	3860.89	902.54	0.16	3.63
7 (1b+2+3+4)	7564	1-Percent	13600	594.9	606.02		606.19	0.001581	2.36	4216.24	949.79	0.16	3.83
7 (1b+2+3+4)	7564	0.2-Percent	18000	594.9	606.88		607.09	0.001642	2.5	5079.85	1220.21	0.16	4.18
7 (1b+2+3+4)	7340	10-Percent	7990	594.8	604.04		604.14	0.001397	2.03	3288.18	997.54	0.15	3.01
7 (1b+2+3+4)	7340	2-Percent	11800	594.8	605.03		605.15	0.00137	2.21	4294.68	1071.7	0.15	3.19
7 (1b+2+3+4)	7340	1-Percent	13600	594.8	605.44		605.58	0.001335	2.28	4741.35	1087.47	0.15	3.24
7 (1b+2+3+4)	7340	0.2-Percent	18000	594.8	606.31		606.47	0.001321	2.43	5728.14	1361.18	0.16	3.38
7 (1b+2+3+4)	7151	10-Percent	7990	594.7	603.37		603.47	0.001567	1.84	3290.74	990	0.15	3.11
7 (1b+2+3+4)	7151	2-Percent	11800	594.7	604.38		604.51	0.001447	2.04	4337.31	1124.52	0.15	3.19
7 (1b+2+3+4)	7151	1-Percent	13600	594.7	604.84		604.97	0.001357	2.12	4874.46	1253.22	0.15	3.17
7 (1b+2+3+4)	7151	0.2-Percent	18000	594.7	605.76		605.89	0.001204	2.28	6395.38	1962.9	0.15	3.08
7 (1b+2+3+4)	6890	10-Percent	7990	593	602.74	600.03	602.81	0.001026	1.47	3867.97	2105.8	0.12	3.24
7 (1b+2+3+4)	6890	2-Percent	11800	593	603.83	600.45	603.92	0.000887	1.62	5152.66	2175.03	0.12	3.23
7 (1b+2+3+4)	6890	1-Percent	13600	593	604.32	600.62	604.42	0.000821	1.69	5745	2226.68	0.12	3.19
7 (1b+2+3+4)	6890	0.2-Percent	18000	593	605.44	600.96	605.48	0.000505	1.62	11256.27	2341.79	0.1	2.84
7 (1b+2+3+4)	6631	10-Percent	7990	592	602.02	599.34	602.13	0.001433	1.69	3237.53	857.65	0.14	3.35
7 (1b+2+3+4)	6631	2-Percent	11800	592	603.17	599.84	603.31	0.001293	1.91	4229.69	866.42	0.14	3.38

Table 11: Flood Scenario 7 with Ice Cover HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chan
7 (1b+2+3+4)	6631	1-Percent	13600	592	603.71	600.03	603.85	0.00121	2.01	4697.71	868.63	0.14	3.34
7 (1b+2+3+4)	6631	0.2-Percent	18000	592	604.9	600.41	605.06	0.00105	2.26	5805.11	985.54	0.14	3.1
7 (1b+2+3+4)	6324	10-Percent	7990	590.5	601.1	598.13	601.22	0.001501	1.95	3042.26	669.99	0.14	3.74
7 (1b+2+3+4)	6324	2-Percent	11800	590.5	602.27	598.68	602.44	0.00153	2.21	3791.27	673.85	0.15	3.95
7 (1b+2+3+4)	6324	1-Percent	13600	590.5	602.85	598.91	603.03	0.001453	2.32	4180.66	676.2	0.15	3.94
7 (1b+2+3+4)	6324	0.2-Percent	18000	590.5	604.13	599.4	604.34	0.001309	2.53	5165.85	835.25	0.15	3.92
7 (1b+2+3+4)	6015	10-Percent	7990	588.7	599.95		600.11	0.00159	2.22	2641.85	532.92	0.16	3.34
7 (1b+2+3+4)	6015	2-Percent	11800	588.7	600.93		601.18	0.002015	2.58	3103.5	539.52	0.18	3.8
7 (1b+2+3+4)	6015	1-Percent	13600	588.7	601.58		601.85	0.001861	2.69	3458.37	543.93	0.18	3.79
7 (1b+2+3+4)	6015	0.2-Percent	18000	588.7	602.95		603.26	0.00171	2.95	4240.38	710.65	0.18	3.85
7 (1b+2+3+4)	5607	10-Percent	7990	587.3	599.49	594.29	599.56	0.000429	1.86	3731.62	527.81	0.11	2.04
7 (1b+2+3+4)	5607	2-Percent	11800	587.3	600.19	595.13	600.33	0.000749	2.32	4043.04	547.08	0.13	2.67
7 (1b+2+3+4)	5607	1-Percent	13600	587.3	600.86	595.39	601.02	0.000755	2.45	4413.35	571.55	0.14	2.71
7 (1b+2+3+4)	5607	0.2-Percent	18000	587.3	602.24	596	602.44	0.00079	2.72	5195.32	963.51	0.14	2.85
7 (1b+2+3+4)	5307	10-Percent	7990	585.8	599.29		599.35	0.000321	1.91	4081.23	560.25	0.1	1.78
7 (1b+2+3+4)	5307	2-Percent	11800	585.8	599.81		599.93	0.000663	2.43	4259.11	572.3	0.13	2.64
7 (1b+2+3+4)	5307	1-Percent	13600	585.8	600.48		600.62	0.000677	2.55	4636.86	587.03	0.13	2.71
7 (1b+2+3+4)	5307	0.2-Percent	18000	585.8	601.85		602.01	0.000713	2.8	5653.11	1137.24	0.14	2.87
7 (1b+2+3+4)	5051	10-Percent	7990	584.3	599		599.11	0.000681	2.4	3230.34	651.68	0.13	2.56
7 (1b+2+3+4)	5051	2-Percent	11800	584.3	599.11		599.38	0.001801	3.37	3156.02	668.63	0.19	3.47
7 (1b+2+3+4)	5051	1-Percent	13600	584.3	599.79		600.07	0.001727	3.47	3640.5	860.74	0.19	3.53
7 (1b+2+3+4)	5051	0.2-Percent	18000	584.3	601.16		601.46	0.001608	3.63	4892.46	954.68	0.19	3.69
7 (1b+2+3+4)	4786	10-Percent	7990	582.8	598.56		598.7	0.001172	2.99	3077.36	804.38	0.16	3.51
7 (1b+2+3+4)	4786	2-Percent	11800	582.8	598.5		598.78	0.000951	4.66	3374.24	798.05	0.23	1
7 (1b+2+3+4)	4786	1-Percent	13600	582.8	599.19		599.48	0.000946	4.84	3945.76	880.52	0.23	1
7 (1b+2+3+4)	4786	0.2-Percent	18000	582.8	600.58		600.89	0.000942	5.2	5334.81	1041.26	0.24	1
7 (1b+2+3+4)	4582	10-Percent	7990	582.7	597.85		598.03	0.002198	3.39	2724.71	765.01	0.2	4.44
7 (1b+2+3+4)	4582	2-Percent	11800	582.7	598.02		598.34	0.001133	4.98	3317.88	790.35	0.25	1
7 (1b+2+3+4)	4582	1-Percent	13600	582.7	598.71		599.04	0.001132	5.19	3913.63	951.19	0.25	1
7 (1b+2+3+4)	4582	0.2-Percent	18000	582.7	600.09		600.45	0.001137	5.61	5367.67	1091.71	0.26	1
7 (1b+2+3+4)	4363	10-Percent	7990	582.5	596.51	592.68	596.89	0.003643	3.53	1834.37	746.56	0.22	5.32
7 (1b+2+3+4)	4363	2-Percent	11800	582.5	597.61	590.78	597.91	0.000987	4.69	2878.57	1019.34	0.23	1
7 (1b+2+3+4)	4363	1-Percent	13600	582.5	598.36	591.3	598.62	0.000868	4.6	4629.13	1189.78	0.22	1
7 (1b+2+3+4)	4363	0.2-Percent	18000	582.5	599.75	592.39	600.03	0.000868	4.96	6317.67	1245	0.23	1
7 (1b+2+3+4)	4182	10-Percent	7990	582.4	596	590.03	596.36	0.002358	4.87	1718.14	457.62	0.27	1.93
7 (1b+2+3+4)	4182	2-Percent	11800	582.4	597.14	590.55	597.66	0.001656	5.93	2176.92	640.15	0.3	1
7 (1b+2+3+4)	4182	1-Percent	13600	582.4	597.78	591.12	598.37	0.001766	6.37	2369.5	895.16	0.31	1
7 (1b+2+3+4)	4182	0.2-Percent	18000	582.4	599.29	592.48	599.8	0.001504	6.4	4713	1187.31	0.3	1
7 (1b+2+3+4)	3997	10-Percent	7990	582.3	595.54	589.59	595.91	0.002506	4.94	1669.43	282.39	0.27	2
7 (1b+2+3+4)	3997	2-Percent	11800	582.3	596.82	590.02	597.36	0.001639	5.95	2153.86	525.73	0.3	1
7 (1b+2+3+4)	3997	1-Percent	13600	582.3	597.41	590.59	598.04	0.001815	6.49	2326.06	800.37	0.32	1
7 (1b+2+3+4)	3997	0.2-Percent	18000	582.3	598.75	591.89	599.47	0.001923	7.2	3968.22	1358.12	0.33	1
7 (1b+2+3+4)	3670	10-Percent	7990	582.1	595.25		595.3	0.00117	2.51	5653	1243.67	0.15	3.77
7 (1b+2+3+4)	3670	2-Percent	11800	582.1	596.76		596.82	0.001013	2.8	7649.98	1351.92	0.15	3.45

Table 11: Flood Scenario 7 with Ice Cover HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chan
7 (1b+2+3+4)	3670	1-Percent	13600	582.1	597.4		597.46	0.001007	2.87	8503.65	1396.1	0.15	3.58
7 (1b+2+3+4)	3670	0.2-Percent	18000	582.1	598.79		598.86	0.000987	3	10643.85	1779.37	0.15	3.9
7 (1b+2+3+4)	2921	10-Percent	7990	576.6	593.85		594.11	0.002182	4.44	2559.64	954.79	0.23	3.08
7 (1b+2+3+4)	2921	2-Percent	11800	576.6	595.76		595.96	0.001287	4.2	5111.49	1428.92	0.2	2.55
7 (1b+2+3+4)	2921	1-Percent	13600	576.6	596.51		596.67	0.001055	4.08	6201.24	1444.71	0.19	2.39
7 (1b+2+3+4)	2921	0.2-Percent	18000	576.6	598.06		598.19	0.000785	3.94	8928.85	2136.62	0.17	2.19
7 (1b+2+3+4)	1922	10-Percent	7990	573.7	593.54		593.58	0.000196	2.09	8257.98	1344.43	0.09	1.45
7 (1b+2+3+4)	1922	2-Percent	11800	573.7	595.49		595.52	0.000184	2.27	10949.93	1463.03	0.1	1.38
7 (1b+2+3+4)	1922	1-Percent	13600	573.7	596.23		596.27	0.000186	2.36	12141.66	1693.19	0.1	1.39
7 (1b+2+3+4)	1922	0.2-Percent	18000	573.7	597.78		597.82	0.000192	2.53	14988.84	1884.17	0.1	1.42
7 (1b+2+3+4)	833	10-Percent	7990	571.5	593.39		593.42	0.000106	2.01	7051.55	1516.47	0.08	1
7 (1b+2+3+4)	833	2-Percent	11800	571.5	595.34		595.38	0.000099	2.1	10374.31	1805.97	0.08	1
7 (1b+2+3+4)	833	1-Percent	13600	571.5	596.09		596.12	0.000098	2.14	11779.88	2068.75	0.08	1
7 (1b+2+3+4)	833	0.2-Percent	18000	571.5	597.64		597.68	0.000096	2.24	15564.63	2543.58	0.08	1
7 (1b+2+3+4)	279	10-Percent	7990	571	593.27	581.03	593.33	0.00012	2.35	5948.74	1083.92	0.1	1
7 (1b+2+3+4)	279	2-Percent	11800	571	595.23	582.78	595.29	0.00012	2.53	8758.64	2173.18	0.1	1
7 (1b+2+3+4)	279	1-Percent	13600	571	595.98	583.49	596.04	0.00012	2.6	10421.48	2286.34	0.1	1
7 (1b+2+3+4)	279	0.2-Percent	18000	571	597.53	585.08	597.59	0.00012	2.73	14338.36	2771.69	0.11	1

## Flood Scenario #8 with Ice Cover

### Flood Bench Configuration: 5 + 6

Plan: UPDATE-FB-5+6-UTILITY-UP+DOWN-LEFT-ICE

Geometry: UPDATE-FB-5+6-UTILITY-UP+DOWN-LEFT-ICE

Steady Flow Data: USGS BF,10,2,1,0.2-PERCENT-UPDATE-BC

Date: December 2022




Figure 36: Flood Scenario #8 (5+6) with Ice Cover Profile Plot

Table 12: Flood Scenario 8 with Ice Cover HEC-RAS Output

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.ChnL	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chn
8 (5+6)	20483	10-Percent	7990	621.4	631.44		632.23	0.00152	7.14	1149.93	159.75	0.42	
8 (5+6)	20483	2-Percent	11800	621.4	633.13		634.27	0.001801	8.71	1502.7	283.71	0.47	
8 (5+6)	20483	1-Percent	13600	621.4	633.75		635.03	0.001907	9.3	1683.2	292.19	0.49	
8 (5+6)	20483	0.2-Percent	18000	621.4	635.05		636.62	0.002117	10.53	2068.77	300.59	0.52	
8 (5+6)	19313	10-Percent	7990	620.4	628.71		629.8	0.002908	8.44	1044.14	306.61	0.56	
8 (5+6)	19313	2-Percent	11800	620.4	630.2		631.56	0.003003	9.73	1584.78	383.6	0.58	
8 (5+6)	19313	1-Percent	13600	620.4	630.82		632.26	0.00298	10.15	1839.27	441.9	0.59	
8 (5+6)	19313	0.2-Percent	18000	620.4	632.19	630.62	633.75	0.002869	10.92	2526.95	588.69	0.59	
8 (5+6)	18244	10-Percent	7990	617.6	626.65		627.29	0.001757	6.95	1777.22	467.86	0.44	
8 (5+6)	18244	2-Percent	11800	617.6	628.34		629.05	0.001639	7.65	2591.04	496.46	0.44	
8 (5+6)	18244	1-Percent	13600	617.6	629.04		629.77	0.001595	7.91	2943.65	525.82	0.44	
8 (5+6)	18244	0.2-Percent	18000	617.6	630.58		631.36	0.001502	8.43	3818.23	582.92	0.43	
8 (5+6)	17053	10-Percent	7990	615.5	624.35		625.09	0.001916	7.31	1642.13	449.92	0.46	
8 (5+6)	17053	2-Percent	11800	615.5	625.99		626.9	0.001962	8.38	2446.6	516.1	0.48	
8 (5+6)	17053	1-Percent	13600	615.5	626.66		627.64	0.001967	8.79	2801.03	526.03	0.49	
8 (5+6)	17053	0.2-Percent	18000	615.5	628.2		629.3	0.001934	9.57	3631.61	561.2	0.49	
8 (5+6)	15751	10-Percent	7990	612.8	621.5		622.32	0.002353	7.63	1281.07	298.43	0.5	
8 (5+6)	15751	2-Percent	11800	612.8	623.1		624.11	0.002331	8.68	1817.82	352.78	0.52	
8 (5+6)	15751	1-Percent	13600	612.8	623.84		624.9	0.00225	9	2082.04	364.34	0.51	
8 (5+6)	15751	0.2-Percent	18000	612.8	625.57		626.72	0.00203	9.55	2727.98	378.09	0.5	
8 (5+6)	14403	10-Percent	7990	610.3	619.62		620	0.001191	5.74	2433.54	541.73	0.36	
8 (5+6)	14403	2-Percent	11800	610.3	621.69		622.05	0.000914	5.87	3595.49	583.34	0.33	
8 (5+6)	14403	1-Percent	13600	610.3	622.61		622.96	0.000824	5.91	4153.09	638.01	0.32	
8 (5+6)	14403	0.2-Percent	18000	610.3	624.76		625.08	0.000624	5.8	5656.48	746.87	0.28	
8 (5+6)	12986	10-Percent	7990	608.9	618.23		618.6	0.000827	5.21	2427.97	736.48	0.31	
8 (5+6)	12986	2-Percent	11800	608.9	620.65		620.99	0.000619	5.29	4558.22	922.39	0.28	
8 (5+6)	12986	1-Percent	13600	608.9	621.69		622.01	0.00055	5.29	5527.13	947.9	0.27	
8 (5+6)	12986	0.2-Percent	18000	608.9	624.04		624.33	0.000438	5.3	7812.1	999.62	0.24	
8 (5+6)	12162	10-Percent	7990	604.9	617.03		617.77	0.001141	6.98	1207.69	135.15	0.37	
8 (5+6)	12162	2-Percent	11800	604.9	619.08		620.18	0.001369	8.55	1649.79	403.06	0.42	
8 (5+6)	12162	1-Percent	13600	604.9	620.09		621.25	0.001345	8.91	2099.31	463.55	0.42	
8 (5+6)	12162	0.2-Percent	18000	604.9	622.62		623.71	0.001117	9.06	3570.84	730.2	0.39	
8 (5+6)	11955	10-Percent	7990	605.5	616.8	611.72	617.53	0.001175	6.85	1177.36	116.61	0.37	
8 (5+6)	11955	2-Percent	11800	605.5	618.78	613.35	619.89	0.001432	8.48	1413.75	149.67	0.42	
8 (5+6)	11955	1-Percent	13600	605.5	619.66	614.06	620.94	0.001509	9.11	1521.56	162.36	0.44	
8 (5+6)	11955	0.2-Percent	18000	605.5	621.72	615.65	623.38	0.001625	10.4	1775.05	330.92	0.47	
8 (5+6)	11860 Union Rd	Bridge											
8 (5+6)	11789	10-Percent	7990	605.5	616.22	612.39	617.18	0.002925	7.85	1022.6	112.37	0.45	1
8 (5+6)	11789	2-Percent	11800	605.5	617.95	614.02	619.43	0.003605	9.76	1223.12	119.72	0.52	1
8 (5+6)	11789	1-Percent	13600	605.5	618.6	614.75	620.34	0.003944	10.61	1302.35	123.37	0.55	1
8 (5+6)	11789	0.2-Percent	18000	605.5	619.92	616.38	622.35	0.004796	12.56	1464.55	152.58	0.61	1
8 (5+6)	11675	10-Percent	7990	602.4	616.13		616.7	0.00209	6.08	1336.39	130.41	0.32	1
8 (5+6)	11675	2-Percent	11800	602.4	617.88		618.79	0.002689	7.72	1568.9	139.64	0.38	1
8 (5+6)	11675	1-Percent	13600	602.4	618.53		619.63	0.002982	8.46	1663.85	150.51	0.41	1

Table 12: Flood Scenario 8 with Ice Cover HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.ChnL	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chn
8 (5+6)	11675	0.2-Percent	18000	602.4	619.88		621.43	0.003666	10.1	1940.6	306.07	0.46	1
8 (5+6)	10302	10-Percent	7990	603.2	612.45		613	0.003613	6.22	1616.88	503.71	0.39	1
8 (5+6)	10302	2-Percent	11800	603.2	613.64		614.32	0.003897	7.21	2289.06	591.18	0.42	1
8 (5+6)	10302	1-Percent	13600	603.2	614.12		614.83	0.003947	7.55	2572.51	601.91	0.43	1
8 (5+6)	10302	0.2-Percent	18000	603.2	615.15		615.95	0.003999	8.23	3211.26	623.52	0.44	1
8 (5+6)	9372	10-Percent	7990	599.6	610.32		610.63	0.001792	4.83	2027.94	598.16	0.28	1
8 (5+6)	9372	2-Percent	11800	599.6	611.55		611.9	0.001737	5.26	2779.32	616.31	0.29	1
8 (5+6)	9372	1-Percent	13600	599.6	612.06		612.41	0.001714	5.42	3092.11	640.46	0.29	1
8 (5+6)	9372	0.2-Percent	18000	599.6	613.28		613.64	0.001546	5.6	4005.58	964.84	0.29	1
8 (5+6)	8312	10-Percent	7990	595.5	608.59		608.64	0.001823	1.32	4572.48	805.09	0.11	8.31
8 (5+6)	8312	2-Percent	11800	595.5	609.23		609.33	0.003345	1.38	4759.71	805.48	0.13	10.15
8 (5+6)	8312	1-Percent	13600	595.5	609.63		609.76	0.003743	1.43	5001.93	811.23	0.14	10.61
8 (5+6)	8312	0.2-Percent	18000	595.5	611.11		611.25	0.003345	1.72	6196.75	833.18	0.14	10.73
8 (5+6)	8145	10-Percent	7990	592.1	607.68	602.98	608.07	0.006948	5	1597.42	459.93	0.3	6.4
8 (5+6)	8145	2-Percent	11800	592.1	608.47	600.89	608.85	0.002228	5	2358.42	477.6	0.25	2.84
8 (5+6)	8145	1-Percent	13600	592.1	609.02	600	609.41	0.001168	5	2717.85	489	0.23	1.35
8 (5+6)	8145	0.2-Percent	18000	592.1	610.37	600.82	610.92	0.001093	5.94	3032.36	511.03	0.26	1
8 (5+6)	8049 Railroad Bridge	Bridge											
8 (5+6)	7984	10-Percent	7990	592.1	607.42	602.06	607.79	0.003266	4.87	1643.53	535.35	0.28	2.73
8 (5+6)	7984	2-Percent	11800	592.1	608.09	601.79	608.62	0.001786	5.94	2027.46	565.94	0.3	1
8 (5+6)	7984	1-Percent	13600	592.1	608.49	602.37	609.15	0.002095	6.6	2103.02	572.55	0.33	1
8 (5+6)	7984	0.2-Percent	18000	592.1	609.4	603.63	610.39	0.002803	8.07	2275.15	599.17	0.39	1
8 (5+6)	7758	10-Percent	7990	595	606.69	603.12	606.81	0.00138	2.28	3085.09	978.74	0.15	3.95
8 (5+6)	7758	2-Percent	11800	595	607.57	604.75	607.73	0.001577	2.32	4018.38	1152.69	0.15	4.8
8 (5+6)	7758	1-Percent	13600	595	607.95	605.52	608.13	0.00164	2.23	4416.87	1309.28	0.15	5.43
8 (5+6)	7758	0.2-Percent	18000	595	608.99	606.34	609.18	0.001405	1.96	5647.38	1316.01	0.13	6.51
8 (5+6)	7564	10-Percent	7990	594.9	606.22		606.32	0.000999	2.24	3452.37	983.92	0.14	3.03
8 (5+6)	7564	2-Percent	11800	594.9	607.01		607.14	0.001235	2.54	4275.8	1266.4	0.15	3.36
8 (5+6)	7564	1-Percent	13600	594.9	607.38		607.52	0.001277	2.59	4752.69	1493.01	0.16	3.55
8 (5+6)	7564	0.2-Percent	18000	594.9	608.5		608.64	0.001131	2.63	6610.45	1770.01	0.15	3.71
8 (5+6)	7340	10-Percent	7990	594.8	605.87		605.96	0.000751	2.06	3761	1121.95	0.13	2.56
8 (5+6)	7340	2-Percent	11800	594.8	606.53		606.66	0.001089	2.34	4525.96	1410.51	0.15	3.19
8 (5+6)	7340	1-Percent	13600	594.8	606.89		607.03	0.001117	2.43	5044.8	1595.48	0.15	3.26
8 (5+6)	7340	0.2-Percent	18000	594.8	608.13		608.24	0.000818	2.44	7330.45	1925.71	0.14	2.99
8 (5+6)	7151	10-Percent	7990	594.7	605.45		605.54	0.001145	2.46	3859.95	1803.53	0.16	2.43
8 (5+6)	7151	2-Percent	11800	594.7	605.78		605.96	0.00238	2.93	4297.85	1966.93	0.2	3.55
8 (5+6)	7151	1-Percent	13600	594.7	606.2		606.36	0.002011	2.86	5157.65	2067.54	0.19	3.48
8 (5+6)	7151	0.2-Percent	18000	594.7	607.78		607.87	0.000806	2.41	8922.68	2522.8	0.14	2.79
8 (5+6)	6890	10-Percent	7990	593	605.22	600.46	605.25	0.000303	1.35	9226.05	2330.43	0.08	2.38
8 (5+6)	6890	2-Percent	11800	593	605.18	601.89	605.24	0.000824	1.7	8902.17	2327.34	0.11	3.71
8 (5+6)	6890	1-Percent	13600	593	605.67	602.14	605.73	0.000758	1.78	10065.08	2352.61	0.11	3.53
8 (5+6)	6890	0.2-Percent	18000	593	607.51	602.48	607.56	0.000427	1.78	14556.13	2402.24	0.1	2.93
8 (5+6)	6631	10-Percent	7990	592	604.74	600.7	604.89	0.001739	2.56	2812.03	865.2	0.17	3.7
8 (5+6)	6631	2-Percent	11800	592	604.19	599.84	604.54	0.001861	4.94	2557.61	636.46	0.29	1

Table 12: Flood Scenario 8 with Ice Cover HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.ChnL	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chn
8 (5+6)	6631	1-Percent	13600	592	604.81	600.23	605.11	0.001555	4.75	3385.36	891.8	0.27	1
8 (5+6)	6631	0.2-Percent	18000	592	606.84	603.31	607.08	0.002067	3.34	5207	1474.77	0.2	3.92
8 (5+6)	6324	10-Percent	7990	590.5	602.93	600.44	603.32	0.003961	2.8	1936.38	622.27	0.21	5.66
8 (5+6)	6324	2-Percent	11800	590.5	603.35	597.94	603.62	0.001179	4.38	2915.42	772.7	0.24	1
8 (5+6)	6324	1-Percent	13600	590.5	603.95	598.34	604.25	0.00124	4.69	3156.45	875.07	0.25	1
8 (5+6)	6324	0.2-Percent	18000	590.5	605.49	602.21	605.76	0.002217	2.99	4817.73	1548.42	0.18	5.39
8 (5+6)	6015	10-Percent	7990	588.7	601.09		601.31	0.001995	2.14	2411.39	571.9	0.16	4.85
8 (5+6)	6015	2-Percent	11800	588.7	601.95		602.34	0.002931	2.32	2765.54	608.13	0.17	6.05
8 (5+6)	6015	1-Percent	13600	588.7	602.58		602.98	0.002708	2.36	3126.38	636.41	0.17	6.25
8 (5+6)	6015	0.2-Percent	18000	588.7	603.92		604.25	0.001979	2.93	4453.01	1082.99	0.18	4.95
8 (5+6)	5607	10-Percent	7990	587.3	600.49	594.51	600.59	0.000572	2.09	3404.25	516.89	0.12	2.63
8 (5+6)	5607	2-Percent	11800	587.3	600.77	595.8	601.01	0.001234	2.74	3465.89	519.34	0.16	3.43
8 (5+6)	5607	1-Percent	13600	587.3	601.43	596.22	601.69	0.00124	2.88	3800.97	567.04	0.16	3.5
8 (5+6)	5607	0.2-Percent	18000	587.3	602.79	597.11	603.12	0.001329	3.15	4470.63	1030.43	0.17	3.86
8 (5+6)	5307	10-Percent	7990	585.8	600.2		600.29	0.000496	2.28	3664.93	503.59	0.12	2.34
8 (5+6)	5307	2-Percent	11800	585.8	600.01		600.25	0.001524	3.23	3410.96	497.29	0.18	3.51
8 (5+6)	5307	1-Percent	13600	585.8	600.65		600.91	0.001577	3.41	3723.69	525.9	0.19	3.62
8 (5+6)	5307	0.2-Percent	18000	585.8	601.99		602.29	0.001637	3.72	4781.78	1214.94	0.19	3.84
8 (5+6)	5051	10-Percent	7990	584.3	599.75		599.88	0.001382	3.13	2937.42	812.17	0.17	3.46
8 (5+6)	5051	2-Percent	11800	584.3	599.21		599.54	0.001187	4.87	2949.37	664.88	0.25	1
8 (5+6)	5051	1-Percent	13600	584.3	599.85		600.2	0.001188	5.08	3421.59	872.11	0.25	1
8 (5+6)	5051	0.2-Percent	18000	584.3	601.21		601.57	0.001159	5.44	4655.56	935.59	0.26	1
8 (5+6)	4786	10-Percent	7990	582.8	599.04		599.16	0.001698	3.17	3059.99	854.13	0.18	4.63
8 (5+6)	4786	2-Percent	11800	582.8	598.68		599.01	0.001074	5	3254.57	817.09	0.24	1
8 (5+6)	4786	1-Percent	13600	582.8	599.33		599.67	0.001074	5.19	3806.97	913.8	0.25	1
8 (5+6)	4786	0.2-Percent	18000	582.8	600.7		601.05	0.001047	5.52	5198.61	1042.58	0.25	1
8 (5+6)	4582	10-Percent	7990	582.7	597.9		598.1	0.004054	4.01	2412.09	756.36	0.24	5.39
8 (5+6)	4582	2-Percent	11800	582.7	598.14		598.51	0.001268	5.31	3182.46	816.12	0.26	1
8 (5+6)	4582	1-Percent	13600	582.7	598.78		599.17	0.001283	5.55	3751.86	977.87	0.27	1
8 (5+6)	4582	0.2-Percent	18000	582.7	600.15		600.56	0.001276	5.97	5199.14	1093.16	0.27	1
8 (5+6)	4363	10-Percent	7990	582.5	596.5	590.5	596.83	0.002491	4.75	1789.22	744.56	0.26	2.36
8 (5+6)	4363	2-Percent	11800	582.5	597.48	590.61	597.95	0.001487	5.72	2365.98	945.93	0.28	1
8 (5+6)	4363	1-Percent	13600	582.5	598.28	591.23	598.66	0.001234	5.46	4087.63	1174.9	0.26	1
8 (5+6)	4363	0.2-Percent	18000	582.5	599.68	592.56	600.06	0.001166	5.73	5787.95	1242.05	0.26	1
8 (5+6)	4182	10-Percent	7990	582.4	596.04	590.06	596.39	0.002346	4.85	1725.47	462.13	0.27	1.94
8 (5+6)	4182	2-Percent	11800	582.4	597.14	590.55	597.66	0.001656	5.93	2176.92	640.15	0.3	1
8 (5+6)	4182	1-Percent	13600	582.4	597.78	591.12	598.37	0.001766	6.37	2369.5	895.16	0.31	1
8 (5+6)	4182	0.2-Percent	18000	582.4	599.29	592.48	599.81	0.001504	6.4	4713.57	1187.32	0.3	1
8 (5+6)	3997	10-Percent	7990	582.3	595.56	589.64	595.93	0.002594	4.95	1664.4	282.96	0.27	2.08
8 (5+6)	3997	2-Percent	11800	582.3	596.82	590.02	597.36	0.001639	5.95	2153.86	525.73	0.3	1
8 (5+6)	3997	1-Percent	13600	582.3	597.41	590.59	598.04	0.001815	6.49	2326.06	800.37	0.32	1
8 (5+6)	3997	0.2-Percent	18000	582.3	598.75	591.89	599.47	0.001922	7.2	3968.88	1358.2	0.33	1
8 (5+6)	3670	10-Percent	7990	582.1	595.26		595.31	0.001187	2.49	5655.65	1244.36	0.15	3.88
8 (5+6)	3670	2-Percent	11800	582.1	596.76		596.82	0.001013	2.8	7649.98	1351.92	0.15	3.45

Table 12: Flood Scenario 8 with Ice Cover HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chn
8 (5+6)	3670	1-Percent	13600	582.1	597.4		597.46	0.001007	2.87	8503.65	1396.1	0.15	3.58
8 (5+6)	3670	0.2-Percent	18000	582.1	598.79		598.86	0.000988	3	10643.31	1779.55	0.15	3.9
8 (5+6)	2921	10-Percent	7990	576.6	593.85		594.11	0.002187	4.44	2559.96	955.18	0.23	3.09
8 (5+6)	2921	2-Percent	11800	576.6	595.76		595.96	0.001287	4.2	5111.49	1428.92	0.2	2.55
8 (5+6)	2921	1-Percent	13600	576.6	596.51		596.67	0.001055	4.08	6201.24	1444.71	0.19	2.39
8 (5+6)	2921	0.2-Percent	18000	576.6	598.06		598.19	0.000785	3.94	8928.85	2136.62	0.17	2.19
8 (5+6)	1922	10-Percent	7990	573.7	593.54		593.58	0.000197	2.08	8257.55	1344.43	0.09	1.46
8 (5+6)	1922	2-Percent	11800	573.7	595.49		595.52	0.000184	2.27	10949.93	1463.03	0.1	1.38
8 (5+6)	1922	1-Percent	13600	573.7	596.23		596.27	0.000186	2.36	12141.66	1693.19	0.1	1.39
8 (5+6)	1922	0.2-Percent	18000	573.7	597.78		597.82	0.000192	2.53	14988.84	1884.17	0.1	1.42
8 (5+6)	833	10-Percent	7990	571.5	593.39		593.42	0.000106	2.01	7051.55	1516.47	0.08	1
8 (5+6)	833	2-Percent	11800	571.5	595.34		595.38	0.000099	2.1	10374.31	1805.97	0.08	1
8 (5+6)	833	1-Percent	13600	571.5	596.09		596.12	0.000098	2.14	11779.88	2068.75	0.08	1
8 (5+6)	833	0.2-Percent	18000	571.5	597.64		597.68	0.000096	2.24	15564.63	2543.58	0.08	1
8 (5+6)	279	10-Percent	7990	571	593.27	581.03	593.33	0.00012	2.35	5948.74	1083.92	0.1	1
8 (5+6)	279	2-Percent	11800	571	595.23	582.78	595.29	0.00012	2.53	8758.64	2173.18	0.1	1
8 (5+6)	279	1-Percent	13600	571	595.98	583.49	596.04	0.00012	2.6	10421.48	2286.34	0.1	1
8 (5+6)	279	0.2-Percent	18000	571	597.53	585.08	597.59	0.00012	2.73	14338.36	2771.69	0.11	1

## Flood Scenario #9 with Ice Cover

**Flood Bench Configuration: 1b + 2 + 3 + 4 + 5 + 6**

Plan: UPDATE-FB-1b+2+3+4+5+6-FULL-SUITE-ICE

Geometry: UPDATE-FB-1b+2+3+4+5+6-FULL-SUITE-ICE

Steady Flow Data: USGS BF,10,2,1,0.2-PERCENT-UPDATE-BC

Date: December 2022




Figure 37: Flood Scenario #9 (1b+2+3+4+5+6) with Ice Cover Profile Plot

Table 13: Flood Scenario 9 with Ice Cover HEC-RAS Output

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chn
9 (1b+2+3+4+5+6)	20483	10-Percent	7990	621.4	631.44		632.23	0.00152	7.14	1149.93	159.75	0.42	
9 (1b+2+3+4+5+6)	20483	2-Percent	11800	621.4	633.13		634.27	0.001801	8.71	1502.7	283.71	0.47	
9 (1b+2+3+4+5+6)	20483	1-Percent	13600	621.4	633.75		635.03	0.001907	9.3	1683.2	292.19	0.49	
9 (1b+2+3+4+5+6)	20483	0.2-Percent	18000	621.4	635.05		636.62	0.002117	10.53	2068.77	300.59	0.52	
9 (1b+2+3+4+5+6)	19313	10-Percent	7990	620.4	628.71		629.8	0.002908	8.44	1044.14	306.61	0.56	
9 (1b+2+3+4+5+6)	19313	2-Percent	11800	620.4	630.2		631.56	0.003003	9.73	1584.78	383.6	0.58	
9 (1b+2+3+4+5+6)	19313	1-Percent	13600	620.4	630.82		632.26	0.00298	10.15	1839.24	441.9	0.59	
9 (1b+2+3+4+5+6)	19313	0.2-Percent	18000	620.4	632.19	630.62	633.75	0.002869	10.92	2526.99	588.7	0.59	
9 (1b+2+3+4+5+6)	18244	10-Percent	7990	617.6	626.65		627.29	0.001757	6.95	1777.22	467.86	0.44	
9 (1b+2+3+4+5+6)	18244	2-Percent	11800	617.6	628.34		629.05	0.001639	7.65	2591.04	496.46	0.44	
9 (1b+2+3+4+5+6)	18244	1-Percent	13600	617.6	629.04		629.77	0.001595	7.91	2943.68	525.83	0.44	
9 (1b+2+3+4+5+6)	18244	0.2-Percent	18000	617.6	630.58		631.36	0.001502	8.43	3818.33	582.92	0.43	
9 (1b+2+3+4+5+6)	17053	10-Percent	7990	615.5	624.35		625.09	0.001916	7.31	1642.13	449.92	0.46	
9 (1b+2+3+4+5+6)	17053	2-Percent	11800	615.5	625.99		626.9	0.001962	8.38	2446.6	516.1	0.48	
9 (1b+2+3+4+5+6)	17053	1-Percent	13600	615.5	626.66		627.64	0.001967	8.79	2801.06	526.03	0.49	
9 (1b+2+3+4+5+6)	17053	0.2-Percent	18000	615.5	628.2		629.3	0.001933	9.57	3631.88	561.22	0.49	
9 (1b+2+3+4+5+6)	15751	10-Percent	7990	612.8	621.5		622.32	0.002353	7.63	1281.07	298.43	0.5	
9 (1b+2+3+4+5+6)	15751	2-Percent	11800	612.8	623.1		624.11	0.002331	8.68	1817.82	352.78	0.52	
9 (1b+2+3+4+5+6)	15751	1-Percent	13600	612.8	623.84		624.9	0.00225	8.99	2082.15	364.34	0.51	
9 (1b+2+3+4+5+6)	15751	0.2-Percent	18000	612.8	625.58		626.72	0.002028	9.55	2728.88	378.1	0.5	
9 (1b+2+3+4+5+6)	14403	10-Percent	7990	610.3	619.62		620	0.001192	5.74	2433.48	541.73	0.36	
9 (1b+2+3+4+5+6)	14403	2-Percent	11800	610.3	621.69		622.05	0.000914	5.87	3595.49	583.34	0.33	
9 (1b+2+3+4+5+6)	14403	1-Percent	13600	610.3	622.61		622.96	0.000824	5.91	4153.48	638.03	0.32	
9 (1b+2+3+4+5+6)	14403	0.2-Percent	18000	610.3	624.77		625.08	0.000624	5.8	5659.35	747.1	0.28	
9 (1b+2+3+4+5+6)	12986	10-Percent	7990	608.9	618.23		618.6	0.000827	5.21	2427.79	736.39	0.31	
9 (1b+2+3+4+5+6)	12986	2-Percent	11800	608.9	620.65		620.99	0.000619	5.29	4558.28	922.39	0.28	
9 (1b+2+3+4+5+6)	12986	1-Percent	13600	608.9	621.69		622.01	0.00055	5.29	5527.99	947.91	0.27	
9 (1b+2+3+4+5+6)	12986	0.2-Percent	18000	608.9	624.05		624.34	0.000437	5.3	7816.98	999.76	0.24	
9 (1b+2+3+4+5+6)	12162	10-Percent	7990	604.9	617.03		617.77	0.001141	6.98	1207.64	135.14	0.37	
9 (1b+2+3+4+5+6)	12162	2-Percent	11800	604.9	619.08		620.18	0.001369	8.55	1649.84	403.11	0.42	
9 (1b+2+3+4+5+6)	12162	1-Percent	13600	604.9	620.09		621.25	0.001344	8.9	2100.01	463.57	0.42	
9 (1b+2+3+4+5+6)	12162	0.2-Percent	18000	604.9	622.63		623.71	0.001115	9.05	3576.64	731.48	0.39	
9 (1b+2+3+4+5+6)	11955	10-Percent	7990	605.5	616.8	611.72	617.53	0.001175	6.85	1177.32	116.61	0.37	
9 (1b+2+3+4+5+6)	11955	2-Percent	11800	605.5	618.78	613.35	619.89	0.001432	8.48	1413.78	149.67	0.42	
9 (1b+2+3+4+5+6)	11955	1-Percent	13600	605.5	619.66	614.06	620.94	0.001509	9.11	1521.75	162.38	0.44	
9 (1b+2+3+4+5+6)	11955	0.2-Percent	18000	605.5	621.72	615.65	623.38	0.001622	10.39	1776.04	332.33	0.47	
9 (1b+2+3+4+5+6)	11860 Union Rd	Bridge											
9 (1b+2+3+4+5+6)	11789	10-Percent	7990	605.5	616.22	612.39	617.18	0.002926	7.85	1022.56	112.37	0.45	1
9 (1b+2+3+4+5+6)	11789	2-Percent	11800	605.5	617.95	614.02	619.43	0.003604	9.76	1223.15	119.72	0.52	1
9 (1b+2+3+4+5+6)	11789	1-Percent	13600	605.5	618.61	614.75	620.34	0.003941	10.61	1302.58	123.38	0.55	1
9 (1b+2+3+4+5+6)	11789	0.2-Percent	18000	605.5	619.93	616.38	622.35	0.004781	12.54	1465.96	153.38	0.61	1
9 (1b+2+3+4+5+6)	11675	10-Percent	7990	602.4	616.13		616.7	0.00209	6.08	1336.33	130.41	0.32	1
9 (1b+2+3+4+5+6)	11675	2-Percent	11800	602.4	617.88		618.8	0.002688	7.72	1568.93	139.64	0.38	1
9 (1b+2+3+4+5+6)	11675	1-Percent	13600	602.4	618.54		619.63	0.00298	8.46	1664.14	150.55	0.41	1

Table 13: Flood Scenario 9 with Ice Cover HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chn
9 (1b+2+3+4+5+6)	11675	0.2-Percent	18000	602.4	619.89		621.44	0.003654	10.09	1944.41	306.6	0.46	1
9 (1b+2+3+4+5+6)	10302	10-Percent	7990	603.2	612.45		613	0.0036	6.21	1619.86	503.92	0.39	1
9 (1b+2+3+4+5+6)	10302	2-Percent	11800	603.2	613.64		614.32	0.003895	7.21	2289.5	591.19	0.42	1
9 (1b+2+3+4+5+6)	10302	1-Percent	13600	603.2	614.11		614.83	0.003959	7.55	2569.24	601.69	0.43	1
9 (1b+2+3+4+5+6)	10302	0.2-Percent	18000	603.2	615.12		615.93	0.004071	8.28	3189.57	623.17	0.45	1
9 (1b+2+3+4+5+6)	9372	10-Percent	7990	599.6	610.22		610.55	0.001922	4.96	1967.46	595.74	0.29	1
9 (1b+2+3+4+5+6)	9372	2-Percent	11800	599.6	611.38		611.75	0.001936	5.48	2671.21	613.29	0.3	1
9 (1b+2+3+4+5+6)	9372	1-Percent	13600	599.6	611.88		612.27	0.001895	5.63	2983.35	628.58	0.31	1
9 (1b+2+3+4+5+6)	9372	0.2-Percent	18000	599.6	613		613.41	0.001783	5.9	3755.36	798.91	0.3	1
9 (1b+2+3+4+5+6)	8312	10-Percent	7990	595.5	607.02		607.15	0.006074	0.56	2916.93	739.56	0.1	10.98
9 (1b+2+3+4+5+6)	8312	2-Percent	11800	595.5	607.84		608.03	0.007861	0.97	3492.62	757.34	0.14	11.24
9 (1b+2+3+4+5+6)	8312	1-Percent	13600	595.5	608.37		608.59	0.007963	0.63	3719.41	760.5	0.11	12.43
9 (1b+2+3+4+5+6)	8312	0.2-Percent	18000	595.5	609.84		610.08	0.006626	1.04	4785.52	788.96	0.13	12.93
9 (1b+2+3+4+5+6)	8145	10-Percent	7990	592.1	605.77	601.11	606.16	0.005447	5.01	1596.39	336.88	0.3	4.32
9 (1b+2+3+4+5+6)	8145	2-Percent	11800	592.1	607.14	599.56	607.53	0.001501	5.01	2357.6	446.8	0.25	1.39
9 (1b+2+3+4+5+6)	8145	1-Percent	13600	592.1	607.71	599.7	608.16	0.001183	5.37	2532.26	460.41	0.26	1
9 (1b+2+3+4+5+6)	8145	0.2-Percent	18000	592.1	608.91	600.82	609.57	0.00153	6.53	2758.53	486.95	0.3	1
9 (1b+2+3+4+5+6)	8049 Railroad Bridge	Bridge											
9 (1b+2+3+4+5+6)	7984	10-Percent	7990	592.1	605.44	600.46	605.87	0.002085	5.26	1540.39	370.68	0.31	1
9 (1b+2+3+4+5+6)	7984	2-Percent	11800	592.1	606.48	601.79	607.22	0.003057	6.93	1729.89	497.76	0.38	1
9 (1b+2+3+4+5+6)	7984	1-Percent	13600	592.1	606.9	602.37	607.8	0.003507	7.66	1806.13	521.08	0.41	1
9 (1b+2+3+4+5+6)	7984	0.2-Percent	18000	592.1	607.72	603.63	609.06	0.004668	9.37	1959.48	557.73	0.49	1
9 (1b+2+3+4+5+6)	7758	10-Percent	7990	595	604.87	602.55	604.98	0.001464	1.74	3219.26	868.24	0.13	4.2
9 (1b+2+3+4+5+6)	7758	2-Percent	11800	595	605.85	603.2	606.01	0.001654	1.57	3872.45	950.48	0.13	5.69
9 (1b+2+3+4+5+6)	7758	1-Percent	13600	595	606.26	603.51	606.45	0.001711	1.49	4143.07	965.99	0.12	6.34
9 (1b+2+3+4+5+6)	7758	0.2-Percent	18000	595	607.16	604.08	607.39	0.001713	1.33	4951.6	1009.33	0.11	7.63
9 (1b+2+3+4+5+6)	7564	10-Percent	7990	594.9	604.29		604.38	0.001375	2.04	3296.58	888.89	0.15	3.12
9 (1b+2+3+4+5+6)	7564	2-Percent	11800	594.9	605.21		605.35	0.001486	2.18	4069.69	924.97	0.15	3.56
9 (1b+2+3+4+5+6)	7564	1-Percent	13600	594.9	605.61		605.76	0.001511	2.22	4423.96	971.04	0.15	3.77
9 (1b+2+3+4+5+6)	7564	0.2-Percent	18000	594.9	606.52		606.71	0.0015	2.34	5296.73	1036.09	0.15	4.05
9 (1b+2+3+4+5+6)	7340	10-Percent	7990	594.8	603.72		603.81	0.001367	1.95	3410.44	1034.3	0.15	2.94
9 (1b+2+3+4+5+6)	7340	2-Percent	11800	594.8	604.64		604.76	0.001349	2.12	4355.69	1074.17	0.15	3.12
9 (1b+2+3+4+5+6)	7340	1-Percent	13600	594.8	605.04		605.17	0.001321	2.18	4783.64	1082.18	0.15	3.18
9 (1b+2+3+4+5+6)	7340	0.2-Percent	18000	594.8	605.99		606.14	0.001229	2.33	5816.23	1163.91	0.15	3.23
9 (1b+2+3+4+5+6)	7151	10-Percent	7990	594.7	603.05		603.14	0.001657	1.81	3364.35	1087.35	0.15	3.07
9 (1b+2+3+4+5+6)	7151	2-Percent	11800	594.7	604		604.12	0.001489	1.98	4404.77	1127.68	0.15	3.14
9 (1b+2+3+4+5+6)	7151	1-Percent	13600	594.7	604.43		604.56	0.001404	2.05	4894.6	1142.47	0.15	3.13
9 (1b+2+3+4+5+6)	7151	0.2-Percent	18000	594.7	605.46		605.59	0.00119	2.19	6314.89	1809.19	0.15	3.07
9 (1b+2+3+4+5+6)	6890	10-Percent	7990	593	602.41	599.9	602.47	0.00099	1.38	4021.85	2088.64	0.11	3.19
9 (1b+2+3+4+5+6)	6890	2-Percent	11800	593	603.43	600.27	603.51	0.000908	1.55	5209.99	2141.33	0.12	3.23
9 (1b+2+3+4+5+6)	6890	1-Percent	13600	593	603.89	600.43	603.98	0.00086	1.62	5764.76	2181.87	0.12	3.21
9 (1b+2+3+4+5+6)	6890	0.2-Percent	18000	593	604.99	600.76	605.09	0.000756	1.78	7077.94	2315.63	0.12	3.12
9 (1b+2+3+4+5+6)	6631	10-Percent	7990	592	601.65	599.25	601.76	0.001609	1.66	3193.05	859.51	0.14	3.36
9 (1b+2+3+4+5+6)	6631	2-Percent	11800	592	602.7	599.75	602.85	0.001524	1.9	4077.56	864.27	0.15	3.47

Table 13: Flood Scenario 9 with Ice Cover HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chn
9 (1b+2+3+4+5+6)	6631	1-Percent	13600	592	603.2	599.93	603.36	0.001438	2	4511.24	866.54	0.15	3.45
9 (1b+2+3+4+5+6)	6631	0.2-Percent	18000	592	604.36	600.34	604.54	0.001265	2.2	5526.92	871.31	0.15	3.4
9 (1b+2+3+4+5+6)	6324	10-Percent	7990	590.5	600.66	598	600.78	0.00159	1.9	3102.98	753.04	0.15	3.68
9 (1b+2+3+4+5+6)	6324	2-Percent	11800	590.5	601.71	598.52	601.87	0.00166	2.14	3842	756.78	0.15	3.94
9 (1b+2+3+4+5+6)	6324	1-Percent	13600	590.5	602.27	598.73	602.44	0.001529	2.23	4276.31	758.79	0.15	3.9
9 (1b+2+3+4+5+6)	6324	0.2-Percent	18000	590.5	603.54	599.17	603.74	0.001327	2.43	5253.53	861.26	0.15	3.85
9 (1b+2+3+4+5+6)	6015	10-Percent	7990	588.7	599.73		599.84	0.001086	1.91	3145.45	633.23	0.14	3.01
9 (1b+2+3+4+5+6)	6015	2-Percent	11800	588.7	600.56		600.74	0.001484	2.27	3611.56	635.8	0.16	3.45
9 (1b+2+3+4+5+6)	6015	1-Percent	13600	588.7	601.22		601.41	0.001346	2.37	4041.32	637.85	0.15	3.39
9 (1b+2+3+4+5+6)	6015	0.2-Percent	18000	588.7	602.61		602.83	0.001203	2.59	4934.22	669.27	0.15	3.37
9 (1b+2+3+4+5+6)	5607	10-Percent	7990	587.3	599.39	594.03	599.45	0.000318	1.72	4233.25	594.97	0.1	1.7
9 (1b+2+3+4+5+6)	5607	2-Percent	11800	587.3	600	594.7	600.11	0.000567	2.15	4538.23	596.4	0.12	2.25
9 (1b+2+3+4+5+6)	5607	1-Percent	13600	587.3	600.68	594.93	600.81	0.000565	2.27	4945.23	598.01	0.13	2.26
9 (1b+2+3+4+5+6)	5607	0.2-Percent	18000	587.3	602.08	595.46	602.23	0.000593	2.53	5770.32	921.46	0.13	2.36
9 (1b+2+3+4+5+6)	5307	10-Percent	7990	585.8	599.24		599.29	0.000235	1.72	4609.51	569.17	0.09	1.54
9 (1b+2+3+4+5+6)	5307	2-Percent	11800	585.8	599.72		599.81	0.000485	2.2	4779.33	570.68	0.12	2.27
9 (1b+2+3+4+5+6)	5307	1-Percent	13600	585.8	600.4		600.51	0.000499	2.32	5162.66	586.26	0.12	2.34
9 (1b+2+3+4+5+6)	5307	0.2-Percent	18000	585.8	601.78		601.91	0.000543	2.58	6146.64	1092.5	0.13	2.52
9 (1b+2+3+4+5+6)	5051	10-Percent	7990	584.3	598.99		599.09	0.000657	2.42	3244.01	650.51	0.13	2.41
9 (1b+2+3+4+5+6)	5051	2-Percent	11800	584.3	599.11		599.37	0.001693	3.41	3194.45	668.42	0.19	3.23
9 (1b+2+3+4+5+6)	5051	1-Percent	13600	584.3	599.79		600.06	0.001647	3.5	3673.75	860.37	0.19	3.32
9 (1b+2+3+4+5+6)	5051	0.2-Percent	18000	584.3	601.16		601.45	0.001548	3.67	4925.24	954.51	0.19	3.49
9 (1b+2+3+4+5+6)	4786	10-Percent	7990	582.8	598.55		598.69	0.001162	2.99	3078.42	803.68	0.16	3.46
9 (1b+2+3+4+5+6)	4786	2-Percent	11800	582.8	598.5		598.78	0.000951	4.66	3374.24	798.05	0.23	1
9 (1b+2+3+4+5+6)	4786	1-Percent	13600	582.8	599.19		599.48	0.000946	4.83	3947.05	880.79	0.23	1
9 (1b+2+3+4+5+6)	4786	0.2-Percent	18000	582.8	600.58		600.89	0.000942	5.2	5335.13	1041.26	0.24	1
9 (1b+2+3+4+5+6)	4582	10-Percent	7990	582.7	597.85		598.03	0.002194	3.39	2724.43	764.86	0.2	4.43
9 (1b+2+3+4+5+6)	4582	2-Percent	11800	582.7	598.02		598.34	0.001133	4.98	3317.88	790.35	0.25	1
9 (1b+2+3+4+5+6)	4582	1-Percent	13600	582.7	598.71		599.04	0.001131	5.19	3915.43	951.61	0.25	1
9 (1b+2+3+4+5+6)	4582	0.2-Percent	18000	582.7	600.09		600.45	0.001136	5.61	5368.01	1091.71	0.26	1
9 (1b+2+3+4+5+6)	4363	10-Percent	7990	582.5	596.51	592.67	596.89	0.003638	3.53	1835.06	746.56	0.22	5.31
9 (1b+2+3+4+5+6)	4363	2-Percent	11800	582.5	597.61	590.78	597.91	0.000987	4.69	2878.57	1019.34	0.23	1
9 (1b+2+3+4+5+6)	4363	1-Percent	13600	582.5	598.36	591.3	598.63	0.000867	4.6	4631.81	1189.86	0.22	1
9 (1b+2+3+4+5+6)	4363	0.2-Percent	18000	582.5	599.75	592.39	600.03	0.000868	4.96	6318.13	1245.01	0.23	1
9 (1b+2+3+4+5+6)	4182	10-Percent	7990	582.4	596	590.04	596.36	0.002358	4.87	1718.18	457.62	0.27	1.93
9 (1b+2+3+4+5+6)	4182	2-Percent	11800	582.4	597.14	590.55	597.66	0.001656	5.93	2176.92	640.15	0.3	1
9 (1b+2+3+4+5+6)	4182	1-Percent	13600	582.4	597.79	591.12	598.38	0.001764	6.37	2370.28	896.17	0.31	1
9 (1b+2+3+4+5+6)	4182	0.2-Percent	18000	582.4	599.29	592.48	599.81	0.001504	6.4	4713.57	1187.32	0.3	1
9 (1b+2+3+4+5+6)	3997	10-Percent	7990	582.3	595.54	589.59	595.91	0.002506	4.94	1669.43	282.39	0.27	2
9 (1b+2+3+4+5+6)	3997	2-Percent	11800	582.3	596.82	590.02	597.36	0.001639	5.95	2153.86	525.73	0.3	1
9 (1b+2+3+4+5+6)	3997	1-Percent	13600	582.3	597.41	590.59	598.04	0.001814	6.48	2326.93	803.2	0.32	1
9 (1b+2+3+4+5+6)	3997	0.2-Percent	18000	582.3	598.75	591.89	599.47	0.001922	7.2	3968.88	1358.2	0.33	1
9 (1b+2+3+4+5+6)	3670	10-Percent	7990	582.1	595.25		595.3	0.00117	2.51	5653	1243.67	0.15	3.77
9 (1b+2+3+4+5+6)	3670	2-Percent	11800	582.1	596.76		596.82	0.001013	2.8	7649.98	1351.92	0.15	3.45


Table 13: Flood Scenario 9 with Ice Cover HEC-RAS Output (*continued*)

Scenario	River.Sta	Profile	Q.Total	Min.Ch.El	W.S..Elev	Crit.W.S.	E.G..Elev	E.G..Slope	Vel.Chnl	Flow.Area	Top.Width	Froude...Chl	Ice.Thick.Chn
9 (1b+2+3+4+5+6)	3670	1-Percent	13600	582.1	597.4		597.46	0.001011	2.86	8502.22	1396.39	0.15	3.61
9 (1b+2+3+4+5+6)	3670	0.2-Percent	18000	582.1	598.79		598.86	0.000988	3	10643.31	1779.55	0.15	3.9
9 (1b+2+3+4+5+6)	2921	10-Percent	7990	576.6	593.85		594.11	0.002182	4.44	2559.64	954.79	0.23	3.08
9 (1b+2+3+4+5+6)	2921	2-Percent	11800	576.6	595.76		595.96	0.001287	4.2	5111.49	1428.92	0.2	2.55
9 (1b+2+3+4+5+6)	2921	1-Percent	13600	576.6	596.51		596.67	0.001055	4.08	6201.24	1444.71	0.19	2.39
9 (1b+2+3+4+5+6)	2921	0.2-Percent	18000	576.6	598.06		598.19	0.000785	3.94	8928.85	2136.62	0.17	2.19
9 (1b+2+3+4+5+6)	1922	10-Percent	7990	573.7	593.54		593.58	0.000196	2.09	8257.98	1344.43	0.09	1.45
9 (1b+2+3+4+5+6)	1922	2-Percent	11800	573.7	595.49		595.52	0.000184	2.27	10949.93	1463.03	0.1	1.38
9 (1b+2+3+4+5+6)	1922	1-Percent	13600	573.7	596.23		596.27	0.000186	2.36	12141.66	1693.19	0.1	1.39
9 (1b+2+3+4+5+6)	1922	0.2-Percent	18000	573.7	597.78		597.82	0.000192	2.53	14988.84	1884.17	0.1	1.42
9 (1b+2+3+4+5+6)	833	10-Percent	7990	571.5	593.39		593.42	0.000106	2.01	7051.55	1516.47	0.08	1
9 (1b+2+3+4+5+6)	833	2-Percent	11800	571.5	595.34		595.38	0.000099	2.1	10374.31	1805.97	0.08	1
9 (1b+2+3+4+5+6)	833	1-Percent	13600	571.5	596.09		596.12	0.000098	2.14	11779.88	2068.75	0.08	1
9 (1b+2+3+4+5+6)	833	0.2-Percent	18000	571.5	597.64		597.68	0.000096	2.24	15564.63	2543.58	0.08	1
9 (1b+2+3+4+5+6)	279	10-Percent	7990	571	593.27	581.03	593.33	0.00012	2.35	5948.74	1083.92	0.1	1
9 (1b+2+3+4+5+6)	279	2-Percent	11800	571	595.23	582.78	595.29	0.00012	2.53	8758.64	2173.18	0.1	1
9 (1b+2+3+4+5+6)	279	1-Percent	13600	571	595.98	583.49	596.04	0.00012	2.6	10421.48	2286.34	0.1	1
9 (1b+2+3+4+5+6)	279	0.2-Percent	18000	571	597.53	585.08	597.59	0.00012	2.73	14338.36	2771.69	0.11	1

Attachment G  
**Bank and Channel Stabilization Strategies**

## Vegetated Coir Logs

Vegetative plugs placed in densely-packed coconut fiber rolls (Figure 1)



**Figure 1. Vegetated coir logs (NRCS 1996).**

### Issue Solution Addresses

Vegetated coir logs prevent erosion by reinforcing the streambank and acting as a natural retaining wall against water velocity. The vegetated rolls are flexible and can mold to the existing curvature of the streambank. They are also highly effective in developing stream channel banks by trapping sediment behind the fiber rolls and improving conditions for vegetation establishment on the water's edge.

### Ideal Location

Coir logs are suitable in low energy environments and work best in areas with minimal ice build-up. High energy environmental can dislodge the logs or cause the logs to break down before rooting the vegetative plugs. Gradual slopes less than 1V:2H (vertical:horizontal) are preferred.

## Design and Construction Considerations

- **Site-Specific Conditions:** Vegetated coir logs are suitable in water velocities of 8 ft/s or less.
- **Materials:** Pre-constructed coir logs, coir netting (optional), vegetated plugs (pre-rooted is preferred), rot-resistant wooden stakes, and erosion control blanket (optional). Erosion control blankets and coir netting are recommended and can reduce the need for maintenance long-term.
- **Construction:** The density of vegetated plugs depends on the fiber roll diameter (Table 1). The root system shall be placed below the water level. The stakes shall be placed on both sides of the roll every 2-4 ft, depending on anticipated water velocity.

**Table 1. Vegetated Plug Density**

Log Diameter (inch)	Vegetated Plug Density (plug/linear foot)
8	1
12	2
16	3
20	5

- **Spacing:** If the shoreline is greater than 10 ft, the coir logs shall be laced together in a continuous line with no gapping between rolls.
- **Placement:** Install the first row of the coir logs parallel to the streambank such that the top two inches of the log are visible at mean water elevation. Additional vertical tiers can be added on the bank slope for further stabilization (Table 2).

**Table 2. Interval Spacing**

Slope (V:H)	Interval Spacing (ft)
1:1	5-10
1:2 > Slope > 1:1	10-20
1:4 > Slope > 1:2	20-40

- **Maintenance:** Replacement of the rolls may be required if the log begins to break apart due to elevated water velocity or ice damage. For the first year, it is encouraged to inspect the structure after the first few floods (~ 3 visits). Monitoring can reduce to once a year after that. Over time, sediment will cover the coir logs, and vegetation will establish.

Other design considerations include installation schedule (i.e., time of year), bank preparation, trench excavation methods, backfilling, compaction and drainage.

## Permitting and Regulatory Considerations

The extent of permit requirements will depend on the location and final design of the project. Consult with your local municipality, NYSDEC, and USACE before beginning any stabilization activities.

## Rough Order of Magnitude Cost

The total cost is approximately \$1,000/20 linear ft. This price includes materials, transportation, and installation. Costs vary with design, site access, installation timeframe, supplier, and labor rates.


## Applications and Effectiveness

- Protect slopes and encourage deposition of sediment

- Coir logs expedite vegetative cover by providing stabilized medium
- Molds to existing curvature of streambank
- Minimal disturbance of streambank

## Brush Mattresses

Living ground cover of layered branch cuttings (Figure 2)



**Figure 2. Brush mattresses (NRCS 1996).**

### Issue Solution Addresses

Brush mattresses slow water velocities along the streambank and reduce erosion. The open space between the woody material allows for sediment deposition and water drainage. The build-up of sediment enhances the colonization of native plants.

## Ideal Location

Brush mattresses are best suited for perennial streams with low to medium water velocities. Constant water flow and sunny conditions will encourage the growth of the wood cuttings. Brush mattresses can be installed on slopes 1V:2H or flatter.

## Design and Construction Considerations

- **Site-Specific Conditions:** Brush mattresses are suitable in water velocities of 5 ft/s. Brush mattresses are commonly implemented with other shoreline stabilization methods to ensure proper protection. Rock bolsters provide toe stabilization against high water velocities and shear stress, Table 3. Note, shoreline protection is dependent on vegetation establishment.

**Table 2. Brush Mattresses Configuration**

Brush Mattress Type	Water Velocity (ft/sec)	Shear (lb/ft <sup>2</sup> )
Staked only without rock bolster at toe	Initial Planting: < 4.0	0.4 – 3
	Established Vegetation: < 5.0	4.0 – 7.0
Staked with rock bolster at toe	Initial Planting: < 5	0.8 – 4.1
	Established Vegetation: < 12	4.0 – 8.0

- **Materials:** Live branch cuttings of a native growing species (e.g., willow) approximately 6 to 9 ft in length, biodegradable untreated twine, dead stout stakes (minimum length of 2.5 ft), 12 gauge galvanized wire, and live fascines. Additional materials may include rock bolster and geotextile fabric for toe stabilization.
- **Placement:** First, install the live fascines in a trench (8 to 10 inches deep and wide) at the streambank base. Place the live branches into the fascines so that the basal end (where the roots grow) faces the riverbed. Drive dead stout stakes into the brush mattress approximately 12 to 18 inches apart. Lastly, wrap metal wire around each stake and pull tightly across the live branches.
- **Maintenance:** Repair of the nature-based structure may be required dependent on stream velocity, flood frequency, sediment load, and timing. For the first year, inspect the structure for loose branches or live fascines after the first few floods (~ 3 visits). Add additional stakes as needed. For the first two dry seasons, water the branches every two weeks if a soaking rain does not occur during a three-week timeframe.

Other design considerations include installation schedule (i.e., time of year), bank preparation, stock type, trench excavation methods, backfilling, compaction and drainage.

## Permitting and Regulatory Considerations

The extent of permit requirements will depend on the location and final design of the project. Consult with your local municipality, NYSDEC, and USACE before beginning any stabilization activities.

## Rough Order of Magnitude Cost

Total cost ranges from \$38 to \$84/10 ft<sup>2</sup>. This price includes materials, transportation, and installation. Costs vary with design, site access, installation timeframe, supplier and labor rates.

### **Applications and Effectiveness**

- Applicable for steep fast-flowing streams
- Captures sediment and encourages vegetation establishment
- Requires good soil to stem contact and moist conditions for branches to grow
- Encourages conditions for colonization of native vegetation
- Immediate protection of streambank after installation

## References

Natural Resources Conservation Service (NRCS). [date unknown]. Guidance on Agroforestry System Design – Riparian Forest Buffer. In: Sustaining Agroforestry Systems for Farms and Ranches. Washington DC (US): United States Department of Agriculture (USDA). Available from:  
[https://www.nrcs.usda.gov/wps/portal/nrcs/detailfull/national/landuse/forestry/sustain/guidance/?cid=nrcsdev11\\_009302](https://www.nrcs.usda.gov/wps/portal/nrcs/detailfull/national/landuse/forestry/sustain/guidance/?cid=nrcsdev11_009302).

Natural Resources Conservation Service (NRCS). 1996. Engineering Field Handbook - Chapter 16: Streambank and Shoreline Protection. Washington DC (US): United States Department of Agriculture (USDA). Available from: [https://efotg.sc.egov.usda.gov/references/public/IA/Chapter-16\\_Streambank\\_and\\_Shoreline\\_Protection.pdf](https://efotg.sc.egov.usda.gov/references/public/IA/Chapter-16_Streambank_and_Shoreline_Protection.pdf).

**WISCONSIN SUPPLEMENT**  
**CHAPTER 16 - ENGINEERING FIELD HANDBOOK**  
**STREAMBANK AND SHORELINE PROTECTION**  
**STANDARD 580**  
**COMPANION DOCUMENT 580-10**  
**Allowable Velocity and Maximum Shear Stress**

Type of Treatment	Allowable Shear lb/sq ft	Velocity ft/sec
<b>Brush Mattresses<sup>1</sup></b>		
Staked only w/ rock riprap toe (initial)	0.8 - 4.1	5
Staked only w/ rock riprap toe (grown)	4.0 - 8.0	12
<b>Coir Geotextile Roll<sup>2</sup></b>		
Roll with coir rope mesh staked only without rock riprap toe	0.2 - 0.8	< 5
Roll with Polypropylene rope mesh staked only without rock riprap toe	0.8 - 3.0	< 8
Roll with Polypropylene rope mesh staked and with rock riprap toe	3.0 - 4.0	< 12
<b>Live Fascine<sup>3</sup></b>		
LF Bundle w/ rock riprap toe	2.0 - 3.1	8
<b>Soils<sup>4</sup></b>		
Fine colloidal sand	0.02-0.03	1.5
Sandy loam (noncolloidal)	0.03-0.04	1.75
Alluvial silt (noncolloidal)	0.045-0.05	2
Silty loam (noncolloidal)	0.045-0.05	1.75-2.25
Firm loam	0.075	2.5
Fine gravels	0.075	2.5
Stiff clay	0.26	3-4.5
Alluvial silt (colloidal)	0.26	3.75
Graded loam to cobbles	0.38	3.75
Graded silts to cobbles	0.43	4
Shales and hardpan	0.67	6
<b>Gravel/Cobble<sup>4</sup></b>		
1-inch	0.33	2.5-5
2-inch	0.67	3-6
6-inch	2	4-7.5
12-inch	4	5.5-12
<b>Vegetation<sup>4</sup></b>		
Class A turf (ret class)	3.7	6-8
Class B turf (ret class)	2.1	4-7
Class C turf (ret class)	1	3.5
Retardance Class D	0.6	Design of roadside channels HEC-15
Retardance Class E	0.35	
Long native grasses	1.2-1.7	4-6
Short native and bunch grass	0.7-0.95	3-4

Type of Treatment	Allowable Shear lb/sq ft	Velocity ft/sec
<b>Soil Bioengineering<sup>4</sup></b>		
Wattles	0.2-1.0	3
Reed fascine	0.6-1.25	5
Coir roll	3-5	8
Vegetated coir mat	4-8	9.5
Live brush mattress (initial)	0.4-4.1	4
Live brush mattress (grown)	3.90-8.2	12
Brush layering (initial/grown)	0.4-6.25	12
Live fascine	1.25-3.10	6-8
Live willow stakes	2.10-3.10	3-10
<b>Hard Surfacing<sup>4</sup></b>		
Gabions	10	14-19
Concrete	12.5	>18
<b>Boulder Clusters<sup>5</sup></b>		
Boulder		
Very large (>80-inch diameter)	37.4	25
Large (>40-in diameter)	18.7	19
Medium (>20-inch diameter)	9.3	14
Small (>10-inch diameter)	4.7	10
Cobble		
Large (>5-inch diameter)	2.3	7
Small (>2.5-inch diameter)	1.1	5
Gravel		
Very Course (>1.25-inch diameter)	0.54	3
Course (>.63-inch diameter)	0.25	2.5

<sup>1</sup> Brush mattresses (ERDC TN EMRRP-SR-23): <http://el.erdc.usace.army.mil/emrrp/pdf/sr23.pdf>.

<sup>2</sup> Coir Geotextile roll (ERDC TN EMRRP-SR-04): <http://el.erdc.usace.army.mil/emrrp/pdf/sr04.pdf>.

<sup>3</sup> Live Fascine (ERDC TN EMRRP-SR-31): <http://el.erdc.usace.army.mil/emrrp/pdf/sr31.pdf>.

<sup>4</sup> Stream Restoration Materials (ERDC TN EMRRP-SR-29): <http://el.erdc.usace.army.mil/emrrp/pdf/sr29.pdf>.

<sup>5</sup> Boulder Clusters (ERDC TN EMRRP-SR-11): <http://el.erdc.usace.army.mil/emrrp/pdf/sr11.pdf>.

## Additional Sources:

Wisconsin Department of Transportation, Erosion Control - Product Acceptability List (PAL):  
<http://www.dot.wisconsin.gov/library/research/docs/finalreports/tau-finalreports/erosion.pdf>

Texas Department of Transportation, Approved Products List:  
<http://www.dot.state.tx.us/mnt/erosion/contents.htm>

## Reference:

Natural Resources Conservation Service (NRCS). 2009. Engineering Field Handbook - Chapter 16: Streambank and Shoreline Protection - Wisconsin Supplement. Washington DC (US): United States Department of Agriculture (USDA). Report No.: EFH Notice 210-WI-119. Available from: [https://www.nrcs.usda.gov/Internet/FSE\\_DOCUMENTS/nrcs142p2\\_024948.pdf](https://www.nrcs.usda.gov/Internet/FSE_DOCUMENTS/nrcs142p2_024948.pdf).

Attachment H  
**Project Cost Estimate**

Project: Buffalo Creek Floodplain Reconnection  
 Owner: Buffalo Niagara Waterkeepers  
 County: Erie  
 Municipality: Town of West Seneca

PROJECT COST ESTIMATE						
Item/Description		Qty	Units	Unit Cost	Amount	
<b>Flood Benches</b>						
<i>Formation of flood bench</i>						
Excavation and Material Disposal		76,000	CY	\$ 25	\$ 1,900,000	
Clearing/Grubbing		9	AC	\$ 20,000	\$ 180,000	
Seeding and/or planting		1	LS	\$ 614,000	\$ 614,000	
Temporary sediment and erosion control		2,700	LF	\$ 88	\$ 237,000	
<i>Land acquisition</i>		24	AC	\$ 3,500	\$ 83,000	
<i>Walking Trail Restoration</i>						
Earth Excavation		1500	CY	\$ 35.00	\$ 53,000	
Compacted Granular Fill		900	CY	\$ 42.00	\$ 38,000	
Fine Grading & Compacting		3,600	SY	\$ 5.00	\$ 18,000	
<i>Bank Stabilization Features</i>		2,700	LF	\$ 100	\$ 270,000	
<i>Allowance for utility owner requirement</i>						
<b>Construction Cost Subtotal</b>						\$ 3,443,000
General Conditions / Project Management		10%				\$ 345,000
Contractor OH&P		15%				\$ 569,000
Construction Contingency		30%				\$ 1,308,000
<b>Total Construction Cost</b>						<b>\$ 5,665,000</b>
<b>Summary</b>						
Construction Costs						\$ 5,665,000
Engineering (Not including additional modeling & ice jam analysis)		10%				\$ 567,000
Construction Management		10%				\$ 567,000
<b>Total</b>						<b>\$ 6,799,000</b>